

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT



<b>APPLICATION FOR PERMIT TO DRILL</b>						<b>1. WELL NAME and NUMBER</b> Tully 16-9-36D					
<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						<b>3. FIELD OR WILDCAT</b> WILDCAT					
<b>4. TYPE OF WELL</b> Oil Well      Coalbed Methane Well: NO						<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b>					
<b>6. NAME OF OPERATOR</b> WHITING OIL & GAS CORPORATION						<b>7. OPERATOR PHONE</b> 303 390-4095					
<b>8. ADDRESS OF OPERATOR</b> 1700 Broadway, Suite 2300, Denver, CO, 80290						<b>9. OPERATOR E-MAIL</b> scottw@whiting.com					
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> ML-52222			<b>11. MINERAL OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>			<b>12. SURFACE OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>					
<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b> Mark Austin						<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b> 435 653 2972					
<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b> PO Box 301, ,						<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>					
<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>			<b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b> YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			<b>19. SLANT</b> VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>					
<b>20. LOCATION OF WELL</b>		<b>FOOTAGES</b>		<b>QTR-QTR</b>	<b>SECTION</b>	<b>TOWNSHIP</b>	<b>RANGE</b>	<b>MERIDIAN</b>			
LOCATION AT SURFACE		860 FNL 856 FWL		NWNW	36	16.0 S	9.0 E	S			
Top of Uppermost Producing Zone		860 FNL 856 FWL		NWNW	36	16.0 S	9.0 E	S			
At Total Depth		860 FNL 856 FWL		NWNW	36	16.0 S	9.0 E	S			
<b>21. COUNTY</b> EMERY				<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 856		<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 640					
				<b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 5280		<b>26. PROPOSED DEPTH</b> MD: 10517 TVD: 10517					
<b>27. ELEVATION - GROUND LEVEL</b> 5873				<b>28. BOND NUMBER</b> RLB 0004585		<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> Municipal Water from Elmo					
<b>Hole, Casing, and Cement Information</b>											
<b>String</b>	<b>Hole Size</b>	<b>Casing Size</b>	<b>Length</b>	<b>Weight</b>	<b>Grade &amp; Thread</b>	<b>Max Mud Wt.</b>	<b>Cement</b>	<b>Sacks</b>	<b>Yield</b>	<b>Weight</b>	
SURF	17.5	13.375	0 - 2100	54.5	L-80 LT&C	9.0	Unknown	760	2.94	11.5	
							Unknown	610	1.2	15.6	
I1	13.375	9.625	0 - 6300	47.0	L-80 LT&C	9.4	Unknown	330	2.16	12.2	
							Unknown	560	1.29	14.2	
							Unknown	620	2.15	12.2	
PROD	8.5	7	0 - 10517	29.0	L-80 LT&C	9.4	Unknown	425	2.15	12.2	
							Unknown	570	1.29	14.2	
<b>ATTACHMENTS</b>											
<b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>											
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER						<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)						<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)						<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
<b>NAME</b> Larry Brown				<b>TITLE</b> CEP H&B Petroleum Consultants				<b>PHONE</b> 307 237-2310			
<b>SIGNATURE</b>				<b>DATE</b> 08/27/2012				<b>EMAIL</b> ld_brown@bresnan.net			
<b>API NUMBER ASSIGNED</b> 43015500030000				<b>APPROVAL</b> <div style="text-align: center;">           Permit Manager       </div>							

RECEIVED: October 15, 2012

**Whiting Oil & Gas Corporation**  
**Poison Spring\_16-9-36D Drill Plan**  
**Vertical – Manning Canyon Well**  
**May 2, 2012**

**Summary:**

The Poison Spring\_16-9-36D well will be a vertical Manning Canyon well. The well will be drilled to 10,517' TD and 7" casing will be run and cemented.

**Surface Location:** 36-T16S-R9E  
860' FNL 856' FWL  
Emery County, Utah

**DRILLING PROGRAM**

**1. ESTIMATED TOPS OF GEOLOGICAL MARKERS:**

Ground Level 5,871' Estimated KB 5,893' (22')

<b><u>Formation</u></b>	<b><u>MD</u></b>	<b><u>Lithology</u></b>	<b><u>Hazard</u></b>
Mancos	Surface	SH-SS	
Ferron	1,092'	SS-COAL-SH	
Dakota	1,982'	SS-SI-SH	
Morrison	2,786'	SI-SH-SS	
Summerville	3,329'	SS-SH	
Curtis	3,688'	SS	
Entrada	3,909'	SS-SI	
Carmel	4,456'	SH-SS	
Navajo	5,075'	SS	Water, CO2
Kayenta	5,530'	SS	
Wingate	5,662'	SS	
Chinle	6,016'	SS-SH	
Moenkopi	6,337'	SS-SH-LS	
Kaibab	7,425'	SS-SH	
White Rim SS	7,602'	SS-SH	
Elephant Canyon	8,292'	LS-DOL	
Manning Canyon	9,664'	DOL-SS-SH	Gas
Humbug Fm	10,417'	LS-DOL	
TD	10,517'		

## 2. PRESSURE CONTROL EQUIPMENT

**A. Type:** 13-5/8" 5,000 psi double gate hydraulic BOP with 13-5/8" 5,000 psi annular preventer with 5,000 psi Casinghead and 5,000 psi Tubinghead.

### **B. Testing Procedure:**

The annular preventer will be pressure tested to 50% of stack rated working pressure for ten (10) minutes or until provisions of test are met, whichever is longer. The BOP, choke manifold, and related equipment will be pressure tested to approved BOP stack working pressure (if isolated from surface casing by a test plug) or to 70% of surface casing internal yield strength (if BOP is not isolated by a test plug). Pressure will be maintained for ten (10) minutes or until the requirements of the test are met, whichever is longer. At a minimum, the Annular and Blow-Out Preventer pressure tests will be performed:

1. When the BOPE is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

Annular will be function tested weekly, and pipe & blind rams activated each trip, but not more than once per day. All BOP drills & tests will be recorded in IADC driller's log.

### **C. Choke Manifold Equipment:**

All choke lines will be straight lines whenever possible at turns, tee blocks will be used or will be targeted with running tees, and will be anchored to prevent whip and vibration.

### **D. Accumulator:**

Accumulator will have sufficient capacity to open hydraulically-controlled choke line valve (if so equipped), close all rams plus annular preventer, and retain a minimum of 200 psi above precharge on the closing manifold without the use of closing unit pumps. The fluid reservoir capacity will be double accumulator capacity and the fluid level will be maintained at manufacturer's recommendations. Accumulator precharge pressure test will be conducted prior to connecting the closing unit to the BOP stack.

### **E. Miscellaneous Information:**

Choke manifold and BOP extension rods with hand wheels will be located outside rig sub-structure. Hydraulic BOP closing unit will be located at least twenty-five (25) feet from the wellhead but readily accessible to the driller. Exact locations and configurations of the hydraulic BOP closing unit will depend upon the particular rig contracted to drill this hole.

A flare line will be installed after the choke manifold with the discharge point of the flare line to a separate pit located at least 125 feet away from the wellbore and any existing production facilities.

A volume monitoring system with alarms will be used to monitor pit gains/losses along with visual backup.

**3. PROPOSED CASING PROGRAM****A. Casing Program: All New**

Hole Size	Casing Size	Wt./Ft.	Grade	Joint	Coupling OD	Burst (psi)	Collapse (psi)	Tension (Body/Joint) (klbs)	Depth Set (md)
17-1/2"	13-3/8"	54.50	J-55	ST&C	14.375"	2,730	1,130	853/514	0 – 2,100'
12-1/4"	9-5/8"	47	L-80	LT&C	10.625"	6,870	4,750	1,086/893	0 – 6,300'
8-1/2"	7"	29	L-80	LT&C	7.656"	8,160	7,020	676/587	0 – 10,517'

13-3/8" surface casing will have centralizers as follows:

1. Install a bowspring centralizer at the first and second collars above the guide shoe.
2. Install one bowspring centralizer every third joint above the second collar.
3. Centralizer and basket placed 120' below the surface (or at the bottom of the third joint below the surface).
4. Centralizer and basket placed 80' below the surface (or at the bottom of the second joint below the surface).

9-5/8" intermediate casing will have centralizers as follows:

1. Install a bowspring centralizer at the first and second collars above the guide shoe.
2. After that centralize every third joint to surface with single bow spring centralizers

7" production casing will have centralizers as follows:

1. Install a bowspring centralizer at the first and second collars above the guide shoe.
2. After that centralize every third joint to surface with single bow spring centralizers.

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

**B. Casing Design Parameters:****Surface Casing**

Interval	Size	Wt	Grade	Burst (psi) <sup>a</sup> /SF	Collapse (psi) <sup>b</sup> /SF	Tension (klb) <sup>c</sup> /SF
0' – 2,100'	13-3/8"	54.50 lb/ft	J-55	2,730/1.87	1,130/1.15	514/5.21

- a. based on frac gradient at shoe of 14.0 ppg
- b. based on full evacuation with 9.0 ppg fluid on backside
- c. based on casing string weight in 9.0 ppg mud

String Weight in 9.0 ppg mud ≈ 98,724 lbs

**Intermediate Casing**

Interval	Size	Wt	Grade	Burst (psi) <sup>a</sup> /SF	Collapse (psi) <sup>b</sup> /SF	Tension (klb) <sup>c</sup> /SF
0' – 6,300'	9-5/8"	47.0 lb/ft	L-80	6,870/3.69	4,750/1.54	893/3.52

- a. based on frac gradient at shoe of 14.0 ppg
- b. based on full evacuation with 9.4 ppg pore pressure on backside
- c. based on casing string weight in 9.4 ppg mud  
String Weight in 9.4 ppg mud ≈ 253,606 lbs.

**Production Casing**

Interval	Size	Wt	Grade	Burst (psi) <sup>a</sup> /SF	Collapse (psi) <sup>b</sup> /SF	Tension (klb) <sup>c</sup> /SF
0' – 10,517'	7"	27.0 lb/ft	L-80	8,160/1.17	7,020/1.37	587/2.25

- a. based on 7,000 psi frac pressure.
- b. based on full evacuation with 9.4 ppg pore pressure on backside
- c. based on casing string weight in 9.4 ppg mud  
String Weight in 9.4 ppg mud ≈ 261,223 lbs.



**4. PROPOSED CEMENTING PROGRAM****Surface Casing – 13-3/8" Casing:** TOC Surface, (100% Excess)

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	XC (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
13-3/8"	Lead	1,600'	Lead Cement Rockies LT; - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 0.25 lbm/sk Kwik Seal (Lost Circulation Additive)	760	100	11.5	2.94
13-3/8"	Tail	500'	Tail Cement Premium Cement; - 94 lbm/sk Premium Cement (Cement) - 2% Calcium Chloride (Accelerator) - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive)	610	100	15.6	1.20

A cement top job is required if cement fallback is greater than 10' below ground level.

**Intermediate Casing – 9-5/8" Casing:** TOC Surface, (Stage Tool at 3,300' – Stage\_1 - 50% Excess, Stage\_2 – 50% Excess)

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	XC (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
9-5/8"	Stage_1 – Lead	1,500'	First Stage Lead Cement ECONOCER; - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 1 % HR-5 (Retarder) - 0.2 % Super CBL (Expander)	330	50	12.2	2.16
9-5/8"	Stage_1 – Tail	1,500'	First Stage Tail Cement EXTENDACER; - 0.5 % HR-5 (Retarder) - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 3 lbm/sk Gilsonite (Lost Circulation Additive)	560	50	14.2	1.29
9-5/8"	Stage_2 – Lead	3,300'	Second Stage Primary Cement ECONOCER; - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 0.5 % HR-5 (Retarder) - 0.2 % Super CBL (Expander)	620	50	12.2	2.15

Cement volumes for the 9-5/8" Production Casing will be calculated to provide a top of cement to Surface.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

**Production Casing – 7" Casing: TOC Surface, (35% Excess)**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	XC (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
7"	Lead	6,300'	Lead Cement ECONOCEM; - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 0.8 % HR-5 (Retarder) - 0.2 % Super CBL (Expander)	425	35	12.2	2.15
7"	Tail	4,217'	Tail Cement EXTENDACEM; - 0.4 % HR-5 (Retarder) - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive)	570	35	14.2	1.29

Cement volumes for the 7" Production Casing will be calculated to provide a top of cement to Surface.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

**5. MUD PROGRAM**

<u>Depth (MD)</u>	<u>Mud System</u>	<u>MW</u>	<u>PV</u>	<u>YP</u>	<u>FL</u>
0 -2,100'	Water, Gel/Lime Sweeps	8.4 – 9.0	2 - 20	2 - 18	NC
2,100' – 6,300'	3% KCL Water/Polymer	8.4 – 9.4	10 - 28	6 - 18	6 - 10
6,300' – 10,517'	3% KCL Water/Polymer	8.4 – 9.4	14 - 32	10 - 22	4 - 10

## 6. EVALUATION PROGRAM

Cores: 60' of core planned from 6,337' to 6,397'.  
60' of core planned from 9,664' to 9,754'.

DST: None planned

Surveys: Deviation surveys every 500' to TD in both surface, intermediate and production hole.

Mud Logger:

Samples: 30' samples surface to 10,517'

Open Hole Logging Program: Triple Combo 10,517' to Surface

## 7. ABNORMAL CONDITIONS

No abnormal pressures are anticipated. No H<sub>2</sub>S gas is anticipated.

Anticipated bottom hole pressure is 4,554 psi (0.433 psi/ft) at 10,517' TVD in the Humbug and the maximum anticipated surface pressure equals approximately 2,240 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

## 8. ANTICIPATED STARTING DATES


### A. Anticipated Starting Dates:

Dirt work startup: July 2012

Spud: July 2012

Duration: 25 – 35 days

# Utah Division of Water Rights



Point Location: S 860 ft, E 856 ft, from the NW Corner, Section 36, Township 16S, Range 9E, SL B&M




Search all of Utah.gov »

# Utah Division of Water Rights



## Output Listing for Points of Diversion



## Water Rights

WR Number	Diversion Type/Location	Well Log	Status	Priority	Uses	CFS	ACFT	Owner Name
<a href="#">0991005M00</a>	Underground	<a href="#">well info</a>	A			0.000	0.000	USA BUREAU OF RECLAMATION
	N1584 W84 S4 25 16S 9E SL							302 E 1860 S
<a href="#">91-1684</a>	Point to Point		P	18690000	S	0.000	0.000	JOSEPHINE M. LUNDY
	N660 W660 SE 25 16S 9E SL							CLEVELAND UT 84518
<a href="#">91-1691</a>	Point to Point		P	18690000	S	0.000	0.000	RALPH L. LUNDY
	N660 E660 S4 25 16S 9E SL							CLEVELAND UT 84518
<a href="#">91-1698</a>	Point to Point		P	18690000	S	0.000	0.000	RALPH L. LUNDY
	N660 E660 SW 30 16S 10E SL							CLEVELAND UT 84518
<a href="#">91-1712</a>	Point to Point		P	18690000	S	0.000	0.000	ARVEL & GEORGINA HANSEN
	S660 W660 N4 31 16S 10E SL							ELMO UT 84521
<a href="#">91-3065</a>	Point to Point		P	18690000	S	0.000	0.000	M. JAMES AND DORIS ATWOOD
	S660 W1980 E4 25							CLEVELAND UT 84518

<a href="#">91-3134</a>	16S 9E SL Point to Point S660 E660 NW 31 16S 10E SL	P	18690000 S	0.000 0.000	N. C. OVESON CLEVELAND UT 84518
<a href="#">91-3160</a>	Point to Point S660 E1980 W4 26 16S 9E SL	P	18690000 S	0.011 0.000	PRICE FIELD OFFICE USA BUREAU OF LAND MANAGEMENT 125 SOUTH 600 WEST
<a href="#">91-1684</a>	Point to Point N660 W660 SE 25 16S 9E SL	P	18690000 S	0.000 0.000	JOSEPHINE M. LUNDY CLEVELAND UT 84518
<a href="#">91-1691</a>	Point to Point N660 E660 S4 25 16S 9E SL	P	18690000 S	0.000 0.000	RALPH L. LUNDY CLEVELAND UT 84518
<a href="#">91-1698</a>	Point to Point N660 E660 SW 30 16S 10E SL	P	18690000 S	0.000 0.000	RALPH L. LUNDY CLEVELAND UT 84518
<a href="#">91-3065</a>	Point to Point N660 W660 SE 25 16S 9E SL	P	18690000 S	0.000 0.000	M. JAMES AND DORIS ATWOOD CLEVELAND UT 84518
<a href="#">91-4193</a>	Underground N520 E1130 SW 36 16S 9E SL	<a href="#">well info</a> P	19790320 S	0.015 0.000	JAMES B. JARVIS BOX 38
<a href="#">91-4194</a>	Underground S70 W1220 N4 01 17S 9E SL	T	19780323 DIS	0.015 0.000	JAMES O. & PRISCILLA FAITH HAWKINS CLEVELAND UT 84518
<a href="#">91-4197</a>	Underground N1730 E275 SW 30 16S 10E SL	T	19790515 DIS	0.015 0.000	RALPH L. LUNDY CARBON-EMERY ROUTE
<a href="#">91-4219</a>	Underground S120 W510 N4 01 17S 9E SL	T	19800226 DIS	0.015 0.000	GAROLD K. HORROCKS BOX 246
<a href="#">91-4220</a>	Underground S100 W220 N4 01 17S 9E SL	T	19800226 DIS	0.015 0.000	GAROLD K. HORROCKS BOX 246
<a href="#">91-4221</a>	Underground S80 E200 N4 01 17S 9E SL	T	19800226 DIS	0.015 0.000	GAROLD K. HORROCKS BOX 246
<a href="#">91-4228</a>	Underground N70 E1240 SW 36 16S 9E SL	T	19800814 DIS	0.015 0.000	DORENE HORROCKS FREMONT UT 84727
<a href="#">91-4264</a>	Underground S752 E495 NW 31 16S 10E SL	<a href="#">well info</a> P	19810506 IS	0.015 0.000	ADELBERT BLAKE SMITH BOX 383
<a href="#">91-5019</a>	Surface S45 E40 NW 06 17S 10E SL	T	19990111 I	0.000 40.400	STEVEN K. ALLRED P.O. BOX 368



T16S, R9E, S.L.B.&M.

WHITTING OIL & GAS CORP.



Well location, TULLY #16-9-36D, located as shown in the NW 1/4 NW 1/4 of Section 36, T16S, R9W, S.L.B.&M., Emery County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION LOCATED AT THE NORTHWEST CORNER OF SECTION 36, T16S, R9E, S.L.B.&M., TAKEN FROM THE ELMO QUADRANGLE, UTAH, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5991 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

KAY ROBERT L.  
REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH

REVISED: 08-01-2012


UTAH ENGINEERING & LAND SURVEYING  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 12-20-11	DATE DRAWN: 12-23-11
PARTY B.B. J.G. B.L.B.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE WHITTING OIL & GAS CORP.	

LEGEND:

- 90° SYMBOL
- PROPOSED WELL HEAD.
- SECTION CORNERS LOCATED.

NAD 83 (SURFACE LOCATION)
LATITUDE = 39°23'39.19" (39.394214)
LONGITUDE = 110°52'05.93" (110.868314)
NAD 27 (SURFACE LOCATION)
LATITUDE = 39°23'39.30" (39.394250)
LONGITUDE = 110°52'03.34" (110.867594)





**Tully 16-9-36  
NWNW Sec. 36, T16S, R9E  
Emery County, Utah  
Fee Minerals**

**Whiting Oil and Gas Corporation**

**Related Surface Information**

- 1) **CURRENT SURFACE USE:** Livestock Grazing.
- 2) **PROPOSED SURFACE DISTURBANCE:**
  - a) The road will be crown and ditch. Water wings will be constructed on the access road as needed.
  - b) The topsoil will be windrowed and respread in the borrow area.
  - c) New construction and upgraded road to be constructed will be approximately 6557 feet in length, 25 feet wide.
  - d) All equipment and vehicles will be confined to the access road, pad and area specified in the APD.
- 3) **LOCATION OF EXISTING WELLS:**

Existing oil, gas and water wells within one (1) mile radius of proposed well:  
Producing Wells = 0  
Plugged and Abandoned wells = 0  
Water Wells = see attached map and list

Water for drilling will be obtained from the Town of Elmo, Utah municipal water supply.
- 4) **EXISTING/PROPOSED FACILITIES FOR PRODUCTIVE WELL:**
  - a) There are no existing facilities that will be utilized for this well.
  - b) Upgrade and maintain access roads and drainage control structures (e.g., culverts, drainage dips, ditching, etc.) as necessary to prevent soil erosion and accommodate safe, year-round traffic.
- 5) **CONSTRUCTION MATERIALS:**

Native soil from road and location will be used for construction materials along with gravel and/or scoria road base material. In the event that conditions should necessitate graveling of all or part of the access road and location, surfacing materials will be purchased from commercial suppliers in the marketing area.

**6) METHODS FOR HANDLING WASTE DISPOSAL:**

- a) The reserve pit will be designed to prevent the collection of surface runoff and will be constructed with a minimum of  $\frac{1}{2}$  the total depth below the original ground surface on the lowest point within the pit. The pit will be lined with a 9-mil polyethylene to prevent leakage of fluids. The liner will be rolled into place and secured at the ends, i.e. buried on top of the pit berms. Prior to use, the reserve pit will be fenced on three sides; the fourth side will be fenced at the time the rig is removed. Drilling fluids, cuttings and produced water will be contained in the reserve pit (trash will be placed in the trash cage). Fluids in the reserve pit will be allowed to evaporate prior to pit burial.
- b) Garbage and other trash will be contained in a portable trash cage and hauled off the location to an authorized disposal site. Any trash on the pad will be cleaned up prior to the rig move off location and hauled to an authorized disposal site.
- c) Sewage will be handled in Portable Toilets.
- d) Produced water will be placed in the reserve pit for a period not to exceed ninety days after initial production. Any hydrocarbons produced during completion work will be contained in test tanks and removed from location at a later date.
- e) Water from the reserve pit may be used for drilling of additional wells. The water will be trucked along access roads as approved in pertinent APD's.

**7) ANCILLARY FACILITIES:**

There will be no ancillary facilities associated with this project.

**8) SURFACE RECLAMATION PLANS:**

Backfilling of the pits will be done when dry. In the event of a dry hole, the location will be re-contoured, the topsoil will be distributed evenly over the entire location, and the seedbed prepared

- a) Seed will be planted after September 15<sup>th</sup>, and prior to ground frost, or seed will be planted after the frost has left and before May 15<sup>th</sup>. Slopes to steep for machinery will be hand broadcast and raked with twice the specified amount of seed.
  1. The construction program and design are on the attached cut, fill and cross sectional diagrams.
  2. Prior to construction, all topsoil will be removed from the entire site and stockpiled. Topsoil for this site is the first 6 inches of soil materials.
  3. After the location has been reshaped and after redistributing the topsoil, the operator will rip and scarify the drilling platform and access road on the contour, to a depth of at least 12 inches.
- b) Rehabilitation will begin upon the completion of the drilling. Complete rehabilitation will depend on weather conditions and the amount of time required to dry the reserve pit.

2. All rehabilitation work including seeding will be completed as soon as weather and the reserve pit conditions are appropriate.
3. Landowner will be contacted for rehabilitation requirements.

**9) SURFACE OWNERSHIP:**

**Mark Austin**

PO Box 301


Cleveland Utah 84513

Phone 435-653-2992

**10) OTHER INFORMATION:**

- a) The surface soil consists of clay, and silt.
- b) Flora - vegetation consists of the following: Sagebrush, Juniper and prairie grasses.
- c) Fauna - antelope, deer, coyotes, raptors, small mammals, and domestic grazing animals.
- d) Current surface uses – Livestock grazing and mineral exploration and production.

CONFIDENTIAL



The location of the rams, drilling spool (if used) and the size and location of the valves may vary depending on the rig used. However, all equipment will meet BLM and Utah Division of Oil, Gas and Mining Specifications.



## WHITING OIL &amp; GAS CORP.

## TYPICAL CROSS SECTIONS FOR

TULLY #16-9-36D

SECTION 36, T16S, R9E, S.L.B.&amp;M.

860' FNL 856' FWL


FIGURE #2

DATE: 12-23-11

DRAWN BY: B.L.B.

REVISED: 08-01-12

1" = 40'  
X-Section  
Scale  
1" = 100'



## NOTE:

Topsoil should not be  
Stripped Below Finished  
Grade on Substructure Area.

APPROXIMATE ACREAGES  
WELL SITE DISTURBANCE =  $\pm 3.267$  ACRES

\* NOTE:  
FILL QUANTITY INCLUDES  
5% FOR COMPACTION

APPROXIMATE YARDAGES

(6") Topsoil Stripping = 2,300 Cu. Yds.  
Remaining Location = 15,210 Cu. Yds.  
TOTAL CUT = 17,510 CU.YDS.  
FILL = 13,280 CU.YDS.

EXCESS MATERIAL = 4,230 Cu. Yds.  
Topsoil & Pit Backfill = 4,000 Cu. Yds.  
(1/2 Pit Vol.)  
EXCESS UNBALANCE = 230 Cu. Yds.  
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

RECEIVED: August 23, 2012



**THIS AGREEMENT** is made and entered into this **15<sup>th</sup>** day of **May, 2012** by and between **Mark D. Austin and Angela Austin, a/k/a Angie Austin, husband and wife**, whose address is **P.O. Box 301, Cleveland, UT 84518-0301**, hereinafter referred to as "Grantor" whether one or more, and **Whiting Oil and Gas Corporation**, whose address is **1700 Broadway, Ste. 2300, Denver, CO 80290-2300**, hereinafter referred to as "Grantee".

**WHEREAS**, Grantor is the surface owner of the following described lands in **Emery County, Utah**:

**Township 16 South, Range 9 East, S.L.B.&M.**  
**Section 36: NW/4NE/4 and NW/4**

(hereinafter referred to as the "Lands") and

**WHEREAS**, Grantee desires to enter onto and cross such Lands for the purpose of drilling the following oil and/or gas well:

Well Name	Lands	Section	Township	Range	County
<b>Poison Spring #16-9-36D</b>	<b>NW/4NW/4</b>	<b>36</b>	<b>16 South</b>	<b>9 East</b>	<b>Emery</b>

(hereinafter referred to as the "Drill Site").

**NOW THEREFORE**, for and in consideration of the mutual promises and covenants herein contained, and other good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged, the parties hereto agree as follows:

- I. Grantee and its assigns or agents shall have the right to locate an access road across the subject Lands, and shall have the unrestricted right to move and install pipelines, derricks, drilling tools, vehicles and all other machinery and equipment necessary or incident to the drilling, testing, completion and operation of an oil and/or gas well at the Drill Site.
- II. Grantee shall pay to Grantor the sum of [REDACTED] for the surface damages for the one well for the Drill Site location and the sum of [REDACTED] for the access road across the subject Lands to the Drill Site location. This onetime payment to Grantor is for damages and non-restricted use of the access road and Drill Site location. Prior to commencement of actual operations of constructing or reconstructing the access road on said Lands, the sums, settlement and payments agreed to in this Paragraph II are due and payable, or this Agreement terminates with respect to both Grantor and Grantee. If payments provided for herein have not been made within one year of the date of this Agreement, this agreement shall not terminate.
- III. This Agreement and the rights granted herein are effective on the date of execution by Grantor and shall continue in full force and effect so long as operations are conducted on the wellsite.
- IV. Cattle guards or gates will be constructed, if requested by Grantor, at all places where they go through. The existing fences and gates will be kept closed at all times except when opened for passage of traffic.
- V. If there is any fill used for roads constructed across any drainage, then culverts will be used for the free flow of water through said drainage.
- VI. If the access road departs from existing established roadways and new construction is required, topsoil will be segregated and stockpiled for replacement during reclamation activities.
- VII. It is understood that any road constructed across the said Lands shall not exceed **thirty three (33) feet** in width without the prior approval of Grantor.

- IX.** It is expressly understood that this settlement is only for construction and unrestricted use of an access road and Drill Site location and it is not a settlement for any damages to contiguous property, personal property of the Grantor or a release of any personal injuries that may be sustained by reason of the operations carried on by the oil and gas lessee or his agent.
- X.** Both the Grantor and Grantee may assign this Agreement.
- XI.** This Agreement shall be binding upon the Parties hereto, their heirs, successors and assigns, and shall run with the Lands.
- XII.** This Agreement constitutes the entire agreement between the Parties and supersedes all prior agreements and understandings, both written and oral, between the Parties with respect to the subject matter hereof. This Agreement may only be amended, modified, or supplemented by a written instrument signed by all the Parties expressly stating that such instrument is intended to amend, modify or supplement this Agreement.
- XIII.** This Agreement may be executed in any number of counterparts, each of which shall be deemed an original, and all of which together shall be considered one and the same document.
- XIV.** If at any time subsequent to the date hereto any provision of this Agreement shall be held by any court of competent jurisdiction to be illegal, void or unenforceable, such provision shall be of no force and effect, but the illegality or unenforceability of such provision shall have no effect upon and shall not impair the enforceability of the other provisions of this Agreement.
- XV.** The Parties to this Agreement shall also execute a Memorandum evidencing the execution of this Agreement. Said Memorandum of Agreement may be recorded in the appropriate County Recorder's Office to provide notice of the existence of this Agreement.
- XVI.** Grantee agrees to use the attached road route to the wellsite proposed by the Grantor, which is approximately 4,500 feet in length and will be determined by and subject to the survey and engineering thereof.

IN WITNESS WHEREOF, the parties have set their hands on the day and year first written above.

**GRANTOR:**


  
By: **Mark D. Austin**

  
By: **Angela Austin, a/k/a Angie Austin**

**GRANTEE: Whiting Oil and Gas Corporation**


  
By: **David M. Seery, Vice President-Land**

#### ACKNOWLEDGEMENTS

STATE OF UTAH                    )  
  ) ss.  
COUNTY OF **EMERY** 

On this 22 day of May, 2012, before me, a Notary Public, personally appeared **Mark D. Austin and Angela Austin, a/k/a Angie Austin, husband and wife**, known to me to be the persons described in and who executed the within instrument, and acknowledged to me that **they** executed the






*Tamera Jean Ellis*  
NOTARY PUBLIC  
My Commission Expires: July 16, 2015

STATE OF COLORADO )  
 ) ss.  
COUNTY OF DENVER )

On this 15<sup>th</sup> day of MAY, 2012, before me, a Notary Public, personally appeared **David M. Seery, Vice President-Land**, a duly Authorized Agent of **Whiting Oil and Gas Corporation**, on behalf of the corporation.

WITNESS my hand and official seal the day and year first above written.


(SEAL)



*Frank J. Olsey III*  
NOTARY PUBLIC  
My Commission Expires: 8-31-2014


CONFIDENTIAL

**CONFIDENTIAL**



**API Number: 4301550003**  
**Well Name: Tully 16-9-36D**  
**Township T16.0S Range R09.0E Section 36**  
**Meridian: SLBM**  
**Operator: WHITING OIL & GAS CORPORATION**  
 Map Prepared:  
 Map Produced by Diana Mason

Units	Wells Query
<b>STATUS</b>	<b>Status</b>
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERM	PGW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
<b>Fields</b>	TA - Temp. Abandoned
Unknown	TW - Test Well
ABANDONED	WDW - Water Disposal
ACTIVE	WW - Water Injection Well
COMBINED	WSW - Water Supply Well
INACTIVE	Bottom Hole Location - Oil/Gas/Dls
STORAGE	
TERMINATED	



Well Name	WHITING OIL & GAS CORPORATION Tully 16-9-36D 43015500030000			
String	SURF	I1	PROD	
Casing Size(in)	13.375	9.625	7.000	
Setting Depth (TVD)	2100	6300	10517	
Previous Shoe Setting Depth (TVD)	0	2100	6300	
Max Mud Weight (ppg)	9.0	9.4	9.4	
BOPE Proposed (psi)	0	5000	5000	
Casing Internal Yield (psi)	2730	6870	8160	
Operators Max Anticipated Pressure (psi)	4554		8.3	

Calculations	SURF String	13.375	"
Max BHP (psi)	.052*Setting Depth*MW=	983	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	731	NO water, gel lime sweeps
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	521	NO OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	521	NO No expected pressure
Required Casing/BOPE Test Pressure=		1911	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	I1 String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	3079	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	2323	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	1693	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2155	NO OK
Required Casing/BOPE Test Pressure=		4809	psi
*Max Pressure Allowed @ Previous Casing Shoe=		2100	psi *Assumes 1psi/ft frac gradient

Calculations	PROD String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	5141	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	3879	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2827	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	4213	YES OK
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		6300	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BHP (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

# 43015500030000 Tully 16-9-36D

## Casing Schematic



Well name:	<b>43015500030000 Tully 16-9-36D</b>	
Operator:	<b>WHITING OIL &amp; GAS CORPORATION</b>	
String type:	Surface	Project ID: 43-015-50003
Location:	EMERY COUNTY	

**Design parameters:****Collapse**

Mud weight: 9.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 103 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 100 ft

**Burst:**

Design factor 1.00

Cement top: Surface

**Burst**

Max anticipated surface pressure: 1,848 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 2,100 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.70 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Non-directional string.****Re subsequent strings:**

Next setting depth: 6,300 ft  
Next mud weight: 9.400 ppg  
Next setting BHP: 3,076 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 2,100 ft  
Injection pressure: 2,100 psi

Tension is based on air weight.  
Neutral point: 1,821 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2100	13.375	54.50	J-55	ST&C	2100	2100	12.49	26057

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	982	1130	1.151	2100	2730	1.30	114.4	514	4.49 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: October 11, 2012  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 2100 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	<b>43015500030000 Tully 16-9-36D</b>	
Operator:	<b>WHITING OIL &amp; GAS CORPORATION</b>	
String type:	Intermediate	Project ID: 43-015-50003
Location:	EMERY COUNTY	

**Design parameters:****Collapse**

Mud weight: 9.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 162 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 995 ft

**Burst**

Max anticipated surface pressure: 2,822 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 4,208 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on air weight.  
Neutral point: 5,412 ft

**Non-directional string.****Re subsequent strings:**

Next setting depth: 10,517 ft  
Next mud weight: 9.400 ppg  
Next setting BHP: 5,136 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 6,300 ft  
Injection pressure: 6,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	6300	9.625	47.00	L-80	LT&C	6300	6300	8.625	105904

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	3076	4760	1.547	4208	6870	1.63	296.1	893	3.02 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: October 11, 2012  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 6300 ft, a mud weight of 9.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>43015500030000 Tully 16-9-36D</b>	
Operator:	<b>WHITING OIL &amp; GAS CORPORATION</b>	
String type:	Production	Project ID: 43-015-50003
Location:	EMERY COUNTY	

**Design parameters:****Collapse**

Mud weight: 9.700 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 221 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 3,254 ft

**Burst**

Max anticipated surface pressure: 2,986 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 5,299 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

**Non-directional string.**

Tension is based on air weight.  
Neutral point: 8,973 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	10517	7	29.00	L-80	LT&C	10517	10517	6.059	114252

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5299	7020	1.325	5299	8160	1.54	305	587	1.92 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: October 11, 2012  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 10517 ft, a mud weight of 9.7 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.



# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** WHITING OIL & GAS CORPORATION  
**Well Name** Tully 16-9-36D  
**API Number** 43015500030000      **APD No** 6704    **Field/Unit** WILDCAT  
**Location: 1/4,1/4** NWNW    **Sec** 36    **Tw** 16.0S    **Rng** 9.0E    860 FNL 856 FWL  
**GPS Coord (UTM)**      **Surface Owner** Mark Austin

### **Participants**

Bart Kettle-Division of Oil, Gas & Mining (DOGM), Mike McCandless-Emery County Economic Development, Mike Brown-CEP H&B Petroleum Consultants, Mark Austin-Surface Owner.

### **Regional/Local Setting & Topography**

Proposed project is located 3.2 miles north of the town of Cleveland, in Emery County Utah. Locally the proposed project is surrounded by salt scrub range lands adjacent to agriculture lands used to grow alfalfa, small grains and irrigated pasture. The closest permanent residents are located 0.7 miles to the east and south. Lights from drilling operations will be visible from some permanent residents.

Regionally the project area is within in the Castle Valley. The Castle Valley is largely composed of arid sites with poorly developed soils and sparse vegetation. Topography rises sharply to the west reaching elevations in excess of 10,000 atop the Wasatch Plateau. Montane forest and high elevation grass/forb communities dominate vegetation. To the east a series of reefs rise to the San Rafael Swell. Vegetation is a mixture of salt desert scrub and Pinion/Juniper forest.

Natural precipitation at the project site is considered a 8-10" zone, although artificial irrigation will raise annual water applications to around 40" in surrounding agriculture fields. Drainage flows into the North Branch of the Cleveland Cannel where it would be distributed to various agriculture fields.

### **Surface Use Plan**

#### **Current Surface Use**

Grazing  
Wildlfe Habitat

<b>New Road Miles</b>	<b>Well Pad</b>	<b>Src Const Material</b>	<b>Surface Formation</b>
1.25	<b>Width</b> 300 <b>Length</b> 360	Onsite	MNCS

**Ancillary Facilities** N

**Waste Management Plan Adequate?** Y

### **Environmental Parameters**

**Affected Floodplains and/or Wetlands** N

**Flora / Fauna**

**Flora:**

Grass: Salina Wild rye grass, Indian Rice grass, Curly Gallata, bottle brush squirrel tail, cheat grass.

Forbs: Globe mallow.

Shrubs: Black greasewood, mat salt brush, shade scale.

Trees: None at project site

Fauna: Site has the potential to hold small ground nesting birds, seasonal use by song birds, burrowing rodents, red fox, coyote, stripped skunk, antelope and mule deer.

**Soil Type and Characteristics**

Fine gray clays weathered from Mancos shale inter mixed with sandstone fragments.  
NRCS classify soils as Persayo Vickel Complex

**Erosion Issues Y**

Soils prone to wind erosion once disturbed. Fresh water should be applied to access road and well pad to control dust.

**Sedimentation Issues N**

**Site Stability Issues N**

Site appears suitable for the proposed drilling program.

**Drainage Diversion Required? Y**

Storm water should be diverted prior to entering well pad.

**Berm Required? N**

**Erosion Sedimentation Control Required? Y**

Apply fresh water to access road and well pad for dust control.

**Paleo Survey Run? N    Paleo Potential Observed? N    Cultural Survey Run? N    Cultural Resources? N**

**Reserve Pit**

Site-Specific Factors		Site Ranking
<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0
<b>Distance to Other Wells (feet)</b>	>1320	0
<b>Native Soil Type</b>	Low permeability	0
<b>Fluid Type</b>	TDS>5000 and	10
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>		0

<b>Affected Populations</b>	10 to 30	10 to 30
<b>Presence Nearby Utility Conduits</b>	Not Present	0
<b>Final Score</b>		16 3 Sensitivity Level

**Characteristics / Requirements**

APD proposed 9 mil liner. A 12 mil synthetic line is being required.

**Closed Loop Mud Required? N Liner Required? Y Liner Thickness 12 Pit Underlayment Required? N**

**Other Observations / Comments**

Emery County expressed concern regarding nuisance issues potentially associated with the proposed project. Previous oil and gas related activities in the county have lead to public complaints and several public meetings. Potential nuisance issue are:

Dust

H2S

Noise

Rig Lights

County Road Encroachment

It is in the best interest of all parties to take steps prior to drilling to limit potential for conflicts. Access roads and the well pad should have regular application of fresh water to control dust. In the event that an air drilling package is used a foaming agent is recommended to control dust from drill cuttings. Management of fluids should include a biocide to prevent the formation of H2S. Emery County recommends an informative heads up be delivered to surrounding residents outlining the project location, activities and anticipated length prior to initiating drilling activities.

DOGM expressed concern that an access gate/cattle guard arrangement had not be discussed with the surface owner. Access gate should meet the wishes of the surface owner, but at a minimum contain enough width to accommodate the expected traffic and remain functional as a barrier to livestock. A combination of a cattle guard with panel gates and a wire gate on the side is recommended for access from Hwy 155 and at the property boundary.

Bart Kettle  
**Evaluator**

9/25/2012  
**Date / Time**

# Application for Permit to Drill

## Statement of Basis

### Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
6704	43015500030000	LOCKED	OW	P	No
Operator	WHITING OIL & GAS CORPORATION		Surface Owner-APD	Mark Austin	
Well Name	Tully 16-9-36D		Unit		
Field	WILDCAT		Type of Work	DRILL	
Location	NWNW 36 16S 9E S 860 FNL 856 FWL GPS Coord (UTM) 511339E 4360531N				

#### Geologic Statement of Basis

The proposed well is to be drilled to a total depth of 10,517' with surface casing set from 0'-2,100'. The surface string will be drilled using fresh water and gel/lime sweeps. Within a 10,000' radius from the proposed well there are several shallow subsurface groundwater rights which are used for domestic, irrigation, and stock watering purposes. Several of the wells are also used for groundwater monitoring. The wells range in depth from 20' to 500'. The poorly permeable soil has been formed from the erosion of the Blue Gate Member of the Mancos Shale. Units of the Ferron Sandstone Member of the Mancos Shale are present in the subsurface, this strata is included within the interval to be protected by the surface casing string. The operator should be aware of the likelihood of these units being water saturated and to respond to protecting these zones as necessary. Proposed surface casing and cement should adequately isolate any shallow zones containing water. The Navajo Sandstone is a known fresh water aquifer in many parts of the state. In the San Rafael Swell area, the quality of the Navajo Sandstone aquifer generally becomes poorer with increased depth. The proposed well is expected to penetrate the Navajo Sandstone. The operator expects the Navajo Sandstone to be water saturated and the proposed intermediate casing and cementing program should adequately protect this zone as necessary.

Ammon McDonald  
APD Evaluator

10/10/2012  
Date / Time

#### Surface Statement of Basis

On-site evaluation conducted September 25, 2012. In attendance: Bart Kettle-Division of Oil, Gas & Mining (DOGM), Mike McCandless-Emery County Economic Development, Mark Austin-Surface owner, Mike Brown-CEP H&B Consultants

As proposed the project area is in close proximity to permanent residences. Nuisance complaints regarding drilling activity are a potential conflict. Emery County expressed multiple concerns regarding the management of nuisance issues. A daylight drilling program may limit noise conflicts. In the event a 24 hour drilling program is chosen, traffic to the project site should be limited between 8 pm and 7 am.

Fresh water should be applied daily to the access road and well pad to control dust. Portions of access road in close proximity to permanent residences may require fresh water applications multiple times each day.

Strict quality control should be implemented for all fluids used for the drilling and completion at this site. Biocide agents should be mixed with fluids to prevent the formation

of H2S currently and into the future.

Emery County requires application with the counties building and zoning department: Individual Gas/ Oil Well (Level I Permit) must be submitted and approved prior to drilling.

A Highway Road Encroachment Permit will be require for a change of use at access road intersection with HWY 155. Encroachment permit should be secured from Utah Department of Transportation.

A geomembrane liner with a minimum thickness of 12 mils shall be installed and maintained in reserve pit. Geomembrane liner shall consist of a string reinforced impervious synthetic material, resistant to hydrocarbons, salts and alkaline solutions.

It is recommended a 20' cattle guard with panel gates be installed at entrance to HWY 155 and at property boundary between Mr. Austin and Mr. Jensen. Cattle guard gate assembly should be installed with enough set back to allow trucks leaving HWY 155 a safe parking spot while gates are being opened or closed. Trees removed for construction of access should be removed from property so as not to interfere with agriculture practices.

Bart Kettle  
Onsite Evaluator

9/25/2012  
Date / Time

**Conditions of Approval / Application for Permit to Drill**

Category	Condition
Pits	A geomembrane liner with a minimum thickness of 12 mils shall be installed and maintained. Geomembrane liner shall consist of a string reinforced impervious synthetic material, resistant to hydrocarbons, salts and alkaline solutions.
Surface	Fresh water should be applied daily to the access road and well pad to control dust.
Surface	Applicable state and county permits shall be secured prior to initiating construction or drilling activity.

## WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 8/27/2012

API NO. ASSIGNED: 43015500030000

WELL NAME: Tully 16-9-36D

OPERATOR: WHITING OIL &amp; GAS CORPORATION (N2680)

PHONE NUMBER: 307 237-2310

CONTACT: Larry Brown

PROPOSED LOCATION: NWNW 36 160S 090E

Permit Tech Review: ☒

SURFACE: 0860 FNL 0856 FWL

Engineering Review: ☒

BOTTOM: 0860 FNL 0856 FWL

Geology Review: ☒

COUNTY: EMERY

LATITUDE: 39.39420

LONGITUDE: -110.86832

UTM SURF EASTINGS: 511339.00

NORTHINGS: 4360531.00

FIELD NAME: WILDCAT

LEASE TYPE: 3 - State

LEASE NUMBER: ML-52222

PROPOSED PRODUCING FORMATION(S): MANNING CANYON

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

## RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE - RLB 0004585☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: Municipal Water from Elmo☒ RDCC Review: 2012-10-15 00:00:00.0☒ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

## LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: R649-3-2

Effective Date:

Siting:

☐ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhill  
21 - RDCC - dmason  
23 - Spacing - dmason  
25 - Surface Casing - hmacdonald

RECEIVED: October 15, 2012



GARY R. HERBERT  
*Governor*

GREGORY S. BELL  
*Lieutenant Governor*

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

### Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

## Permit To Drill

\*\*\*\*\*

**Well Name:** Tully 16-9-36D  
**API Well Number:** 43015500030000  
**Lease Number:** ML-52222  
**Surface Owner:** FEE (PRIVATE)  
**Approval Date:** 10/15/2012

### Issued to:

WHITING OIL & GAS CORPORATION, 1700 Broadway, Suite 2300, Denver, CO 80290

### Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-2. The expected producing formation or pool is the MANNING CANYON Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

### Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### Conditions of Approval:

The Application for Permit to Drill has been forwarded to the Resource Development Coordinating Committee for review of this action. The operator will be required to comply with any applicable recommendations resulting from this review. (See attached)

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Surface casing shall be cemented to the surface.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

**Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels  
OR  
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website  
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program  
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

**Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office  
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office  
801-231-8956 - after office hours

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion



- Well Completion Report (Form 8) - due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read "J. Rogers", written over a faint horizontal line.

For John Rogers  
Associate Director, Oil & Gas

CONFIDENTIAL

## DIVISION OF OIL, GAS AND MINING

### SPUDDING INFORMATION

Name of Company; WHITING OIL & GAS CORPORATION

Well Name: TULLY 16-9-36D

Api No: 43-015-50003 Lease Type STATE

Section 36 Township 16S Range 09E County EMERY

Drilling Contractor PETE MARTIN DRLG RIG # 16

### SPUDDED:

Date 11/30/2012

Time 1:00 PM

How DRY

**Drilling will Commence:** \_\_\_\_\_

Reported by CHRIS BLODGETT

Telephone # (406) 647-2110

Date 11/30/2012 Signed CHD

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: Whiting Oil & Gas Corporation  
Address: 1700 Broadway, Suite 2300  
city Denver  
state CO zip 80290

Operator Account Number: N 2680

Phone Number: (303) 390-4095

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301550003	Tully 16-9-36D		NWNA	36	16S	9E	Emery
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	<u>new</u>	<u>18859</u>	<u>12/7/2012</u>		<u>1-9-2013</u>		
Comments: <u>mncyn</u>							

**CONFIDENTIAL**

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

**RECEIVED**

JAN 04 2013

Peggy Butler  
Name (Please Print)  
[Signature]  
Signature  
Deputy Tech  
Title  
1/3/13  
Date

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-52222
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: Tully 16-9-36D	
2. NAME OF OPERATOR: WHITING OIL & GAS CORPORATION	9. API NUMBER: 43015500030000	
3. ADDRESS OF OPERATOR: 1700 Broadway, Suite 2300, Denver, CO, 80290 2300	PHONE NUMBER: 303 390-4095 Ext	9. FIELD and POOL or WILDCAT: WILDCAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0860 FNL 0856 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S	COUNTY: EMERY	
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <b>2/20/2013</b>	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			
	OTHER: <span style="border: 1px solid black; padding: 2px;">Change of Drilling Plans</span>		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Whiting Oil and Gas Corporation is requesting a change of drilling plans to drill a casing exit horizontal lateral out of the subject well. The horizontal will target the Moenkopi Formation. The well will be drilled as follows: Also see attached drilling, directional plans and plat) KOP: 6,305' MD & TVD. Horizontal BHL: 660' FSL & 1,980' FEL, SWSE Section 36-T16S-R9W. A 4-1/2", 11.6#, L-80 grade liner will be set from 6,105' to 11,118' MD. Attached are the following documents for this request: Lease set-back affidavit, Drilling and Directional Plans, Horizontal well plat, Casing summary, existing cementing summaries for surface, intermediate and production casing strings.

**Approved by the  
Utah Division of  
Oil, Gas and Mining**


Date: February 13, 2013

By: *D. K. Duff*

NAME (PLEASE PRINT) Scott Webb	PHONE NUMBER 303 390-4095	TITLE Regulatory & Permitting Manager
SIGNATURE N/A		DATE 1/18/2013

# 43015500030000 Tully 16-9-36DrevH

## Casing Schematic



860 NL	856 WL
3760	2520
4620	3376
5297	5306
<u>677 FEL</u>	<u>1930 FEL</u>

Well name:	<b>43015500030000 Tully 16-9-36DrevH</b>	
Operator:	<b>WHITING OIL &amp; GAS CORPORATION</b>	
String type:	Production Liner	Project ID: 43-015-50003
Location:	EMERY COUNTY	

**Design parameters:****Collapse**

Mud weight: 9.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 169 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

**Burst**

Max anticipated surface pressure: 1,827 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 3,325 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on air weight.  
Neutral point: 6,782 ft

Liner top: 6,105 ft

**Directional Info - Build & Hold**

Kick-off point 6305 ft  
Departure at shoe: 4625 ft  
Maximum dogleg: 11 °/100ft  
Inclination at shoe: 90 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	5019	4.5	11.60	L-80	LT&C	6810	11119	3.875	23254
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	3325	6350	1.910	3325	7780	2.34	8.2	212	25.72 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: February 13, 2013  
Salt Lake City, Utah

**Remarks:**

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 6810 ft, a mud weight of 9.4 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

*Engineering responsibility for use of this design will be that of the purchaser.*

T16S, R9E, S.L.B.&M.

WHITTING OIL & GAS CORP.


Well location, TULLY #16-9-36D, located as shown in the NW 1/4 NW 1/4 of Section 36, T16S, R9W, S.L.B.&M., Emery County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION LOCATED AT THE NORTHWEST CORNER OF SECTION 36, T16S, R9E, S.L.B.&M., TAKEN FROM THE ELMO QUADRANGLE, UTAH, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5991 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
STATE OF UTAH  
161519

REVISED: 08-01-2012


UNTARH ENGINEERING & LAND SURVEYING  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE: 1" = 1000'  
DATE SURVEYED: 12-20-11 DATE DRAWN: 12-23-11

PARTY	REFERENCES
B.B. J.G. B.L.B.	G.L.O. PLAT
WEATHER	FILE
COLD	WHITTING OIL & GAS CORP.

LEGEND:

- 90° SYMBOL
- PROPOSED WELL HEAD.
- SECTION CORNERS LOCATED.





AFFIDAVIT Distance to Lease Lines

Tully 15-11-18E

Well Name: Tully 16-9-36D Horizontal Casing Exit

Location: SHL 860' FNL & 856' FWL

BHL 1980' FSL & 660' FEL


Section 36-T16S-R9E

County: Emery County, Utah

Permit No.: API# 43-015-50030

The Subject well horizontal wellbore will be a minimum of 660 feet away from all lease lines in Section 36-T16S-R9E, Emery County, Utah

Dated: January 18, 2013



Scott M. Webb-Regulatory & Permitting Manager

Whiting Oil and Gas Corporation

ACKNOWLEDGEMENT

STATE OF COLORADO )


) ss.

COUNTY OF DENVER )

On this 18th day of January, 2013, before me, a Notary Public, personally appeared Scott M. Webb, who being by me duly sworn, did say that he is Regulatory & Permitting Manager of Whiting Oil and Gas Corporation, and that the foregoing instrument was executed by him on behalf of said company as its free act and deed.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed by Notarial Seal the day and year first above written.

(SEAL)



NOTARY PUBLIC

My Commission Expires **4/27/2016**

**Whiting Oil & Gas Corporation**  
**Tully 16-9-36D Drill Plan**  
**Horizontal – Moenkopi Well**  
**January 18, 2013**

**Summary:**

The Tully 16-9-36D well will be a horizontal well in the Moenkopi formation. The well was drilled to 7,480' TD and 7" casing was run and cemented. A whip-stock will be set and a window cut in the 7" casing at 6,305' MD. A 6-1/8" curve will be built to land the in the Moenkopi at 6,810' TVD. The lateral will be drilled with a 6-1/8" bit to TD at 11,118' MD. 4-1/2" casing with swell packers will be run in the lateral for completion.

**Surface Location:** 36-T16S-R9E  
 860' FNL 856' FWL  
 Emery County, Utah

**Bottomhole Location:** 36-T16S-R9E  
 660' FSL 1980' FEL  
 Weld County, Colorado

**DRILLING PROGRAM****1. ESTIMATED TOPS OF GEOLOGICAL MARKERS:**

Ground Level 5,871' Estimated KB 5,893' (22')

<b><u>Formation</u></b>	<b><u>MD</u></b>	<b><u>Lithology</u></b>	<b><u>Hazard</u></b>
Mancos	Surface	SH-SS	
Ferron	1,049'	SS-COAL-SH	
Dakota	1,939'	SS-SI-SH	
Chinle	5,980'	SS-SH	
Moenkopi	6,301'	SS-SH-LS	
Horizontal Target (TVD)	6,810'	SS-SH-LS	
TD Niobrara Horizontal (MD)	11,118'		

**2. DIRECTIONAL PLANS**

KOP: 6,305' MD, 6,305' TVD  
 BUILD RATE - AZIMUTH: 11°/100', 146.54° Azimuth  
 END OF BUILD: 7,108' MD, 6,810' TVD at 90° Inc and 146.54° Azimuth  
 TD LATERAL: 11,117' MD, 6,810' TVD at 90.00° Inc and 146.54° Azimuth  
 BH LOCATION: 660' FSL & 1980' FEL Sec 36 T16S R9E

See attached Directional Proposal Listings for more details.

### **3. PRESSURE CONTROL EQUIPMENT**

**A. Type:** 13-5/8" 5,000 psi double gate hydraulic BOP with 13-5/8" 5,000 psi annular preventer with 5,000 psi Casinghead and 5,000 psi Tubinghead.

**B. Testing Procedure:**

The annular preventer will be pressure tested to 50% of stack rated working pressure for ten (10) minutes or until provisions of test are met, whichever is longer. The BOP, choke manifold, and related equipment will be pressure tested to approved BOP stack working pressure (if isolated from surface casing by a test plug) or to 70% of surface casing internal yield strength (if BOP is not isolated by a test plug). Pressure will be maintained for ten (10) minutes or until the requirements of the test are met, whichever is longer. At a minimum, the Annular and Blow-Out Preventer pressure tests will be performed:

1. When the BOPE is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

Annular will be function tested weekly, and pipe & blind rams activated each trip, but not more than once per day. All BOP drills & tests will be recorded in IADC driller's log.

**C. Choke Manifold Equipment:**

All choke lines will be straight lines whenever possible at turns, tee blocks will be used or will be targeted with running tees, and will be anchored to prevent whip and vibration.

**D. Accumulator:**

Accumulator will have sufficient capacity to open hydraulically-controlled choke line valve (if so equipped), close all rams plus annular preventer, and retain a minimum of 200 psi above precharge on the closing manifold without the use of closing unit pumps. The fluid reservoir capacity will be double accumulator capacity and the fluid level will be maintained at manufacturer's recommendations. Accumulator precharge pressure test will be conducted prior to connecting the closing unit to the BOP stack.

**E. Miscellaneous Information:**

Choke manifold and BOP extension rods with hand wheels will be located outside rig sub-structure. Hydraulic BOP closing unit will be located at least twenty-five (25) feet from the wellhead but readily accessible to the driller. Exact locations and configurations of the hydraulic BOP closing unit will depend upon the particular rig contracted to drill this hole.

A flare line will be installed after the choke manifold with the discharge point of the flare line to a separate pit located at least 125 feet away from the wellbore and any existing production facilities.

A volume monitoring system with alarms will be used to monitor pit gains/losses along with visual backup.

**4. PROPOSED CASING PROGRAM****A. Casing Program: All New**

Hole Size	Casing Size	Wt./Ft.	Grade	Joint	Coupling OD	Burst (psi)	Collapse (psi)	Tension (Body/Joint) (klbs)	Depth Set (md)
17-1/2"	13-3/8"	54.50	J-55	ST&C	14.375"	2,730	1,130	853/514	0 – 2,081'
12-1/4"	9-5/8"	47	L-80	LT&C	10.625"	6,870	4,750	1,086/893	0 – 6,294'
8-1/2"	7"	29	L-80	LT&C	7.656"	8,160	7,020	676/587	0 – 7,460'
6-1/8"	4-1/2"	11.6	L-80	LT&C	5"	7,780	6,350	267/212	6,105' – 11,118'

Existing 13-3/8" surface casing has centralizers as follows:

1. Install a bowspring centralizer at the first and second collars above the guide shoe.
2. Install one bowspring centralizer every third joint above the second collar.
3. Centralizer and basket placed 120' below the surface (or at the bottom of the third joint below the surface).
4. Centralizer and basket placed 80' below the surface (or at the bottom of the second joint below the surface).

Existing -5/8" intermediate casing has centralizers as follows:

1. Install a bowspring centralizer at the first and second collars above the guide shoe.
2. After that centralize every third joint to surface with single bow spring centralizers

Existing 7" production casing has centralizers as follows:

1. Install a bowspring centralizer at the first and second collars above the guide shoe.
2. After that centralize every third joint to surface with single bow spring centralizers.

A 4-1/2" Liner to be run with Swelling Packers and Frac Sleeves

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

**B. Casing Design Parameters:****Existing Surface Casing**

Interval	Size	Wt	Grade	Burst (psi) <sup>a</sup> /SF	Collapse (psi) <sup>b</sup> /SF	Tension (klb) <sup>c</sup> /SF
0' – 2,081'	13-3/8"	54.50 lb/ft	J-55	2,730/1.89	1,130/1.16	514/5.25

- a. based on frac gradient at shoe of 14.0 ppg
- b. based on full evacuation with 9.0 ppg fluid on backside
- c. based on casing string weight in 9.0 ppg mud  
String Weight in 9.0 ppg mud ≈ 97,831 lbs

**Existing Intermediate Casing**

Interval	Size	Wt	Grade	Burst (psi) <sup>a</sup> /SF	Collapse (psi) <sup>b</sup> /SF	Tension (klb) <sup>c</sup> /SF
0' – 6,294'	9-5/8"	47.0 lb/ft	L-80	6,870/4.92	4,750/1.54	893/3.52

- a. based on frac gradient at shoe of 14.0 ppg
- b. based on full evacuation with 9.4 ppg pore pressure on backside
- c. based on casing string weight in 9.4 ppg mud  
String Weight in 9.4 ppg mud ≈ 253,365 lbs.

**Existing Production Casing**

<u>Interval</u>	<u>Size</u>	<u>Wt</u>	<u>Grade</u>	<u>Burst (psi)<sup>a</sup>/SF</u>	<u>Collapse (psi)<sup>b</sup>/SF</u>	<u>Tension (klb)<sup>c</sup>/SF</u>
0' – 7,460'	7"	29.0 lb/ft	L-80	8,160/1.26	7,020/1.93	587/3.17

- based on 6,500 psi frac pressure.
- based on full evacuation with 9.4 ppg pore pressure on backside
- based on casing string weight in 9.4 ppg mud  
String Weight in 9.4 ppg mud  $\approx$  185,293 lbs.

**Proposed Production Liner**

<u>Interval</u>	<u>Size</u>	<u>Wt</u>	<u>Grade</u>	<u>Burst (psi)<sup>a</sup>/SF</u>	<u>Collapse (psi)<sup>b</sup>/SF</u>	<u>Tension (klb)<sup>c</sup>/SF</u>
6,105' – 11,118'	4-1/2"	11.6 lb/ft	L-80	7,780/1.20	6,350/1.91	212/4.26

- based on 6,500 psi frac pressure.
- based on full evacuation with 9.4 ppg pore pressure on backside
- based on casing string weight in 9.4 ppg mud  
String Weight in 9.4 ppg mud  $\approx$  49,805 lbs.

**5. Existing CEMENTING PROGRAM****Existing Surface Casing – 13-3/8" Casing: TOC Surface, (100% Excess)**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	XC (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
13-3/8"	Lead	1,581'	Lead Cement Rockies LT; - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 0.25 lbm/sk Kwik Seal (Lost Circulation Additive)	1070	100	11.5	2.94
13-3/8"	Tail	500'	Tail Cement Premium Cement; - 94 lbm/sk Premium Cement (Cement) - 2% Calcium Chloride (Accelerator) - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive)	440	100	15.6	1.20

A cement top job is required if cement fallback is greater than 10' below ground level.

**Existing Intermediate Casing – 9-5/8" Casing:** TOC Surface, (Stage Tool at 3,300' – Stage\_1 - 50% Excess,  
Stage\_2 – 50% Excess)

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	XC (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
9-5/8"	Stage_1 – Lead	1,500'	First Stage Lead Cement ECONOCЕМ; - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 1 % HR-5 (Retarder) - 0.2 % Super CBL (Expander)	700	50	12.2	2.16
9-5/8"	Stage_1 – Tail	1,500'	First Stage Tail Cement EXTENDACЕМ; - 0.5 % HR-5 (Retarder) - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 3 lbm/sk Gilsonite (Lost Circulation Additive)	350	50	14.2	1.29
9-5/8"	Stage_2 – Lead	3,300'	Second Stage Primary Cement ECONOCЕМ; - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 0.5 % HR-5 (Retarder) - 0.2 % Super CBL (Expander)	920	50	12.2	2.15

**Existing Production Casing – 7" Casing:** TOC Surface, (35% Excess)

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	XC (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
7"	Lead	6,294'	Lead Cement ECONOCЕМ; - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive) - 0.8 % HR-5 (Retarder) - 0.2 % Super CBL (Expander)	435	35	12.2	2.15
7"	Tail	1,186'	Tail Cement EXTENDACЕМ; - 0.4 % HR-5 (Retarder) - 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive)	230	35	14.2	1.29

**6. MUD PROGRAM**

<u>Depth (MD)</u>	<u>Mud System</u>	<u>MW</u>	<u>PV</u>	<u>YP</u>	<u>FL</u>
0 -2,081'	Water, Gel/Lime Sweeps	8.4 – 9.0	2 - 20	2 - 18	NC
2,081' – 6,294'	3% KCL Water/Polymer	8.4 – 9.4	10 - 28	6 - 18	6 - 10
6,294' – 7,480'	3% KCL Water/Polymer	8.4 – 9.4	14 - 32	10 - 22	4 - 10
6,305' – 11,118'	3% KCL Water/Polymer	8.4 – 9.4	14 - 32	10 - 22	4 - 10

**7. EVALUATION PROGRAM (in vertical bore)**

Cores: 60' of core planned from 6,337' to 6,397'.  
60' of core planned from 9,664' to 9,754'.

DST: None planned

Surveys: Deviation surveys every 500' to TD in the surface, intermediate and production holes.

Mud Logger:

Samples: 30' samples surface to TD

Open Hole Logging Program: Triple Combo 7,480' to Surface

**8. ABNORMAL CONDITIONS**

No abnormal pressures are anticipated. No H<sub>2</sub>S gas is anticipated.

Anticipated bottom hole pressure is 3,239 psi (0.433 psi/ft) at 7,480' TVD in the Humbug and the maximum anticipated surface pressure equals approximately 1,593 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

**9. ANTICIPATED STARTING DATES**

**A. Anticipated Starting Dates:**

Drilling work startup: February 2013


Original Spud: December 7, 2012

Duration: 25 – 35 days





Project: Emery County, UT  
 Site: S36-T16S-R9W  
 Well: Tully #16-9-36D  
 Wellbore: CURVE-LATERAL  
 Design: Scenario 3



## Planning Report

<b>Database:</b>	USA EDM 5000 Multi Users DB	<b>Local Co-ordinate Reference:</b>	Well Tully #16-9-36D
<b>Company:</b>	Whiting Petroleum Corporation	<b>TVD Reference:</b>	16.5' KB @ 5905.5usft (Frontier 2)
<b>Project:</b>	Emery County, UT	<b>MD Reference:</b>	16.5' KB @ 5905.5usft (Frontier 2)
<b>Site:</b>	S36-T16S-R9W	<b>North Reference:</b>	True
<b>Well:</b>	Tully #16-9-36D	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	CURVE-LATERAL		
<b>Design:</b>	Scenario 3		

<b>Project</b>	Emery County, UT		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	Utah Central Zone		

Site		S36-T16S-R9W			
Site Position:		Northing:	6,948,708.81 usft	Latitude:	39° 23' 39.190 N
From:	Lat/Long	Easting:	1,818,931.37 usft	Longitude:	110° 52' 5.930 W
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16"	Grid Convergence:	0.40 °

Well	Tully #16-9-36D					
Well Position	+N/-S	0.0 usft	Northing:	6,948,708.77 usft	Latitude:	39° 23' 39.190 N
	+E/-W	0.0 usft	Easting:	1,818,931.37 usft	Longitude:	110° 52' 5.930 W
Position Uncertainty		0.0 usft	Wellhead Elevation:	usft	Ground Level:	5,889.0 usft

<b>Wellbore</b>	CURVE-LATERAL				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2010	1/7/2013	11.33	65.06	51,641

<b>Design</b>	Scenario 3				
<b>Audit Notes:</b>					
<b>Version:</b>	<b>Phase:</b>	PROTOTYPE	<b>Tie On Depth:</b>	6,305.4	
<b>Vertical Section:</b>	<b>Depth From (TVD) (usft)</b>	<b>+N/-S (usft)</b>	<b>+E/-W (usft)</b>	<b>Direction (°)</b>	
	0.0	0.0	0.0	146.17	

<b>Plan Sections</b>										
<b>Measured Depth (usft)</b>	<b>Inclination (°)</b>	<b>Azimuth (°)</b>	<b>Vertical Depth (usft)</b>	<b>+N/-S (usft)</b>	<b>+E/-W (usft)</b>	<b>Dogleg Rate (°/100usft)</b>	<b>Build Rate (°/100usft)</b>	<b>Turn Rate (°/100usft)</b>	<b>TFO (°)</b>	<b>Target</b>
6,305.4	1.76	131.21	6,304.6	18.1	18.7	0.00	0.00	0.00	0.00	
7,108.1	90.00	146.54	6,810.0	-414.1	309.1	11.00	10.99	1.91	15.35	
11,118.5	90.00	146.54	6,810.0	-3,760.0	2,520.0	0.00	0.00	0.00	0.00	Tully #16-9-36D Scen

## Planning Report

<b>Database:</b>	USA EDM 5000 Multi Users DB	<b>Local Co-ordinate Reference:</b>	Well Tully #16-9-36D
<b>Company:</b>	Whiting Petroleum Corporation	<b>TVD Reference:</b>	16.5' KB @ 5905.5usft (Frontier 2)
<b>Project:</b>	Emery County, UT	<b>MD Reference:</b>	16.5' KB @ 5905.5usft (Frontier 2)
<b>Site:</b>	S36-T16S-R9W	<b>North Reference:</b>	True
<b>Well:</b>	Tully #16-9-36D	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	CURVE-LATERAL		
<b>Design:</b>	Scenario 3		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100u)	Comments / Formations
6,305.4	1.76	131.21	6,304.6	18.1	18.7	-4.6	0.00	0.00	KOP @ 6305'
6,400.0	12.11	144.37	6,398.4	9.0	25.6	6.8	11.00	10.94	
6,500.0	23.11	145.45	6,493.6	-15.8	42.9	37.0	11.00	11.00	
6,600.0	34.11	145.86	6,581.2	-55.3	69.8	84.8	11.00	11.00	
6,700.0	45.11	146.08	6,658.1	-108.0	105.4	148.4	11.00	11.00	
6,800.0	56.11	146.23	6,721.5	-172.1	148.4	225.6	11.00	11.00	
6,900.0	67.11	146.35	6,769.0	-245.2	197.1	313.4	11.00	11.00	
7,000.0	78.11	146.45	6,798.8	-324.5	249.9	408.7	11.00	11.00	
7,100.0	89.11	146.54	6,810.0	-407.3	304.7	507.9	11.00	11.00	
7,108.1	90.00	146.54	6,810.0	-414.1	309.1	516.1	11.00	11.00	LP @ 6810' MD; 90°
7,200.0	90.00	146.54	6,810.0	-490.7	359.8	607.9	0.00	0.00	
7,300.0	90.00	146.54	6,810.0	-574.1	414.9	707.9	0.00	0.00	
7,400.0	90.00	146.54	6,810.0	-657.6	470.0	807.9	0.00	0.00	
7,500.0	90.00	146.54	6,810.0	-741.0	525.2	907.9	0.00	0.00	
7,600.0	90.00	146.54	6,810.0	-824.4	580.3	1,007.9	0.00	0.00	
7,700.0	90.00	146.54	6,810.0	-907.9	635.4	1,107.9	0.00	0.00	
7,800.0	90.00	146.54	6,810.0	-991.3	690.5	1,207.9	0.00	0.00	
7,900.0	90.00	146.54	6,810.0	-1,074.7	745.7	1,307.9	0.00	0.00	
8,000.0	90.00	146.54	6,810.0	-1,158.2	800.8	1,407.9	0.00	0.00	
8,100.0	90.00	146.54	6,810.0	-1,241.6	855.9	1,507.9	0.00	0.00	
8,200.0	90.00	146.54	6,810.0	-1,325.0	911.1	1,607.9	0.00	0.00	
8,300.0	90.00	146.54	6,810.0	-1,408.5	966.2	1,707.9	0.00	0.00	
8,400.0	90.00	146.54	6,810.0	-1,491.9	1,021.3	1,807.9	0.00	0.00	
8,500.0	90.00	146.54	6,810.0	-1,575.3	1,076.4	1,907.9	0.00	0.00	
8,600.0	90.00	146.54	6,810.0	-1,658.7	1,131.6	2,007.9	0.00	0.00	
8,670.1	90.00	146.54	6,810.0	-1,717.2	1,170.2	2,078.0	0.00	0.00	Tully #16-9-36D Scenario 1 PBHL
8,700.0	90.00	146.54	6,810.0	-1,742.2	1,186.7	2,107.9	0.00	0.00	
8,800.0	90.00	146.54	6,810.0	-1,825.6	1,241.8	2,207.9	0.00	0.00	
8,900.0	90.00	146.54	6,810.0	-1,909.0	1,297.0	2,307.9	0.00	0.00	
9,000.0	90.00	146.54	6,810.0	-1,992.5	1,352.1	2,407.9	0.00	0.00	
9,100.0	90.00	146.54	6,810.0	-2,075.9	1,407.2	2,507.9	0.00	0.00	
9,200.0	90.00	146.54	6,810.0	-2,159.3	1,462.3	2,607.9	0.00	0.00	
9,300.0	90.00	146.54	6,810.0	-2,242.8	1,517.5	2,707.9	0.00	0.00	
9,400.0	90.00	146.54	6,810.0	-2,326.2	1,572.6	2,807.9	0.00	0.00	
9,500.0	90.00	146.54	6,810.0	-2,409.6	1,627.7	2,907.9	0.00	0.00	
9,600.0	90.00	146.54	6,810.0	-2,493.1	1,682.9	3,007.9	0.00	0.00	
9,700.0	90.00	146.54	6,810.0	-2,576.5	1,738.0	3,107.9	0.00	0.00	
9,800.0	90.00	146.54	6,810.0	-2,659.9	1,793.1	3,207.9	0.00	0.00	
9,900.0	90.00	146.54	6,810.0	-2,743.4	1,848.2	3,307.9	0.00	0.00	
10,000.0	90.00	146.54	6,810.0	-2,826.8	1,903.4	3,407.9	0.00	0.00	
10,100.0	90.00	146.54	6,810.0	-2,910.2	1,958.5	3,507.9	0.00	0.00	
10,200.0	90.00	146.54	6,810.0	-2,993.7	2,013.6	3,607.9	0.00	0.00	
10,300.0	90.00	146.54	6,810.0	-3,077.1	2,068.8	3,707.9	0.00	0.00	
10,400.0	90.00	146.54	6,810.0	-3,160.5	2,123.9	3,807.8	0.00	0.00	
10,500.0	90.00	146.54	6,810.0	-3,243.9	2,179.0	3,907.8	0.00	0.00	
10,600.0	90.00	146.54	6,810.0	-3,327.4	2,234.1	4,007.8	0.00	0.00	
10,700.0	90.00	146.54	6,810.0	-3,410.8	2,289.3	4,107.8	0.00	0.00	
10,730.2	90.00	146.54	6,810.0	-3,436.0	2,305.9	4,138.0	0.00	0.00	Tully #16-9-36D Scenario 2 PBHL
10,800.0	90.00	146.54	6,810.0	-3,494.2	2,344.4	4,207.8	0.00	0.00	
10,900.0	90.00	146.54	6,810.0	-3,577.7	2,399.5	4,307.8	0.00	0.00	
11,000.0	90.00	146.54	6,810.0	-3,661.1	2,454.7	4,407.8	0.00	0.00	
11,100.0	90.00	146.54	6,810.0	-3,744.5	2,509.8	4,507.8	0.00	0.00	

## Planning Report

<b>Database:</b>	USA EDM 5000 Multi Users DB	<b>Local Co-ordinate Reference:</b>	Well Tully #16-9-36D
<b>Company:</b>	Whiting Petroleum Corporation	<b>TVD Reference:</b>	16.5' KB @ 5905.5usft (Frontier 2)
<b>Project:</b>	Emery County, UT	<b>MD Reference:</b>	16.5' KB @ 5905.5usft (Frontier 2)
<b>Site:</b>	S36-T16S-R9W	<b>North Reference:</b>	True
<b>Well:</b>	Tully #16-9-36D	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	CURVE-LATERAL		
<b>Design:</b>	Scenario 3		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100u)	Comments / Formations
11,118.5	90.00	146.54	6,810.0	-3,760.0	2,520.0	4,526.4	0.00	0.00	TD at 11118.5 - Tully #16-9-36D Scenario 3 PBI

Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Tully #16-9-36D Scenari - plan hits target center - Circle (radius 1,980.0)	0.00	0.00	6,810.0	-3,760.0	2,520.0	6,944,966.66	1,821,477.86	39° 23' 2.024 N	110° 51' 33.833 W
Tully #16-9-36D Scenari - plan misses target center by 1827.9usft at 10730.2usft MD (6810.0 TVD, -3436.0 N, 2305.9 E) - Point	0.00	0.00	6,810.0	-2,428.3	3,831.0	6,946,307.58	1,822,779.43	39° 23' 15.185 N	110° 51' 17.133 W
Tully #16-9-36D PBHL - plan misses target center by 1320.1usft at 11118.5usft MD (6810.0 TVD, -3760.0 N, 2520.0 E) - Point	0.00	0.00	6,810.0	-3,748.0	3,840.0	6,944,987.98	1,822,797.75	39° 23' 2.141 N	110° 51' 17.021 W
Tully #16-9-36D Scenari - plan misses target center by 3169.4usft at 8670.1usft MD (6810.0 TVD, -1717.2 N, 1170.2 E) - Point	0.00	0.00	6,810.0	30.0	3,814.5	6,948,765.71	1,822,745.57	39° 23' 39.483 N	110° 51' 17.338 W

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
6,305.4	6,304.6	18.1	18.7	KOP @ 6305'	
7,108.1	6,810.0	-414.1	309.1	LP @ 6810' MD; 90°	
11,118.5	6,810.0	-3,760.0	2,520.0	TD at 11118.5	



## Casing Summary

Well Name: TULLY 16-9-36D

### Well Information

Well Information												
API Number 43015500030000			WPC ID 1UT029802		Field Name Wildcat			KB-Grd (ft) 16.50		Original Spud Date 12/7/2012		
Lot	Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36	Township	Township... 16 S	Range	Range E... 9 E	County Emery	State UT	Well Configuration Type Vertical

### Wellbore Sections

Section Des	Size (in)	Act Top (ftKB)	Act Btm (ftKB)
Conductor	26	16.5	96.5
Surface	17 1/2	96.5	2,122.0
Intermediate	12 1/4	2,122.0	6,315.0
Production	8 1/2	6,315.0	7,480.0

### Casing

#### Conductor Pipe, 96.5ftKB

Comment

Run Date 12/1/2012	Set Depth (ft/KB) 96.5	Set Tension (kips)	OD (in) 20	Centralizers					Scratchers		
Jts	Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Top (ft/KB)	Btm (ft/KB)	Len (ft)	P Burst (psi)	P Collapse (psi)
2	Casing Joints	20	19.124	94.00	H-40		16.5	96.5	80.00		520.0

#### Surface Csg, 2,081.2ftKB

Comment

Run Date 12/12/2012	Set Depth (ftKB) 2,081.2	Set Tension (kips)	OD (in) 13 3/8	Centralizers Bow Spring on first joint then every third					Scratchers		
Jts	Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Top (ftKB)	Btm (ftKB)	Len (ft)	P Burst (psi)	P Collapse (psi)
46	Casing Joints	13 3/8	12.615	54.50	J-55	ST&C	16.5	2,034.5	2,018.00		
1	Float Collar	13 3/8	12.615	54.50	J-55	ST&C	2,034.5	2,035.5	1.00		1,130.0
1	Casing Joints	13 3/8	12.615	54.50	J-55	ST&C	2,035.5	2,080.7	45.20		1,130.0
1	Shoe	13 3/8	12.615	54.50	J-55		2,080.7	2,081.2	0.50		

#### Intermediate Csg, 6,294.2ftKB

Comment

Run Date 12/22/2012		Set Depth (ftKB) 6,294.2		Set Tension (kips)		OD (in) 9 5/8		Centralizers		Scratchers	
Jts	Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Top (ftKB)	Btm (ftKB)	Len (ft)	P Burst (psi)	P Collapse (psi)
80	Casing Joints	9 5/8	8.681	47.00	L-80	LT&C	16.5	3,293.5	3,277.02		4,760.0
1	DV Tool	9 5/8				LT&C	3,293.5	3,296.0	2.50		
70	Casing Joints	9 5/8	8.681	47.00	L-80	LT&C	3,296.0	6,249.9	2,953.90		4,760.0
1	Float Collar	9 5/8				LT&C	6,249.9	6,251.4	1.50		
1	Casing Joints	9 5/8	8.681	47.00	L-80	LT&C	6,251.4	6,292.7	41.28		4,760.0
1	Guide Shoe	9 5/8				LT&C	6,292.7	6,294.2	1.50		

#### Production Csg, 7,460.0ftKB

Comment

Run Date 1/2/2013		Set Depth (ft)B 7,460.0		Set Tension (kips)		OD (in) 7		Centralizers		Scratchers	
Jts	Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Top (ft)B	Btm (ft)B	Len (ft)	P Burst (psi)	P Collapse (psi)
0	Casing Joints	7	6.184	29.00	HCL-80	LT&C	16.5	16.5	0.00		
1	Landing Joint	7	6.184	29.00	HCL-80	LT&C	16.5	25.6	9.05		
1	Casing Joints	7	6.184	29.00	HCL-80	LT&C	25.6	50.2	24.67		
0	Casing Joints	7	6.184	29.00	HCL-80	LT&C	50.2	50.2	0.00		
173	Casing Joints	7	6.184	29.00	HCL-80	LT&C	50.2	7,418.0	7,367.76		
1	Float Collar	7	6.184	29.00	HCL-80	LT&C	7,418.0	7,419.0	1.00		
1	Casing Joints	7	6.184	29.00	HCL-80	LT&C	7,419.0	7,459.0	40.02		
1	Float Shoe	7	6.184	29.00	HCL-80	LT&C	7,459.0	7,460.0	1.00		





## Cement Summary

**Well Name: TULLY 16-9-36D**

### Well Information

Well Information													
API Number 43015500030000				WPC ID 1UT029802			Field Name Wildcat			KB-Grd (ft) 16.50		Original Spud Date 12/7/2012	
Lot	Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36	Township 16 S	Twnshp...	Range 9 E	Rng E'...	County Emery	State UT	Well Configuration Type Vertical	

### Wellbores

Wellbore Name Original Hole					Profile Type Vertical			Kick Off Depth (ftKB)			
Section Des					Size (in)			Act Top (ftKB)		Act Btm (ftKB)	
Conductor					26			16.5		96.5	
Surface					17 1/2			96.5		2,122.0	
Intermediate					12 1/4			2,122.0		6,315.0	
Production					8 1/2			6,315.0		7,480.0	

### Wellheads

Type	Install Date										
------	--------------	--	--	--	--	--	--	--	--	--	--

### Conductor Cement

Cementing Start Date			Cementing End Date			Wellbore		
12/1/2012 11:30			12/1/2012 12:30			Original Hole		
Evaluation Method						Cement Evaluation Results		
Returns to Surface								
Comment								

### Stage #<Stage Number?>

Top Depth (ftKB) 16.5	Bottom Depth (ftKB) 96.5	Full Return? No	Vol Cement Ret (bbl) No	Top Plug? No	Bottom Plug? No
Initial Pump Rate (bbl/min)	Final Pump Rate (bbl/min)	Avg Pump Rate (bbl/min)		Final Pump Pressure (psi)	Plug Bump Pressure (psi)
Pipe Reciprocated? No	Reciprocation Stroke Length (ft)	Reciprocation Rate (spm)		Pipe Rotated? No	Pipe RPM (rpm)
Tagged Depth (ftKB)	Tag Method	Depth Plug Drilled Out To (ftKB)		Drill Out Diameter (in)	Drill Out Date



## Cement Summary

Well Name: TULLY 16-9-36D

### Well Information

Well Information													
API Number 43015500030000				WPC ID 1UT029802			Field Name Wildcat			KB-Grd (ft) 16.50		Original Spud Date 12/7/2012	
Lot	Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36	Township 16 S	Township...	Range 9 E	Rng E/...	County Emery	State UT	Well Configuration Type Vertical	

### Wellbores

Wellbore Name	Profile Type	Kick Off Depth (ftKB)		
Original Hole	Vertical			
Section Des	Size (in)	Act Top (ftKB)	Act Btm (ftKB)	
Conductor	26	16.5	96.5	
Surface	17 1/2	96.5	2,122.0	
Intermediate	12 1/4	2,122.0	6,315.0	
Production	8 1/2	6,315.0	7,480.0	

### Wellheads

Type	Install Date
------	--------------

### Surface Casing Cement

Cementing Start Date			Cementing End Date			Wellbore		
12/12/2012 09:30			12/12/2012 16:00			Original Hole		
Evaluation Method						Cement Evaluation Results		
Returns to Surface								
Comment								

### Stage #1

Top Depth (ftKb)	Bottom Depth (ftKb)	Full Return?	Vol Cement Ret (bbl)	Top Plug?	Bottom Plug?
16.5	2,081.2	Yes	2.5	No	Yes
Initial Pump Rate (bbl/min)	Final Pump Rate (bbl/min)	Avg Pump Rate (bbl/min)		Final Pump Pressure (psi)	Plug Bump Pressure (psi)
6	1	4		385.0	385.0
Pipe Reciprocated?	Reciprocation Stroke Length (ft)	Reciprocation Rate (spm)		Pipe Rotated?	Pipe RPM (rpm)
No				No	
Tagged Depth (ftKb)	Tag Method	Depth Plug Drilled Out To (ftKb)		Drill Out Diameter (in)	Drill Out Date

### Spacer

Fluid Type Spacer	Fluid Description	Amount (sacks)	Class	Volume Pumped (bbl) 15.0
Estimated Top (ftKb)	Estimated Bottom Depth (ftKb)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
Free Water (%)	Density (lb/gal) 8.34	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

### Preflush

Fluid Type Preflush	Fluid Description	Amount (sacks)	Class	Volume Pumped (bbl) 30.0
Estimated Top (ftKb)	Estimated Bottom Depth (ftKb)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
Free Water (%)	Density (lb/gal) 9.20	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

### Spacer

Fluid Type Spacer	Fluid Description	Amount (sacks)	Class	Volume Pumped (bbl) 15.0
Estimated Top (ftKb)	Estimated Bottom Depth (ftKb)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
Free Water (%)	Density (lb/gal) 8.34	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

### Cement Fluid Additives

Add	Type	Amount	Amount Units	Conc	Conc Unit
Flush		68.0	lb		

### Lead Cement

Fluid Type Lead Cement	Fluid Description	Amount (sacks) 1,070	Class Prem Lite	Volume Pumped (bbl) 560.0
Estimated Top (ftKb) 16.5	Estimated Bottom Depth (ftKb) 1,400.0	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack) 17.83
Free Water (%)	Density (lb/gal) 11.49	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

### Cement Fluid Additives

Add	Type	Amount	Amount Units	Conc	Conc Unit
Kwik Seal	Lost Circulation Additive	0.25	lbm		
Celloflake	Poyl-e-flake	0.125	lbm		





## Cement Summary

Well Name: TULLY 16-9-36D

### Well Information

Well Information												
API Number 43015500030000				WPC ID 1UT029802		Field Name Wildcat			KB-Grd (ft) 16.50		Original Spud Date 12/7/2012	
Lot	Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36	Township	16 S	Range	9 E	County Emery	State UT	Well Configuration Type Vertical

### Tail Cement

Fluid Type Tail Cement	Fluid Description	Amount (sacks) 440	Class Premium	Volume Pumped (bbl) 94.0
Estimated Top (ftKB) 1,400.0	Estimated Bottom Depth (ftKB) 2,081.0	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack) 5.24
Free Water (%)	Density (lb/gal) 15.60	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

### Cement Fluid Additives

Add	Type	Amount	Amount Units	Conc	Conc Unit
CaCl2	Pellets			2.0	%
Cellophane Flakes	Polyflake	0.125	lbm		

### Displacement

Fluid Type Displacement	Fluid Description	Amount (sacks)	Class	Volume Pumped (bbl) 310.0
Estimated Top (ftKB)	Estimated Bottom Depth (ftKB)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
Free Water (%)	Density (lb/gal) 9.20	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)



## Cement Summary

Well Name: TULLY 16-9-36D

### Well Information

Well Information												
API Number				WPC ID			Field Name			KB-Grd (ft)	Original Spud Date	
43015500030000				1UT029802			Wildcat			16.50	12/7/2012	
Lot	Quarter 1	Quarter 2	Quarter 3	Quarter 4	Section	Township	Township...	Range	Rng E/...	County	State	Well Configuration Type
	NW	NW			36		16 S		9 E	Emery	UT	Vertical

### Wellbores

Wellbore Name	Profile Type	Kick Off Depth (ftKB)		
Original Hole	Vertical			
Section Des	Size (in)	Act Top (ftKB)	Act Btm (ftKB)	
Conductor	26	16.5	96.5	
Surface	17 1/2	96.5	2,122.0	
Intermediate	12 1/4	2,122.0	6,315.0	
Production	8 1/2	6,315.0	7,480.0	

### Wellheads

Type	Install Date

### Intermediate Casing Cement

Cementing Start Date		Cementing End Date	Wellbore
12/23/2012 03:30		12/23/2012 06:00	Original Hole
Evaluation Method		Cement Evaluation Results	
Comment			

### Stage #1

Top Depth (ftKB)	Bottom Depth (ftKB)	Full Return?	Vol Cement Ret (bbl)	Top Plug?	Bottom Plug?
3,296.0	6,294.2	Yes	0.0	No	Yes
Initial Pump Rate (bbl/min)	Final Pump Rate (bbl/min)	Avg Pump Rate (bbl/min)	Final Pump Pressure (psi)	Plug Bump Pressure (psi)	
6	3	6	500.0		
Pipe Reciprocated?	Reciprocation Stroke Length (ft)	Reciprocation Rate (spm)	Pipe Rotated?	Pipe RPM (rpm)	
No			No		
Tagged Depth (ftKB)	Tag Method	Depth Plug Drilled Out To (ftKB)	Drill Out Diameter (in)	Drill Out Date	

### Preflush

Fluid Type	Fluid Description	Amount (sacks)	Class	Volume Pumped (bbl)
Preflush	Water		Water	10.0
Estimated Top (ftKB)	Estimated Bottom Depth (ftKB)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
Free Water (%)	Density (lb/gal)	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)
	8.30			

### Lead Cement

Fluid Type	Fluid Description	Amount (sacks)	Class	Volume Pumped (bbl)
Lead Cement	Lead cement slurry	200	EconoCem	75.0
Estimated Top (ftKB)	Estimated Bottom Depth (ftKB)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
3,296.0	4,874.0	0.0	2.15	11.96
Free Water (%)	Density (lb/gal)	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)
	12.20			

### Tail Cement

Fluid Type	Fluid Description	Amount (sacks)	Class	Volume Pumped (bbl)
Tail Cement	Tail slurry	350	ExtendaCem	80.0
Estimated Top (ftKB)	Estimated Bottom Depth (ftKB)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
4,874.0	6,294.2	0.0	1.32	5.79
Free Water (%)	Density (lb/gal)	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)
	14.20			

### Displacement

Fluid Type	Fluid Description	Amount (sacks)	Class	Volume Pumped (bbl)
Displacement			9.2 Waterbase mud	457.0
Estimated Top (ftKB)	Estimated Bottom Depth (ftKB)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
Free Water (%)	Density (lb/gal)	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)
	9.20			

### Stage #2

Top Depth (ftKB)	Bottom Depth (ftKB)	Full Return?	Vol Cement Ret (bbl)	Top Plug?	Bottom Plug?
16.5	3,296.0	No	45.0	No	Yes
Initial Pump Rate (bbl/min)	Final Pump Rate (bbl/min)	Avg Pump Rate (bbl/min)	Final Pump Pressure (psi)	Plug Bump Pressure (psi)	
6	1	6	650.0		2,000.0
Pipe Reciprocated?	Reciprocation Stroke Length (ft)	Reciprocation Rate (spm)	Pipe Rotated?	Pipe RPM (rpm)	
No			No		
Tagged Depth (ftKB)	Tag Method	Depth Plug Drilled Out To (ftKB)	Drill Out Diameter (in)	Drill Out Date	



# Cement Summary

Well Name: TULLY 16-9-36D

## Well Information

API Number 43015500030000					WPC ID 1UT029802		Field Name Wildcat			KB-Grd (ft) 16.50	Original Spud Date 12/7/2012	
Lot	Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36	Township	Township ...	Range	Rng E/ ... 9 E	County Emery	State UT	Well Configuration Type Vertical

## Preflush

Fluid Type Preflush	Fluid Description	Amount (sacks) 0	Class Water	Volume Pumped (bbl) 10.0
Estimated Top (ft/B)	Estimated Bottom Depth (ft/B)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
Free Water (%)	Density (lb/gal) 8.30	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

## Lead Cement

Fluid Type Lead Cement	Fluid Description	Amount (sacks) 820	Class EconoCem	Volume Pumped (bbl) 315.0
Estimated Top (ft/B) 16.5	Estimated Bottom Depth (ft/B) 2,852.0	Percent Excess Pumped (%) 0.0	Yield (ft <sup>3</sup> /sack) 2.15	Mix H2O Ratio (gal/sack) 11.92
Free Water (%)	Density (lb/gal) 12.20	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

## Tail Cement

Fluid Type Tail Cement	Fluid Description	Amount (sacks) 100	Class	Volume Pumped (bbl) 25.0
Estimated Top (ft/B) 2,852.0	Estimated Bottom Depth (ft/B) 3,296.0	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack) 1.32	Mix H2O Ratio (gal/sack) 5.79
Free Water (%)	Density (lb/gal) 14.20	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

## Displacement

Fluid Type Displacement	Fluid Description	Amount (sacks) 0	Class	Volume Pumped (bbl) 241.0
Estimated Top (ft/B)	Estimated Bottom Depth (ft/B)	Percent Excess Pumped (%)	Yield (ft <sup>3</sup> /sack)	Mix H2O Ratio (gal/sack)
Free Water (%)	Density (lb/gal) 9.20	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)





## Cement Summary

Well Name: TULLY 16-9-36D

### Well Information

API Number 43015500030000				WPC ID 1UT029802		Field Name Wildcat			KB-Grid (ft) 16.50		Original Spud Date 12/7/2012	
Lot	Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36	Township 16 S	Twnshp... Range	Rng E/... 9 E	County Emery	State UT	Well Configuration Type Vertical	

### Wellbores

Wellbore Name Original Hole	Profile Type Vertical	Kick Off Depth (ftKB)		
Section Des	Size (in)	Act Top (ftKB)	Act Btm (ftKB)	
Conductor	26	16.5	96.5	
Surface	17 1/2	96.5	2,122.0	
Intermediate	12 1/4	2,122.0	6,315.0	
Production	8 1/2	6,315.0	7,480.0	

### Wellheads

Type	Install Date
------	--------------

### Production Casing Cement

Cementing Start Date	Cementing End Date	Wellbore
1/2/2013 15:30	1/2/2013 18:30	Original Hole
Evaluation Method	Cement Evaluation Results	
Volume Calculations	Cement at surface	
Comment		

### Stage #1

Top Depth (ftKB) 16.5	Bottom Depth (ftKB) 6,194.0	Full Return? No	Vol Cement Ret (bbl) 35.0	Top Plug? No	Bottom Plug? No
Initial Pump Rate (bbl/min) 5	Final Pump Rate (bbl/min) 5	Avg Pump Rate (bbl/min) 5	Final Pump Pressure (psi) 430.0	Plug Bump Pressure (psi)	
Pipe Reciprocated? No	Reciprocation Stroke Length (ft)	Reciprocation Rate (spm)	Pipe Rotated? No	Pipe RPM (rpm)	
Tagged Depth (ftKB)	Tag Method	Depth Plug Drilled Out To (ftKB)	Drill Out Diameter (in)	Drill Out Date	

### Lead Cement

Fluid Type Lead Cement	Fluid Description	Amount (sacks) 435	Class Econocem	Volume Pumped (bbl) 158.0
Estimated Top (ftKB) 0.0	Estimated Bottom Depth (ftKB) 6,194.0	Percent Excess Pumped (%) 0.0	Yield (ft <sup>3</sup> /sack) 2.05	Mix H2O Ratio (gal/sack) 11.08
Free Water (%)	Density (lb/gal) 12.50	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

### Stage #2

Top Depth (ftKB) 6,194.0	Bottom Depth (ftKB) 7,460.0	Full Return? No	Vol Cement Ret (bbl) 5	Top Plug? No	Bottom Plug? No
Initial Pump Rate (bbl/min) 5	Final Pump Rate (bbl/min) 5	Avg Pump Rate (bbl/min) 5	Final Pump Pressure (psi) 1,600.0	Plug Bump Pressure (psi) 2,150.0	
Pipe Reciprocated? No	Reciprocation Stroke Length (ft)	Reciprocation Rate (spm)	Pipe Rotated? No	Pipe RPM (rpm)	
Tagged Depth (ftKB)	Tag Method	Depth Plug Drilled Out To (ftKB)	Drill Out Diameter (in)	Drill Out Date	

### Tail Cement

Fluid Type Tail Cement	Fluid Description	Amount (sacks) 230	Class Extenda-Cem	Volume Pumped (bbl) 51.0
Estimated Top (ftKB) 4,375.0	Estimated Bottom Depth (ftKB) 6,404.0	Percent Excess Pumped (%) 35.0	Yield (ft <sup>3</sup> /sack) 1.25	Mix H2O Ratio (gal/sack) 5.46
Free Water (%)	Density (lb/gal) 14.20	Plastic Viscosity (cp)	Thickening Time (hr)	1st Compressive Strength (psi)

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-52222
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> WHITING OIL & GAS CORPORATION		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		<b>8. WELL NAME and NUMBER:</b> Tully 16-9-36D
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0860 FNL 0856 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		<b>9. API NUMBER:</b> 43015500030000
<b>PHONE NUMBER:</b> 303 390-4095 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WILDCAT
<b>COUNTY:</b> EMERY		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION	<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <b>2/28/2013</b>  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input type="checkbox"/> DRILLING REPORT Report Date:
OTHER: <span style="border: 1px solid black; padding: 2px;">Status update 022013</span>				

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Tag fluid @ 750'. Pump 2000 gals HCl (47.6 bbls) into perfs @ 6772-84'. Pressure @ 4028#. Displace w/45 bbls 7% KCl, ISIP 3726#, 5 mins 4379#, 10 mins 3414#, 15 mins 3375#. FL @ 6300', swab 44.5 bbls in 11 runs. Well on vac. Swab back 11 bbls in 4 runs, all water. Con't swabbing. On 6th run lost swab tools in hole. 2 mandrels 2', jars 40.5", sinker bar 9'10.5", Fish stuck in XN nipple. Will leave tool in XN until pkr/tbg pulled fr/hole. Con't swabbing started seeing small oil shows. WP=0. No FL, no fluid recovery. Prep to perf Torrey, Release pkr, caught fish, POOH. RIH, set CIBP @ 6765#, press test to 2000#. RIH w/ 3 1/8" guns, 6 spf, perf Torrey B @ 6714-29'. POOH, RIH with BHA, set pkr to 2000#. Pump DFIT @ 3.5 bpm, Avg press 3658#. ISIP 3605#, 5 mins 3266#, 10 mins 3189#, 15 mins 3135#. Swab 47 bbls in 8 runs, runs 10 & 11 no fluid. Con't swabbing, got trace of oil.

**Accepted by the  
Utah Division of  
Oil, Gas and Mining**

**FOR RECORD ONLY**

June 18, 2013

<b>NAME (PLEASE PRINT)</b> Pauleen Tobin	<b>PHONE NUMBER</b> 303 390-4267	<b>TITLE</b> Engineer Tech
<b>SIGNATURE</b> N/A	<b>DATE</b> 6/18/2013	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-52222
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> WHITING OIL & GAS CORPORATION		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		<b>8. WELL NAME and NUMBER:</b> Tully 16-9-36D
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0860 FNL 0856 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		<b>9. API NUMBER:</b> 43015500030000
<b>PHONE NUMBER:</b> 303 390-4095 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WILDCAT
<b>COUNTY:</b> EMERY		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 3/5/2013	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: <span style="border: 1px solid black; padding: 2px;">Status Update Mar 2013</span>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Con't swabbing. WP=0. FL @ 6500'. RD, release pkr, POOH. Well SI pending further economic evaluation.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> July 11, 2013		
<b>NAME (PLEASE PRINT)</b> Pauleen Tobin	<b>PHONE NUMBER</b> 303 390-4267	<b>TITLE</b> Engineer Tech
<b>SIGNATURE</b> N/A	<b>DATE</b> 6/18/2013	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-52222
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well		8. WELL NAME and NUMBER: Tully 16-9-36D
2. NAME OF OPERATOR: WHITING OIL & GAS CORPORATION		9. API NUMBER: 43015500030000
3. ADDRESS OF OPERATOR: 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		9. FIELD and POOL or WILDCAT: WILDCAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0860 FNL 0856 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		COUNTY: EMERY
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION	<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 1/31/2013  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input type="checkbox"/> DRILLING REPORT Report Date:
OTHER: <span style="border: 1px solid black; padding: 2px;">Status Update 01/2013</span>				

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU Svc Unit, BOPE. Roll hole, fluid clean. Run CBL. Perf 7180-7194, 6spf. Press csg to 2000#, held. Pump 500 gals 15% HCl, Over flush w/5bbls, press 4690#, ISIP 3547#, 5 mins 3122#, SI 1 hr. Max press 5060#, Avg press 4792#, Max rate 4.5bpm, Avg rate 2.5 bpm. Open to flow back. Swab back 40 bbls in 8 runs. Con't swabbing 100% wtr. well press @ 400#, SI 24 hrs, PBU. After 36 hrs WP 725#, FL @ 6000'. Caught fluid sample. POOH w/ kill string. RIH, set CIBP @ 7150', dump 2sx cmt on top. POOH, RIH w/4" guns, perf Sinbad @ 6772-84'. POOH. RU BHA latch into sx nipple, EOT 6760'. Press test csg to 200#. Pump DFIT. ISIP 3846#, 5 mins 3370#, 10 mins 3160#, 15 mins 2993#.

**Accepted by the  
Utah Division of  
Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 July 11, 2013

NAME (PLEASE PRINT) Pauleen Tobin	PHONE NUMBER 303 390-4267	TITLE Engineer Tech
SIGNATURE N/A		DATE 6/18/2013



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

**WELL COMPLETION OR RECOMPLETION REPORT AND LOG**

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>ML-52222</b>
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR: <b>Whiting Oil and Gas Corporation</b>		7. UNIT or CA AGREEMENT NAME
3. ADDRESS OF OPERATOR: <b>1700 Broadway Ste 2300 CITY Denver STATE CO ZIP 80290</b>		8. WELL NAME and NUMBER: <b>Tully</b>
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: <b>860 FNL, 856 FWL</b>  AT TOP PRODUCING INTERVAL REPORTED BELOW:  AT TOTAL DEPTH: <b>860 FNL, 856 FWL</b>		9. API NUMBER: <b>4301550003</b>
PHONE NUMBER: <b>(303) 837-1661</b>		10. FIELD AND POOL, OR WILDCAT <b>Wildcat</b>
		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NWNW 36 16S 9E S</b>
		12. COUNTY <b>Emery</b>
		13. STATE <b>UTAH</b>

14. DATE SPUDDED: <b>12/7/2012</b>	15. DATE T.D. REACHED: <b>12/30/2012</b>	16. DATE COMPLETED: <b>3/5/2013</b>	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): <b>5871'GR, 5887'KB</b>
18. TOTAL DEPTH: MD <b>7,480</b> TVD <b>7,480</b>	19. PLUG BACK T.D.: MD <b>6,765</b> TVD <b>6,765</b>	20. IF MULTIPLE COMPLETIONS, HOW MANY? * <b>No</b>		21. DEPTH BRIDGE PLUG SET: MD <b>6,765</b> TVD <b>6,765</b>
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) <b>MICRO,BH COMP/SONIC, CALIPER, TRIPLE COMBO, COMB MAG RES, ISOLATION SCANNER, AI/GR, PTFRM EX</b>			23. WAS WELL CORED? NO <input type="checkbox"/> YES <input checked="" type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

**24. CASING AND LINER RECORD (Report all strings set in well)**

HOLE SIZE	SIZE/GRADE	WEIGHT (LBS.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
26	20 H40	94	0	97				0	
17 1/2	13 3/8 J55	54.5	0	2,081		P/PL 1,510	654	0	
12 1/4	9 5/8 L80	47	0	6,297	3,296	Econo 1,470	495	0	
8 1/2	7 HCL80	29	0	7,460		Econo 665	209	0	

**25. TUBING RECORD**

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

**26. PRODUCING INTERVALS**

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Moenkopi	6,156	6,769	6,156	6,769	6,714 6,729		62	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) Sinbad	6,770	7,176	6,770	7,176	6,772 6,784		73	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(C) Kaibab	7,176	7,326	7,176	7,326	7,180 7,194		50	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

**28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.**

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
7180-7194	500gals 15% acid
6772-6784	2000gals 15% HCl acid

**29. ENCLOSED ATTACHMENTS:**

☒ ELECTRICAL/MECHANICAL LOGS      ☐ GEOLOGIC REPORT      ☐ DST REPORT      ☐ DIRECTIONAL SURVEY  
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION      ☒ CORE ANALYSIS      ☒ OTHER: Cement Rpts

**30. WELL STATUS:**

**SI**

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 2/26/2013		TEST DATE: 3/3/2013		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 0	WATER – BBL: 3	PROD. METHOD: swab
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 0	WATER – BBL: 3	INTERVAL STATUS: SI

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED: 2/4/2013		TEST DATE: 2/11/2013		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 0		WATER – BBL: 3		PROD. METHOD: swab			
CHOKE SIZE:	TBG. PRESS.	CSG PRESS.	API GRAVITY	BTU – GAS		GAS/OIL RATIO		24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 0		WATER – BBL: 3		INTERVAL STATUS: SI	

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED: 1/18/2013		TEST DATE: 1/19/2013		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 0	WATER – BBL: 14	PROD. METHOD: swab
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 0	WATER – BBL: 14	INTERVAL STATUS: SI

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				Dakota	1,891
				Morrison	2,647
				Summerville	3,270
				Curtis	3,534
				Entrada	3,714
				Carmel	4,291
				Navajo	4,925
				Kayenta	5,350
				Wingate	5,476
				Chinle	5,841

## 35. ADDITIONAL REMARKS (Include plugging procedure)

Additional Log tops: Moenkopi 6156', Sinbad 6770', Kaibab 7176', White Rim SS 7326'. Well SI pending further evaluation.

## 36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Pauleen TobinTITLE Engineer TechSIGNATURE DATE 8/21/13

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940



**HALLIBURTON****Cementing Job Summary****The Road to Excellence Starts with Safety**

<b>Sold To #:</b> 366960	<b>Ship To #:</b> 2968516	<b>Quote #:</b>	<b>Sales Order #:</b> 900070117
<b>Customer:</b> WHITING OIL & GAS CORP - EBUS		<b>Customer Rep:</b>	
<b>Well Name:</b> Tully		<b>Well #:</b> Tully 16-9-36D	<b>API/UWI #:</b>
<b>Field:</b>	<b>City (SAP):</b> EMERY	<b>County/Parish:</b> Emery	<b>State:</b> Utah
<b>Contractor:</b> FRONTIER		<b>Rig/Platform Name/Num:</b> 2	
<b>Job Purpose:</b> Cement Surface Casing			
<b>Well Type:</b> Development Well		<b>Job Type:</b> Cement Surface Casing	
<b>Sales Person:</b> FLING, MATTHEW		<b>Srv Supervisor:</b> MCKEE, RALPH	<b>MBU ID Emp #:</b> 259268

**Job Personnel**

HES Emp Name	Exp Hrs	Emp #	HES Emp Name	Exp Hrs	Emp #	HES Emp Name	Exp Hrs	Emp #
ARMENDARIZ, MIGUEL Angel	3.5	517738	GILES, JAMES W	3.5	522124	GOODRICH, BENJAMIN Franklin	3.5	481342
MCKEE, RALPH R	3.5	259268	SHIFLETT, JESSE Amos	3.5	469551			

**Equipment**

HES Unit #	Distance-1 way	HES Unit #	Distance-1 way	HES Unit #	Distance-1 way	HES Unit #	Distance-1 way
10261036	130 mile	10574660C	130 mile	10982756	130 mile	10994445	130 mile
11108220	130 mile	11127544	130 mile	11259879	130 mile	11287531	130 mile
11410666	130 mile						

**Job Hours**

Date	On Location Hours	Operating Hours	Date	On Location Hours	Operating Hours	Date	On Location Hours	Operating Hours
<b>TOTAL</b>			Total is the sum of each column separately					

**Job****Job Times**

Formation Name					Date		Time	Time Zone
Formation Depth (MD)		Top	Bottom		Called Out	11 - Dec - 2012	16:00	MST
Form Type		BHST		On Location	11 - Dec - 2012	20:30	MST	
Job depth MD		2750. ft	Job Depth TVD		Job Started	12 - Dec - 2012	11:19	MST
Water Depth		Wk Ht Above Floor		Job Completed	12 - Dec - 2012	15:50	MST	
Perforation Depth (MD)		From	To		Departed Loc	12 - Dec - 2012	18:00	MST

**Well Data**

Description	New / Used	Max pressure psig	Size in	ID in	Weight lbm/ft	Thread	Grade	Top MD ft	Bottom MD ft	Top TVD ft	Bottom TVD ft
17 1/2" Open Hole				17.5					2750.		
13 3/8" Surface Casing	Unknown		13.375	12.615	61.	8 RD	J-55		2750.		

**Sales/Rental/3<sup>rd</sup> Party (HES)**

Description	Qty	Qty uom	Depth	Supplier
CENTRALIZER-13 3/8"-CSG-17 1/2"-HINGED	5	EA		
SHOE,FLOAT,13-3/8 8RD,2-3/4 SUPER SEAL	1	EA		
CLR,FLT,13-3/8 8RD 48-72PPF,2-3/4	1	EA		



**HALLIBURTON****Cementing Job Summary**

Tools and Accessories													
Type	Size	Qty	Make	Depth	Type	Size	Qty	Make	Depth	Type	Size	Qty	Make
Guide Shoe					Packer					Top Plug			
Float Shoe					Bridge Plug					Bottom Plug			
Float Collar					Retainer					SSR plug set			
Insert Float										Plug Container			
Stage Tool										Centralizers			

Miscellaneous Materials															
Gelling Agt			Conc		Surfactant			Conc		Acid Type		Qty		Conc	%
Treatment Fld			Conc		Inhibitor			Conc		Sand Type		Size		Qty	

Fluid Data													
Stage/Plug #: 1													
Fluid #	Stage Type	Fluid Name	Qty	Qty uom	Mixing Density lbm/gal	Yield ft <sup>3</sup> /sk	Mix Fluid Gal/sk	Rate bbl/min	Total Mix Fluid Gal/sk				
1	Fresh Water		3.00	bbl	8.34	.0	.0	.0					
2	SUPER FLUSH		30.00	bbl	9.2	.0	.0	.0					
	68 lbm/bbl	HALLIBURTON SUPER FLUSH (100003639)											
3	Fresh Water		15.00	bbl	8.33	.0	.0	.0					
4	Rockies LT	ROCKIES LT - SBM (430481)	1070.0	sacks	11.49	2.94	17.83		17.83				
	0.125 lbm	POLY-E-FLAKE (101216940)											
	0.25 lbm	KWIK SEAL, SK (100064010)											
	17.83 Gal	FRESH WATER											
5	PREMIUM CEMENT	CMT - PREMIUM - CLASS G, 94 LB SK (100003685)	440.0	sacks	15.6	1.2	5.24		5.24				
	94 lbm	CMT - PREMIUM - CLASS G REG OR TYPE V, BULK (100003685)											
	2 %	CALCIUM CHLORIDE - HI TEST PELLET (100005053)											
	0.125 lbm	POLY-E-FLAKE (101216940)											
	5.238 Gal	FRESH WATER											
6	Displacement Fluid		310.00	bbl	8.34	.0	.0	.0					
7	PREMIUM CEMENT	CMT - PREMIUM - CLASS G, 94 LB SK (100003685)		sacks	15.8	1.17	5.02		5.02				
	94 lbm	CMT - PREMIUM - CLASS G REG OR TYPE V, BULK (100003685)											
	2 %	CALCIUM CHLORIDE - HI TEST PELLET (100005053)											
	5.019 Gal	FRESH WATER											

Calculated Values				Pressures				Volumes			
Displacement		Shut In: Instant		Lost Returns		Cement Slurry		Pad			
Top Of Cement		5 Min		Cement Returns		Actual Displacement		Treatment			
Frac Gradient		15 Min		Spacers		Load and Breakdown		Total Job			

Rates															
Circulating		Mixing		Displacement		Avg. Job									
Cement Left In Pipe		Amount	40 ft	Reason	Shoe Joint										
Frac Ring # 1 @		ID		Frac ring # 2 @		ID		Frac Ring # 3 @		ID		Frac Ring # 4 @		ID	

The Information Stated Herein Is Correct	Customer Representative Signature
--	-----------------------------------



**HALLIBURTON****Cementing Job Summary****The Road to Excellence Starts with Safety**

<b>Sold To #:</b> 366960	<b>Ship To #:</b> 2968516	<b>Quote #:</b>	<b>Sales Order #:</b> 900081431
<b>Customer:</b> WHITING OIL & GAS CORP - EBUS		<b>Customer Rep:</b> Betts, Benjamin	
<b>Well Name:</b> Tully	<b>Well #:</b> 16-9-36D	<b>API/UWI #:</b>	
<b>Field:</b> HOOK	<b>City (SAP):</b> EMERY	<b>County/Parish:</b> Carbon	<b>State:</b> Utah
<b>Contractor:</b> FRONTIER	<b>Rig/Platform Name/Num:</b> 2		
<b>Job Purpose:</b> Cement Multiple Stages			
<b>Well Type:</b> Development Well	<b>Job Type:</b> Cement Multiple Stages		
<b>Sales Person:</b> FLING, MATTHEW	<b>Srv Supervisor:</b> CARPENTER, LANCE	<b>MBU ID Emp #:</b> 461737	

**Job Personnel**

HES Emp Name	Exp Hrs	Emp #	HES Emp Name	Exp Hrs	Emp #	HES Emp Name	Exp Hrs	Emp #
ARCHULETA, ZACK	0.0	529108	CARPENTER, LANCE S	0.0	461737	CLARK, SHAUN Cameron	0.0	527195
GAMBLES, BRAYDEN Kade	0.0	469413	SLAUGH, CODY B	0.0	104465	SMITH, BRET George	0.0	529662

**Equipment**

HES Unit #	Distance-1 way	HES Unit #	Distance-1 way	HES Unit #	Distance-1 way	HES Unit #	Distance-1 way

**Job Hours**

Date	On Location Hours	Operating Hours	Date	On Location Hours	Operating Hours	Date	On Location Hours	Operating Hours

<b>TOTAL</b>	Total is the sum of each column separately							
--------------	--	--	--	--	--	--	--	--

**Job****Job Times**

333								Date	Time	Time Zone
Formation Name										
Formation Depth (MD)		Top			Bottom		Called Out	22 - Dec - 2012	16:00	MST
Form Type				BHST			On Location	22 - Dec - 2012	23:45	MST
Job depth MD		6299. ft		Job Depth TVD		6299. ft	Job Started	23 - Dec - 2012	03:50	MST
Water Depth				Wk Ht Above Floor		4. ft	Job Completed	23 - Dec - 2012	11:20	MST
Perforation Depth (MD)		From			To		Departed Loc	23 - Dec - 2012	13:00	MST

**Well Data**

Description	New / Used	Max pressure psig	Size in	ID in	Weight lbm/ft	Thread	Grade	Top MD ft	Bottom MD ft	Top TVD ft	Bottom TVD ft
12 1/4" Open Hole				12.25				2750.	7050.		
13 3/8" Surface Casing	Unknown		13.375	12.615	61.		J-55	.	2750.		
9 5/8" Intermediate Casing	Unknown		9.625	8.681	47.	LTC	L-80	.	7050.		
Multiple Stage Cementer	Used		9.625	8.681	47.	8 RD (LT&C)	K-55	.	3950.		

**Sales/Rental/3<sup>rd</sup> Party (HES)**

Description	Qty	Qty uom	Depth	Supplier
SHOE,FLT,9-5/8 8RD,2-3/4 SUPER SEAL	1	EA		
CLR,FLT,9-5/8 8RD 29.3-40PPF,2-3/4	1	EA		
CENTRALIZER-9-5/8"-CSG-12 1/4"-HINGED	52	EA		

Summit  
Version:

Monday, July 22, 2013 14:37:00

RECEIVED: Aug. 21, 2013



**HALLIBURTON****Cementing Job Summary**

Description										Qty	Qty uom	Depth	Supplier
COLLAR-STOP-9 5/8"-FRICTION-HINGED										1	EA		
KIT,HALL WELD-A										3	EA		
PLUG SET,FREE FALL,9-5/8 8RD&BUTRS										1	EA		
Tools and Accessories													
Type	Size	Qty	Make	Depth	Type	Size	Qty	Make	Depth	Type	Size	Qty	Make
Guide Shoe					Packer					Top Plug			
Float Shoe					Bridge Plug					Bottom Plug			
Float Collar					Retainer					SSR plug set			
Insert Float										Plug Container			
Stage Tool										Centralizers			
Miscellaneous Materials													
Gelling Agt			Conc		Surfactant			Conc		Acid Type			Qty
Treatment Fld			Conc		Inhibitor			Conc		Sand Type			Size
													Conc %
													Qty
													%
Fluid Data													
Stage/Plug #: 1													
Fluid #	Stage Type	Fluid Name				Qty	Qty uom	Mixing Density lbm/gal	Yield ft <sup>3</sup> /sk	Mix Fluid Gal/sk	Rate bbl/min	Total Mix Fluid Gal/sk	
1	Fresh Water					10.00	bbl	8.33	.0	.0	.0		
2	EconoCem	ECONOCEM (TM) SYSTEM (452992)				200.0	sacks	12.2	2.15	11.96		11.96	
	0.125 lbm	POLY-E-FLAKE (101216940)											
	0.2 %	SUPER CBL, 50 LB PAIL (100003668)											
	11.96 Gal	FRESH WATER											
3	EXTENDACEM	EXTENDACEM (TM) SYSTEM (452981)				450.0	sacks	14.2	1.32	5.79		5.79	
	0.2 %	SUPER CBL, 50 LB PAIL (100003668)											
	0.3 %	HALAD(R)-413, 50 LB (100003738)											
	5.79 Gal	FRESH WATER											
4	Displacement Fluid					457.00	bbl	9.4			.0		
Stage/Plug #: 2													
Fluid #	Stage Type	Fluid Name				Qty	Qty uom	Mixing Density uom	Yield uom	Mix Fluid uom	Rate uom	Total Mix Fluid uom	
1	Fresh Water					10.00	bbl	8.33	.0	.0	.0		
2	EconoCem	ECONOCEM (TM) SYSTEM (452992)				820.0	sacks	12.2	2.15	11.96		11.96	
	0.125 lbm	POLY-E-FLAKE (101216940)											
	0.2 %	SUPER CBL, 50 LB PAIL (100003668)											
	11.96 Gal	FRESH WATER											
3	Displacement Fluid					241.00	bbl	8.6	.0	.0	.0		
Calculated Values		Pressures		Volumes									
Displacement		Shut In: Instant		Lost Returns		Cement Slurry		Pad					
Top Of Cement		5 Min		Cement Returns		Actual Displacement		Treatment					
Frac Gradient		15 Min		Spacers		Load and Breakdown		Total Job					
Rates													
Circulating		Mixing		Displacement		Avg. Job							
Cement Left In Pipe		Amount	40 ft	Reason	Shoe Joint								
Frac Ring # 1 @		ID	Frac ring # 2 @	ID	Frac Ring # 3 @		ID	Frac Ring # 4 @		ID			
The Information Stated Herein Is Correct					Customer Representative Signature								

Summit  
Version:

Monday, July 22, 2013 14:37:00

RECEIVED: Aug. 21, 2013



**HALLIBURTON****Cementing Job Summary***The Road to Excellence Starts with Safety*

Sold To #: 366960	Ship To #: 2968516	Quote #:	Sales Order #: 900098975
Customer: WHITING OIL & GAS CORP - EBUS		Customer Rep: Betts, Benjamin	
Well Name: TULLY	Well #: 16-9-36D	API/UWI #:	
Field: HOOK	City (SAP): EMERY	County/Parish: Carbon	State: Utah
Contractor: FRONTIER	Rig/Platform Name/Num: 2		
Job Purpose: Cement Production Casing			
Well Type: Development Well	Job Type: Cement Production Casing		
Sales Person: FLING, MATTHEW	Srv Supervisor: DEAN, MARK	MBU ID Emp #: 454214	

**Job Personnel**

HES Emp Name	Exp Hrs	Emp #	HES Emp Name	Exp Hrs	Emp #	HES Emp Name	Exp Hrs	Emp #
DEAN, MARK Christophe	0.0	454214	FUCHS, JUSTIN Mark	0.0	509124	GILES, JAMES W	0.0	522124
HUNTER, SAMUEL David	0.0	479669						

**Equipment**

HES Unit #	Distance-1 way	HES Unit #	Distance-1 way	HES Unit #	Distance-1 way	HES Unit #	Distance-1 way

**Job Hours**

Date	On Location Hours	Operating Hours	Date	On Location Hours	Operating Hours	Date	On Location Hours	Operating Hours

TOTAL Total is the sum of each column separately**Job**

Formation Name	Top	Bottom	Called Out	Date	Time	Time Zone
Formation Depth (MD)			On Location	01 - Jan - 2013	23:00	MST
Form Type		BHST	Job Started	02 - Jan - 2013	06:30	MST
Job depth MD	7702. ft	Job Depth TVD	Job Completed	02 - Jan - 2013	15:20	MST
Water Depth		Wk Ht Above Floor	Deparated Loc	02 - Jan - 2013	17:39	MST
Perforation Depth (MD)	From	To		02 - Jan - 2013	19:45	MST

**Well Data**

Description	New / Used	Max pressure psig	Size in	ID in	Weight lbm/ft	Thread	Grade	Top MD ft	Bottom MD ft	Top TVD ft	Bottom TVD ft
8 1/2" Open Hole				8.5				6294.	7702.		
7" Intermediate Casing	Unknown		7.	6.184	29.	LTC	HCP110	.	7702.		
9 5/8" Intermediate Casing	Unknown		9.625	8.681	47.	LTC	L-80	.	6294.		

**Sales/Rental/3<sup>rd</sup> Party (HES)**

Description	Qty	Qty uom	Depth	Supplier
PLUG,CMTG,TOP,7,HWE,5.66 MIN/6.54 MAX CS	1	EA		

**Tools and Accessories**

Type	Size	Qty	Make	Depth	Type	Size	Qty	Make	Depth	Type	Size	Qty	Make
Guide Shoe					Packer					Top Plug			
Float Shoe					Bridge Plug					Bottom Plug			
Float Collar					Retainer					SSR plug set			
Insert Float										Plug Container			
Stage Tool										Centralizers			

Summit  
Version:

Sunday, January 13, 2013 16:35:00

RECEIVED: Aug. 21, 2013

**HALLIBURTON****Cementing Job Summary**

Miscellaneous Materials																
Gelling Agt		Conc		Surfactant		Conc		Acid Type		Qty		Conc	%			
Treatment Fld		Conc		Inhibitor		Conc		Sand Type		Size		Qty				
Fluid Data																
Stage/Plug #: 1																
Fluid #	Stage Type	Fluid Name			Qty	Qty uom	Mixing Density lbm/gal	Yield ft <sup>3</sup> /sk	Mix Fluid Gal/sk	Rate bbl/min	Total Mix Fluid Gal/sk					
1	Fresh Water					bbl	8.33	.0	.0	.0						
2	Super Flush					bbl	10.	2.55	15.84	.0						
	110 lbm/bbl	HALLIBURTON SUPER FLUSH (100003639)														
	15.84 gal/bbl	FRESH WATER														
3	Fresh Water					bbl	8.33	.0	.0	.0						
4	Econocem	ECONOCEM (TM) SYSTEM (452992)				sacks	12.5	2.05	11.08		11.08					
	0.4 %	HR-800, 50 LB SACK (101619742)														
	0.125 lbm	POLY-E-FLAKE (101216940)														
	11.08 Gal	FRESH WATER														
5	EXTENDACEM	EXTENDACEM (TM) SYSTEM (452981)				sacks	14.2	1.25	5.46		5.46					
	0.3 %	HR-5, 50 LB SK (100005050)														
	0.125 lbm	POLY-E-FLAKE (101216940)														
	5.46 Gal	FRESH WATER														
6	Displacement Fluid					bbl	10.5			.0						
Calculated Values		Pressures			Volumes											
Displacement		Shut In: Instant				Lost Returns				Cement Slurry				Pad		
Top Of Cement		5 Min				Cement Returns				Actual Displacement				Treatment		
Frac Gradient		15 Min				Spacers				Load and Breakdown				Total Job		
Rates																
Circulating		Mixing				Displacement				Avg. Job						
Cement Left In Pipe		Amount	40 ft	Reason		Shoe Joint										
Frac Ring # 1 @		ID		Frac ring # 2 @		ID		Frac Ring # 3 @		ID		Frac Ring # 4 @		ID		
The Information Stated Herein Is Correct						Customer Representative Signature										

Summit  
Version:

Sunday, January 13, 2013 16:35:00

RECEIVED: Aug. 21, 2013



Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah

4301550003

360 FAL 850 FAL

NOONW 36 163 9E



### CMS-300 CONVENTIONAL PLUG ANALYSIS

RECEIVED

AUG 26 2013

DIV. OF OIL, GAS & MINING

CL File No.: DEN-120167

Date: 5/31/2013

Analyst(s): JC

NOOD 36 163 9E

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg (md)	Kair (md)				Oil	Water		
									% Pore Volume			
1w	6677.00	ambient	0.64	***	***	***	***	***	6.6	76.4	2.701	
1w	6677.00	2000	***	***	***	***	***	***				(2)
2w	6680.00	ambient	1.47	***	***	***	***	***	5.1	80.2	2.758	(5)
3	6684.20	ambient	2.83	***	***	***	***	***	4.7	61.7	2.735	(5)
4	6686.10	ambient	3.09	***	***	***	***	***	18.2	48.2	2.699	
4	6686.10	2000	2.65	.011	.030	48.56	3.53E+13	1.90E+03			2.699	(1)
5	6688.50	ambient	1.54	***	***	***	***	***	19.7	43.4	2.711	
5	6688.50	2000	0.65	.00001	.0001	376.36	1.83E+18	3.45E+05			2.711	
6	6689.50	ambient	1.03	***	***	***	***	***	10.3	83.1	2.703	
6	6689.50	2000	***	***	***	***	***	***				(2)
7	6698.30	ambient	1.29	***	***	***	***	***	3.7	73.5	2.716	
7	6698.30	2000	***	***	***	***	***	***				(2)
8w	6701.00	ambient	0.72	***	***	***	***	***	3.4	72.5	2.714	(5)
9w	6702.00	ambient	2.31	***	***	***	***	***	10.3	60.0	2.727	
9w	6702.00	2000	0.87	.015	.040	50.40	4.56E+13	2.25E+03			2.727	(1)
10	6704.40	ambient	0.62	***	***	***	***	***	11.9	77.0	2.702	
10	6704.40	2000	***	***	***	***	***	***				(2)
11w	6707.00	ambient	0.71	***	***	***	***	***	6.1	92.1	2.712	
11w	6707.00	2000	0.43	.0002	.001	251.34	2.27E+17	1.26E+05			2.712	(1)
12	6710.50	ambient	0.88	***	***	***	***	***	3.2	91.4	2.725	
12	6710.50	2000	***	***	***	***	***	***				(2)
13	6711.60	ambient	0.54	***	***	***	***	***	1.6	82.3	2.739	
13	6711.60	2000	***	***	***	***	***	***				(2)
14	6712.50	ambient	1.68	***	***	***	***	***	12.8	38.9	2.717	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg (md)	Kair (md)				Oil	Water		
									% Pore Volume			
14	6712.50	2000	1.56	.001	.004	142.89	1.04E+16	2.93E+04			2.717	
15	6713.60	ambient	2.29	***	***	***	***	***	21.8	33.6	2.727	
15	6713.60	2000	1.77	.0004	.002	189.79	4.99E+16	6.16E+04			2.727	
16	6714.60	ambient	3.40	***	***	***	***	***	20.5	31.8	2.711	
16	6714.60	2000	2.64	.001	.005	126.17	5.21E+15	2.11E+04			2.711	
17	6715.50	ambient	3.44	***	***	***	***	***	26.4	24.5	2.721	
17	6715.50	2000	3.08	.009	.027	62.45	1.28E+14	3.67E+03			2.721	
18	6716.10	ambient	2.77	***	***	***	***	***	39.0	15.4	2.730	
18	6716.10	2000	2.53	.001	.004	143.07	1.05E+16	2.94E+04			2.730	
20	6716.50	ambient	3.28	***	***	***	***	***	40.4	13.0	2.714	
20	6716.50	2000	3.11	.002	.007	114.68	3.08E+15	1.65E+04			2.714	
21	6717.00	ambient	4.19	***	***	***	***	***	45.5	10.4	2.690	
21	6717.00	2000	3.64	.001	.007	117.26	3.48E+15	1.75E+04			2.690	
22	6717.70	ambient	3.50	***	***	***	***	***	48.0	12.0	2.718	
22	6717.70	2000	3.00	.001	.005	129.95	6.13E+15	2.28E+04			2.718	
23	6718.70	ambient	2.77	***	***	***	***	***	15.9	27.4	2.680	
23	6718.70	2000	2.60	.001	.004	141.26	9.75E+15	2.85E+04			2.680	
24	6719.60	ambient	1.43	***	***	***	***	***	28.6	45.2	2.735	
24	6719.60	2000	0.29	.0001	.001	336.99	1.03E+18	2.60E+05			2.735	
25	6720.50	ambient	1.65	***	***	***	***	***	17.5	33.1	2.746	
25	6720.50	2000	1.10	.0004	.002	184.47	4.28E+16	5.73E+04			2.746	(1)
26	6721.50	ambient	1.89	***	***	***	***	***	18.7	28.4	2.742	
26	6721.50	2000	1.14	.251	.284	3.10	8.94E+12	7.32E+03			2.742	(1)
27	6722.50	ambient	1.94	***	***	***	***	***	6.0	36.0	2.743	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
27	6722.50	2000	1.70	.002	.009	105.80	2.00E+15	1.34E+04			2.743	(1)
28	6723.50	ambient	2.50	***	***	***	***	***	29.9	25.1	2.716	
28	6723.50	2000	2.00	.001	.005	138.68	8.80E+15	2.71E+04			2.716	
29	6724.50	ambient	3.45	***	***	***	***	***	46.2	12.2	2.703	
29	6724.50	2000	3.35	.001	.005	135.79	7.81E+15	2.56E+04			2.703	
30	6725.40	ambient	3.05	***	***	***	***	***	40.1	16.5	2.728	
30	6725.40	2000	2.89	.001	.005	136.22	7.95E+15	2.58E+04			2.728	
31v	6725.70	ambient	3.02	***	***	***	***	***	39.0	19.7	2.711	
31v	6725.70	2000	2.37	.001	.004	150.3	1.4E+16	3.4E+04			2.711	
32v	6725.70	ambient	3.46	***	***	***	***	***	34.2	19.6	2.704	
32v	6725.70	2000	3.04	.001	.003	164.6	2.3E+16	4.3E+04			2.704	
34	6726.50	ambient	2.87	***	***	***	***	***	37.3	19.0	2.727	
34	6726.50	2000	2.61	.001	.003	161.96	2.08E+16	4.07E+04			2.727	
35	6726.90	ambient	3.27	***	***	***	***	***	42.4	12.6	2.729	
35	6726.90	2000	2.86	.001	.003	169.73	2.69E+16	4.59E+04			2.729	
36	6728.00	ambient	4.03	***	***	***	***	***	41.0	15.5	2.717	
36	6728.00	2000	3.70	.001	.006	120.35	4.00E+15	1.87E+04			2.717	
38	6728.60	ambient	4.03	***	***	***	***	***	46.0	10.4	2.697	
38	6728.60	2000	3.79	.001	.005	130.0	6.1E+15	2.3E+04			2.697	
39	6729.60	ambient	2.83	***	***	***	***	***	37.5	15.0	2.732	
39	6729.60	2000	2.45	.001	.004	152.32	1.48E+16	3.46E+04			2.732	
40	6730.40	ambient	2.88	***	***	***	***	***	41.4	15.0	2.699	
40	6730.40	2000	2.26	.001	.005	136.55	8.08E+15	2.60E+04			2.699	
41	6731.00	ambient	2.30	***	***	***	***	***	25.5	27.7	2.732	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
41	6731.00	2000	1.89	.006	.020	72.60	2.74E+14	5.25E+03			2.732	(1)
42	6732.00	ambient	1.77	***	***	***	***	***	28.9	29.9	2.742	
42	6732.00	2000	0.46	.0001	.001	341.12	1.09E+18	2.67E+05			2.742	
43	6733.40	ambient	2.60	***	***	***	***	***	31.2	28.2	2.683	
43	6733.40	2000	2.56	.0004	.002	184.65	4.34E+16	5.80E+04			2.683	
44	6734.20	ambient	3.32	***	***	***	***	***	46.0	12.7	2.673	
44	6734.20	2000	3.25	.001	.003	170.32	2.74E+16	4.63E+04			2.673	
45	6735.60	ambient	2.66	***	***	***	***	***	21.8	29.9	2.705	
45	6735.60	2000	2.17	.225	.338	12.08	2.61E+12	1.90E+03			2.705	(1)
46	6736.50	ambient	2.46	***	***	***	***	***	33.4	26.0	2.695	
46	6736.50	2000	2.18	.001	.005	106.22	2.02E+15	1.35E+04			2.695	
47	6737.85	ambient	2.22	***	***	***	***	***	6.4	52.3	2.731	
47	6737.85	2000	2.03	.094	.151	15.69	1.49E+13	5.52E+03			2.731	(1)
48	6738.50	ambient	1.60	***	***	***	***	***	8.8	46.5	2.731	
48	6738.50	2000	1.51	.00003	.0002	239.96	1.79E+17	1.13E+05			2.731	
49	6739.30	ambient	2.36	***	***	***	***	***	16.7	38.2	2.702	
49	6739.30	2000	1.92	.001	.005	108.12	2.22E+15	1.41E+04			2.702	
50	6741.75	ambient	1.52	***	***	***	***	***	6.7	58.7	2.739	
50	6741.75	2000	1.14	.006	.017	56.50	7.86E+13	2.91E+03			2.739	(1)
51	6743.60	ambient	0.82	***	***	***	***	***	3.2	59.4	2.747	
51	6743.60	2000	0.75	.0001	.0003	207.51	8.14E+16	7.77E+04			2.747	
52	6744.60	ambient	1.27	***	***	***	***	***	4.0	67.6	2.757	
52	6744.60	2000	0.85	.010	.017	20.81	3.13E+14	1.11E+04			2.757	(1)
53	6745.65	ambient	1.11	***	***	***	***	***	0.0	84.5	2.741	



### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
53	6745.65	2000	***	***	***	***	***	***				(2)
54	6746.50	ambient	1.06	***	***	***	***	***	0.0	87.3	2.727	(5)
56	6748.50	ambient	2.28	***	***	***	***	***	5.9	72.7	2.737	(5)
60	6755.70	ambient	2.14	***	***	***	***	***	3.1	55.9	2.735	(5)
61	6759.00	ambient	2.35	***	***	***	***	***	15.6	78.6	2.745	(5)
62	6761.00	ambient	1.08	***	***	***	***	***	13.6	41.1	2.717	
62	6761.00	2000	***	***	***	***	***	***				(2)
63	6761.80	ambient	2.29	***	***	***	***	***	35.1	15.1	2.709	
63	6761.80	2000	1.76	.0002	.001	168.73	2.61E+16	4.54E+04			2.709	
64	6762.70	ambient	4.44	***	***	***	***	***	44.8	10.4	2.753	
64	6762.70	2000	4.30	.0003	.001	145.29	1.15E+16	3.07E+04			2.753	
65	6763.50	ambient	3.39	***	***	***	***	***	26.2	27.5	3.033	
65	6763.50	2000	3.01	.053	.067	6.77	2.69E+12	4.72E+02			3.033	(1)
66	6763.85	ambient	2.46	***	***	***	***	***	32.8	18.5	2.725	
66	6763.85	2000	2.16	.0002	.001	154.70	1.61E+16	3.61E+04			2.725	
67	6765.40	ambient	2.80	***	***	***	***	***	40.3	18.5	2.708	
67	6765.40	2000	2.73	.0004	.002	138.93	8.87E+15	2.72E+04			2.708	
68	6766.90	ambient	2.26	***	***	***	***	***	37.1	20.9	2.753	
68	6766.90	2000	2.01	.0002	.001	154.41	1.60E+16	3.60E+04			2.753	
69	6767.50	ambient	1.98	***	***	***	***	***	38.8	38.5	2.762	
69	6767.50	2000	1.76	1.31	1.35	0.65	2.43E+11	1.05E+03			2.762	(1)
70	6768.00	ambient	2.24	***	***	***	***	***	28.8	18.8	2.700	
70	6768.00	2000	2.07	.0001	.0003	210.98	8.98E+16	8.14E+04			2.700	
71	6768.50	ambient	3.03	***	***	***	***	***	27.2	27.6	2.751	



### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
71	6768.50	2000	2.95	.001	.003	117.20	3.46E+15	1.74E+04			2.751	
73	6769.40	ambient	3.69	***	***	***	***	***	36.0	17.9	2.741	
73	6769.40	2000	3.56	.0002	.001	166.91	2.48E+16	4.45E+04			2.741	
74	6769.90	ambient	3.72	***	***	***	***	***	30.7	22.3	2.731	
74	6769.90	2000	3.38	.001	.003	117.98	3.57E+15	1.77E+04			2.731	
76	6770.90	ambient	3.26	***	***	***	***	***	22.6	25.4	2.753	
76	6770.90	2000	2.33	1.21	1.28	1.10	1.15E+10	4.54E+01			2.753	(1)
77	6771.60	ambient	3.38	***	***	***	***	***	29.7	21.8	2.734	
77	6771.60	2000	3.10	.006	.018	70.45	2.37E+14	4.90E+03			2.734	(1)
78	6773.00	ambient	5.70	***	***	***	***	***	45.8	8.5	2.778	
78	6773.00	2000	5.35	.0003	.001	142.90	1.04E+16	2.94E+04			2.778	
79	6773.25	ambient	6.41	***	***	***	***	***	48.2	6.6	2.761	
79	6773.25	2000	5.81	.001	.004	150.1	1.4E+16	3.3E+04			2.761	
80	6773.25	ambient	7.03	***	***	***	***	***	48.6	7.5	2.767	
80	6773.25	2000	6.97	.001	.005	132.1	6.8E+15	2.4E+04			2.767	
81	6773.50	ambient	9.21	***	***	***	***	***	49.4	4.6	2.832	
81	6773.50	2000	8.67	.001	.005	101.90	1.63E+15	1.22E+04			2.832	
83	6774.50	ambient	7.70	***	***	***	***	***	47.2	5.4	2.767	
83	6774.50	2000	7.49	.003	.010	97.14	1.26E+15	1.08E+04			2.767	
84	6775.00	ambient	7.79	***	***	***	***	***	44.6	5.3	2.763	
84	6775.00	2000	7.71	.005	.017	76.88	3.70E+14	6.05E+03			2.763	
85	6775.50	ambient	4.37	***	***	***	***	***	42.1	9.6	2.735	
85	6775.50	2000	4.26	.0004	.002	184.45	4.30E+16	5.74E+04			2.735	
86	6776.00	ambient	4.02	***	***	***	***	***	26.8	20.4	2.715	



### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
86	6776.00	2000	3.97	.002	.009	102.03	1.63E+15	1.22E+04			2.715	
87	6776.50	ambient	3.75	***	***	***	***	***	37.2	11.0	2.706	
87	6776.50	2000	3.50	.001	.003	166.18	2.39E+16	4.34E+04			2.706	
88	6777.50	ambient	1.70	***	***	***	***	***	38.1	18.5	2.697	
88	6777.50	2000	1.21	.0001	.001	285.30	4.38E+17	1.73E+05			2.697	
89	6779.00	ambient	1.53	***	***	***	***	***	39.2	6.8	2.709	
89	6779.00	2000	1.10	.00005	.0003	220.80	1.14E+17	9.10E+04			2.709	
90	6779.50	ambient	2.09	***	***	***	***	***	38.4	5.1	2.692	
90	6779.50	2000	1.68	.0002	.001	165.14	2.32E+16	4.29E+04			2.692	
91	6780.10	ambient	1.96	***	***	***	***	***	41.9	4.2	2.697	
91	6780.10	2000	1.09	.0002	.001	242.31	1.86E+17	1.15E+05			2.697	
92	6780.50	ambient	2.16	***	***	***	***	***	38.3	5.7	2.693	
92	6780.50	2000	1.38	.0002	.002	221.11	1.15E+17	9.19E+04			2.693	
93	6781.10	ambient	2.03	***	***	***	***	***	50.4	5.2	2.689	
93	6781.10	2000	1.30	.0002	.001	239.64	1.76E+17	1.12E+05			2.689	
94	6781.50	ambient	1.98	***	***	***	***	***	46.9	5.3	2.681	
94	6781.50	2000	1.61	.0002	.001	232.18	1.48E+17	1.03E+05			2.681	
95	6781.95	ambient	2.11	***	***	***	***	***	44.2	5.0	2.679	
95	6781.95	2000	1.38	.0002	.001	236.62	1.64E+17	1.08E+05			2.679	
96	6782.60	ambient	2.39	***	***	***	***	***	45.7	4.3	2.680	
96	6782.60	2000	1.69	.0002	.002	227.41	1.33E+17	9.79E+04			2.680	
97	6782.90	ambient	2.42	***	***	***	***	***	37.6	4.7	2.684	
97	6782.90	2000	2.17	.003	.012	88.72	7.74E+14	8.58E+03			2.684	(1)
98	6784.20	ambient	2.84	***	***	***	***	***	48.2	5.1	2.694	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
98	6784.20	2000	2.12	.0001	.001	256.29	2.54E+17	1.35E+05			2.694	
99	6785.50	ambient	2.19	***	***	***	***	***	46.0	5.2	2.692	
99	6785.50	2000	1.11	.0001	.001	299.80	5.68E+17	1.96E+05			2.692	
100	6786.50	ambient	2.47	***	***	***	***	***	46.0	4.9	2.692	
100	6786.50	2000	1.62	.0001	.001	293.41	5.17E+17	1.88E+05			2.692	
101	6787.80	ambient	2.39	***	***	***	***	***	42.4	8.6	2.700	
101	6787.80	2000	1.29	.0001	.001	320.92	8.10E+17	2.32E+05			2.700	
102	6788.30	ambient	1.79	***	***	***	***	***	26.7	25.2	2.704	
102	6788.30	2000	0.56	.0001	.001	346.25	1.18E+18	2.78E+05			2.704	
103	6789.00	ambient	1.68	***	***	***	***	***	8.1	35.1	2.712	
103	6789.00	2000	1.16	.0001	.001	366.50	1.58E+18	3.20E+05			2.712	
104	6790.00	ambient	1.63	***	***	***	***	***	5.1	39.6	2.708	
104	6790.00	2000	***	***	***	***	***	***				(2)
105	6791.60	ambient	2.89	***	***	***	***	***	40.6	42.5	2.721	(5)
106	6792.10	ambient	1.23	***	***	***	***	***	2.7	45.5	2.716	
106	6792.10	2000	***	***	***	***	***	***				(2)
107w	6792.60	ambient	1.20	***	***	***	***	***	13.9	36.1	2.716	
107w	6792.60	2000	***	***	***	***	***	***				(2)
108	6793.60	ambient	1.48	***	***	***	***	***	8.1	44.1	2.720	
108	6793.60	2000	***	***	***	***	***	***				(2)
109	6794.50	ambient	1.40	***	***	***	***	***	2.1	47.8	2.725	
109	6794.50	2000	***	***	***	***	***	***				(2)
110	6795.00	ambient	1.74	***	***	***	***	***	0.0	46.3	2.726	
110	6795.00	2000	0.21	.00004	.0004	423.16	3.16E+18	4.46E+05			2.726	



Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
111	6796.10	ambient	2.42	***	***	***	***	***	11.0	32.4	2.739	
111	6796.10	2000	2.31	.0001	.0004	232.37	1.52E+17	1.05E+05			2.739	
112	6797.00	ambient	2.69	***	***	***	***	***	11.0	32.8	2.734	
112	6797.00	2000	1.65	.0001	.001	284.02	4.34E+17	1.72E+05			2.734	
113	6797.45	ambient	2.39	***	***	***	***	***	7.7	32.0	2.762	
113	6797.45	2000	1.27	.0001	.001	295.47	5.33E+17	1.90E+05			2.762	
114w	6798.35	ambient	1.62	***	***	***	***	***	1.4	41.9	2.732	
114w	6798.35	2000	***	***	***	***	***	***				(2)
115w	6798.90	ambient	1.59	***	***	***	***	***	1.9	38.1	2.729	
115w	6798.90	2000	***	***	***	***	***	***				(2)
116w	6799.70	ambient	1.15	***	***	***	***	***	2.1	32.2	2.717	
116w	6799.70	2000	***	***	***	***	***	***				(2)
117w	6801.30	ambient	1.01	***	***	***	***	***	4.8	69.3	2.714	
117w	6801.30	2000	***	***	***	***	***	***				(2)
118w	6803.70	ambient	1.09	***	***	***	***	***	4.2	39.7	2.710	
118w	6803.70	2000	***	***	***	***	***	***				(2)
119w	6805.50	ambient	2.23	***	***	***	***	***	17.8	29.6	2.706	
119w	6805.50	2000	1.51	.001	.005	109.21	2.36E+15	1.45E+04			2.706	(1)
120w	6808.65	ambient	1.20	***	***	***	***	***	2.1	42.8	2.724	(5)
121w	6810.55	ambient	1.19	***	***	***	***	***	4.3	36.5	2.723	
121w	6810.55	2000	1.08	.0001	.0004	224.36	1.35E+17	1.03E+05			2.723	
122w	6812.60	ambient	1.88	***	***	***	***	***	21.0	6.5	2.719	
122w	6812.60	2000	1.80	.002	.007	96.25	1.82E+15	1.60E+04			2.719	
123w	6813.55	ambient	1.74	***	***	***	***	***	27.9	6.2	2.721	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg (md)	Kair (md)				Oil	Water		
									% Pore Volume			
123w	6813.55	2000	1.69	.005	.015	73.36	2.88E+14	5.37E+03			2.721	(1)
124w	6814.35	ambient	1.28	***	***	***	***	***	39.5	17.6	2.704	
124w	6814.35	2000	1.18	.0005	.002	135.66	7.80E+15	2.56E+04			2.704	(1)
125	6815.60	ambient	1.61	***	***	***	***	***	33.1	6.7	2.708	
125	6815.60	2000	1.56	.0004	.002	132.63	6.86E+15	2.41E+04			2.708	
126	6816.80	ambient	1.54	***	***	***	***	***	1.7	28.2	2.725	
126	6816.80	2000	0.87	.973	1.09	2.26	8.05E+11	2.60E+03			2.725	(1)
127	6819.50	ambient	2.90	***	***	***	***	***	5.4	28.1	2.704	
127	6819.50	2000	1.90	.080	.157	24.60	2.95E+12	7.86E+02			2.704	(1)
128w	6821.45	ambient	2.45	***	***	***	***	***	5.5	37.4	2.700	
128w	6821.45	2000	2.36	.0003	.002	144.22	1.09E+16	3.00E+04			2.700	(1)
129	6815.60	ambient	2.39	***	***	***	***	***	6.8	39.9	2.706	
129	6822.45	2000	2.26	.001	.002	131.72	6.58E+15	2.36E+04			2.706	
130	6823.55	ambient	1.52	***	***	***	***	***	3.5	35.6	2.703	
130	6823.55	2000	1.05	.00002	.0002	254.20	2.40E+17	1.30E+05			2.703	
131	6824.65	ambient	1.26	***	***	***	***	***	0.0	34.9	2.723	(5)
132w	6825.50	ambient	0.74	***	***	***	***	***	0.0	44.1	2.798	
132w	6825.50	2000	***	***	***	***	***	***				(2)
133	6827.00	ambient	1.10	***	***	***	***	***	0.0	71.8	2.721	
133	6827.00	2000	0.76	.706	.750	1.39	1.56E+12	4.01E+03			2.721	(1)
134	6828.10	ambient	1.26	***	***	***	***	***	0.0	69.2	2.722	
134	6828.10	2000	0.96	.001	.004	111.05	2.59E+15	1.52E+04			2.722	
135w	6829.70	ambient	1.11	***	***	***	***	***	4.5	71.7	2.750	
135w	6829.70	2000	0.23	.00001	.0001	349.79	1.24E+18	2.85E+05			2.750	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
136	6830.70	ambient	1.13	***	***	***	***	***	0.4	84.3	2.716	(2)
136	6830.70	2000	***	***	***	***	***	***			2.716	
137	6831.00	ambient	1.06	***	***	***	***	***	0.0	73.1	2.730	(2)
137	6831.00	2000	0.45	.00002	.0001	273.83	3.57E+17	1.57E+05			2.730	
139w	6833.00	ambient	0.80	***	***	***	***	***	2.1	29.8	2.732	(2)
139w	6833.00	2000	***	***	***	***	***	***				
140w	6834.50	ambient	1.50	***	***	***	***	***	3.0	30.8	2.751	(2)
140w	6834.50	2000	0.97	.0005	.002	131.54	6.57E+15	2.36E+04			2.751	
141w	6835.80	ambient	1.08	***	***	***	***	***	1.0	40.5	2.740	(2)
141w	6835.80	2000	***	***	***	***	***	***				
142w	6837.50	ambient	1.03	***	***	***	***	***	0.0	38.0	2.749	(2)
142w	6837.50	2000	***	***	***	***	***	***				
143w	6838.50	ambient	0.95	***	***	***	***	***	0.0	69.0	2.750	(2)
143w	6838.50	2000	***	***	***	***	***	***				
144w	6840.50	ambient	1.23	***	***	***	***	***	3.1	43.7	2.757	(2)
144w	6840.50	2000	***	***	***	***	***	***				
146w	6841.50	ambient	3.59	***	***	***	***	***	22.0	3.9	2.730	(2)
146w	6841.50	2000	3.38	.001	.003	131.03	6.42E+15	2.34E+04			2.730	
147w	6842.65	ambient	5.19	***	***	***	***	***	25.7	2.1	2.709	(2)
147w	6842.65	2000	4.92	.004	.008	36.89	3.37E+15	6.15E+04			2.709	
148w	6843.00	ambient	4.15	***	***	***	***	***	15.5	3.7	2.706	(2)
148w	6843.00	2000	3.79	.005	.015	74.63	3.13E+14	5.59E+03			2.706	
149w	6843.50	ambient	4.36	***	***	***	***	***	11.7	5.0	2.704	(2)
149w	6843.50	2000	3.90	.002	.008	101.27	1.57E+15	1.20E+04			2.704	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
150w	6844.50	ambient	1.22	***	***	***	***	***	0.0	42.7	2.714	
150w	6844.50	2000	0.93	.0001	.001	207.19	9.00E+15	8.59E+03			2.714	
151w	6845.55	ambient	1.38	***	***	***	***	***	0.0	47.3	2.738	(5)
152w	6846.90	ambient	1.35	***	***	***	***	***	0.0	38.1	2.747	
152w	6846.90	2000	***	***	***	***	***	***				(2)
153w	6847.40	ambient	1.22	***	***	***	***	***	0.0	38.6	2.736	
153w	6847.40	2000	0.90	.0001	.001	359.07	1.41E+18	3.02E+05			2.736	
155	6848.60	ambient	1.85	***	***	***	***	***	1.9	36.6	2.738	
155	6848.60	2000	***	***	***	***	***	***				(2)
156w	6849.90	ambient	1.38	***	***	***	***	***	2.4	40.0	2.741	(5)
157w	6851.15	ambient	2.13	***	***	***	***	***	29.1	5.1	2.754	
157w	6851.15	2000	1.67	.0003	.001	143.88	1.08E+16	2.98E+04			2.754	
158w	6851.50	ambient	4.48	***	***	***	***	***	35.7	2.5	2.792	
158w	6851.50	2000	4.12	.001	.003	119.90	3.91E+15	1.84E+04			2.792	
159	6850.20	ambient	1.12	***	***	***	***	***	29.0	9.5	2.732	
159	6850.20	2000	1.04	.00004	.0002	239.78	1.76E+17	1.12E+05			2.732	
160	6850.50	ambient	1.03	***	***	***	***	***	6.8	26.1	2.728	
160	6850.50	2000	0.91	.00004	.0003	231.40	1.47E+17	1.03E+05			2.728	
161	6850.90	ambient	1.34	***	***	***	***	***	3.8	53.1	2.755	
161	6850.90	2000	1.19	.0002	.001	181.82	4.03E+16	5.64E+04			2.755	(1)
162	6851.60	ambient	1.21	***	***	***	***	***	33.9	22.2	2.698	
162	6851.60	2000	***	***	***	***	***	***				(2)
163	6852.10	ambient	5.48	***	***	***	***	***	18.2	4.3	2.699	
163	6852.10	2000	5.01	.003	.010	90.31	8.61E+14	9.05E+03			2.699	



### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg (md)	Kair (md)				Oil	Water		
									% Pore Volume			
164	6852.50	ambient	1.93	***	***	***	***	***	1.4	58.8	2.739	(5)
165	6852.90	ambient	1.85	***	***	***	***	***	28.5	7.5	2.716	
165	6852.90	2000	1.45	.0001	.0005	194.52	5.72E+16	6.58E+04			2.716	
166	6853.40	ambient	0.64	***	***	***	***	***	0.0	58.7	2.760	
166	6853.40	2000	***	***	***	***	***	***				(2)
167	6854.45	ambient	1.65	***	***	***	***	***	0.0	81.9	2.766	
167	6854.45	2000	***	***	***	***	***	***				(2)
168	6855.10	ambient	1.35	***	***	***	***	***	7.3	67.5	2.783	
168	6855.10	2000	0.83	.0004	.002	189.27	4.96E+16	6.16E+04			2.783	(1)
169	6856.10	ambient	0.89	***	***	***	***	***	19.5	31.6	2.758	
169	6856.10	2000	***	***	***	***	***	***				(2)
170	6856.70	ambient	2.88	***	***	***	***	***	31.4	8.5	2.715	
170	6856.70	2000	2.59	.0002	.001	159.77	1.93E+16	3.94E+04			2.715	
171	6857.60	ambient	1.82	***	***	***	***	***	35.1	14.3	2.772	
171	6857.60	2000	0.90	.0001	.001	335.87	1.02E+18	2.61E+05			2.772	
172	6857.95	ambient	1.19	***	***	***	***	***	19.9	57.6	2.767	
172	6857.95	2000	***	***	***	***	***	***				(2)
173	6858.90	ambient	2.29	***	***	***	***	***	5.0	57.8	2.803	
173	6858.90	2000	1.87	.0000	.0001	329.73	9.36E+17	2.49E+05			2.803	
174	6860.10	ambient	1.26	***	***	***	***	***	0.0	50.1	2.752	(5)
175	6861.10	ambient	1.54	***	***	***	***	***	0.0	35.6	2.769	
175	6861.10	2000	0.43	.0001	.001	357.73	1.39E+18	3.01E+05			2.769	
176	6862.20	ambient	1.40	***	***	***	***	***	3.0	70.0	2.786	
176	6862.20	2000	1.25	.0001	.001	333.49	1.02E+18	2.62E+05			2.786	



### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
177	6863.90	ambient	3.81	***	***	***	***	***	29.9	3.8	2.837	
177	6863.90	2000	***	***	***	***	***	***				(2)
178	6864.60	ambient	5.23	***	***	***	***	***	38.5	9.8	2.814	
178	6864.60	2000	4.57	.001	.003	171.81	2.93E+16	4.80E+04			2.814	
179	6865.00	ambient	4.61	***	***	***	***	***	28.7	17.6	2.820	
179	6865.00	2000	3.91	.0002	.002	213.78	9.69E+16	8.46E+04			2.820	
180	6866.10	ambient	2.55	***	***	***	***	***	18.2	16.8	2.830	
180	6866.10	2000	***	***	***	***	***	***				(2)
181	6867.50	ambient	2.22	***	***	***	***	***	7.8	27.8	2.850	
181	6867.50	2000	2.11	.003	.010	88.62	7.68E+14	8.55E+03			2.850	(1)
182	6870.10	ambient	2.96	***	***	***	***	***	1.1	53.1	2.854	
182	6870.10	2000	2.78	.002	.009	102.91	1.71E+15	1.25E+04			2.854	(1)
183	6872.50	ambient	2.22	***	***	***	***	***	0.0	32.9	2.846	
183	6872.50	2000	1.62	.0001	.001	266.36	3.08E+17	1.46E+05			2.846	
184	6876.10	ambient	2.17	***	***	***	***	***	0.0	28.5	2.838	
184	6876.10	2000	2.13	.054	.115	29.46	5.56E+12	9.86E+02			2.838	(1)
185	6879.50	ambient	0.93	***	***	***	***	***	0.0	35.6	2.809	
185	6879.50	2000	0.13	.0001	.001	314.25	7.28E+17	2.21E+05			2.809	
186	6883.20	ambient	2.19	***	***	***	***	***	0.0	63.8	2.730	
186	6883.20	2000	1.32	.002	.008	110.29	2.50E+15	1.49E+04			2.730	(1)
187	6894.40	ambient	0.82	***	***	***	***	***	0.0	66.4	2.737	
187	6894.40	2000	***	***	***	***	***	***				(2)
188	6912.00	ambient	1.03	***	***	***	***	***	0.0	91.0	2.766	(5)
189	6917.90	ambient	0.46	***	***	***	***	***	0.0	92.9	2.756	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
189	6917.90	2000	***	***	***	***	***	***				(2)
190	6925.50	ambient	0.46	***	***	***	***	***	0.0	91.2	2.773	
190	6925.50	2000	***	***	***	***	***	***				(2)
191	6934.50	ambient	0.92	***	***	***	***	***	0.0	86.5	2.744	
191	6934.50	2000	***	***	***	***	***	***				(2)
192	6940.90	ambient	2.30	***	***	***	***	***	0.0	88.4	2.740	
192	6940.90	2000	1.58	.007	.023	68.76	2.08E+14	4.61E+03			2.740	(1)
193	6943.50	ambient	0.55	***	***	***	***	***	4.4	83.3	2.731	
193	6943.50	2000	***	***	***	***	***	***				(2)
194	6961.60	ambient	1.52	***	***	***	***	***	0.0	83.1	2.726	
194	6961.60	2000	1.33	.077	.117	13.59	9.98E+13	2.63E+04			2.726	(1)
195	6978.50	ambient	2.58	***	***	***	***	***	25.0	44.9	2.728	
195	6978.50	2000	1.39	1.64	1.73	1.01	4.68E+11	2.64E+03			2.728	(1)
196	6979.50	ambient	1.39	***	***	***	***	***	6.2	81.4	2.728	
196	6979.50	2000	1.24	.058	.095	17.20	1.45E+14	3.39E+04			2.728	(1)
197	6982.80	ambient	0.68	***	***	***	***	***	0.0	87.3	2.752	
197	6982.80	2000	***	***	***	***	***	***				(2)
198	6990.20	ambient	0.67	***	***	***	***	***	0.0	87.2	2.734	
198	6990.20	2000	0.15	.00003	.0002	245.66	2.02E+17	1.20E+05			2.734	
199	6992.30	ambient	0.63	***	***	***	***	***	0.0	82.1	2.750	
199	6992.30	2000	***	***	***	***	***	***				(2)
200	6996.50	ambient	0.50	***	***	***	***	***	0.0	92.6	2.748	
200	6996.50	2000	***	***	***	***	***	***				(2)
201	6998.30	ambient	1.36	***	***	***	***	***	0.0	87.7	2.765	



Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
201	6998.30	2000	***	***	***	***	***	***				(2)
202	7002.50	ambient	0.83	***	***	***	***	***	0.0	82.9	2.766	
202	7002.50	2000	***	***	***	***	***	***				(2)
203	7004.50	ambient	0.67	***	***	***	***	***	0.0	89.0	2.753	
203	7004.50	2000	***	***	***	***	***	***				(2)
204	7013.10	ambient	0.68	***	***	***	***	***	0.0	82.9	2.757	
204	7013.10	2000	***	***	***	***	***	***				(2)
205	7015.50	ambient	0.59	***	***	***	***	***	0.0	86.2	2.781	
205	7015.50	2000	***	***	***	***	***	***				(2)
206	7028.50	ambient	1.08	***	***	***	***	***	0.0	85.6	2.755	
206	7028.50	2000	***	***	***	***	***	***				(2)
207	7029.30	ambient	0.64	***	***	***	***	***	0.0	90.5	2.751	
207	7029.30	2000	***	***	***	***	***	***				(2)
208	7074.10	ambient	1.53	***	***	***	***	***	0.0	89.9	2.753	
208	7074.10	2000	***	***	***	***	***	***				(2)
209	7076.00	ambient	1.03	***	***	***	***	***	0.0	86.5	2.770	
209	7076.00	2000	***	***	***	***	***	***				(2)
210A	7178.50	ambient	4.86	***	***	***	***	***	0.0	34.8	2.803	
210A	7178.50	2000	4.07	.001	.006	121.96	4.34E+15	1.94E+04			2.803	
211	7180.15	ambient	10.57	***	***	***	***	***	0.0	32.0	2.793	
211	7180.15	2000	10.28	.385	.635	13.31	4.53E+11	5.55E+02			2.793	(1)
212	7182.70	ambient	4.23	***	***	***	***	***	0.0	39.0	2.698	
212	7182.70	2000	3.59	.0002	.002	231.71	1.53E+17	1.07E+05			2.698	
213	7184.90	ambient	9.63	***	***	***	***	***	0.0	18.8	2.801	



### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
213	7184.90	2000	9.15	.160	.252	14.03	7.18E+11	3.72E+02			2.801	
214	7186.10	ambient	12.57	***	***	***	***	***	0.0	22.0	2.833	
214	7186.10	2000	12.02	.168	.311	20.76	7.70E+11	4.21E+02			2.833	
215A	7188.65	ambient	3.02	***	***	***	***	***	0.0	41.0	2.805	
215A	7188.65	2000	2.50	.0003	.002	208.61	8.69E+16	8.18E+04			2.805	
216	7189.80	ambient	3.79	***	***	***	***	***	0.0	48.3	2.810	
216	7189.80	2000	3.30	.0004	.002	185.76	4.54E+16	5.97E+04			2.810	
217	7194.00	ambient	2.85	***	***	***	***	***	0.0	45.9	2.700	
217	7194.00	2000	2.73	.0002	.001	258.79	2.72E+17	1.39E+05			2.700	
218	7196.20	ambient	4.16	***	***	***	***	***	0.0	36.9	2.790	
218	7196.20	2000	3.79	.0004	.003	177.42	3.47E+16	5.18E+04			2.790	
219A	7198.40	ambient	5.08	***	***	***	***	***	0.0	26.4	2.764	
219A	7198.40	2000	4.95	.001	.006	118.76	3.72E+15	1.80E+04			2.764	
220	7200.50	ambient	4.18	***	***	***	***	***	0.0	38.9	2.840	
220	7200.50	2000	3.93	.0005	.003	172.39	2.92E+16	4.78E+04			2.840	
221	7202.05	ambient	5.37	***	***	***	***	***	0.0	38.3	2.847	
221	7202.05	2000	4.86	.002	.007	118.79	3.72E+15	1.80E+04			2.847	
222	7204.00	ambient	4.90	***	***	***	***	***	0.0	38.8	2.846	
222	7204.00	2000	4.69	.001	.007	117.21	3.50E+15	1.76E+04			2.846	
223	7206.00	ambient	3.41	***	***	***	***	***	0.0	29.1	2.849	
223	7206.00	2000	3.14	.036	.084	35.94	4.96E+13	5.74E+03			2.849	
224	7207.30	ambient	3.72	***	***	***	***	***	0.0	41.3	2.821	
224	7207.30	2000	3.65	.002	.008	111.24	2.62E+15	1.53E+04			2.821	
225	7212.00	ambient	6.44	***	***	***	***	***	0.0	30.9	2.837	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg (md)	Kair (md)				Oil	Water		
									% Pore Volume			
225	7212.00	2000	5.11	.001	.006	124.60	4.86E+15	2.05E+04			2.817	
226	7212.55	ambient	5.65	***	***	***	***	***	0.0	20.9	2.809	
226	7212.55	2000	5.23	.003	.013	87.96	7.37E+14	8.38E+03			2.809	
227	7212.00	ambient	4.48	***	***	***	***	***	0.0	24.3	2.817	
227	7212.00	2000	***	***	***	***	***	***				(2)
228	7215.40	ambient	5.57	***	***	***	***	***	0.0	26.8	2.827	
228	7215.40	2000	5.21	.002	.009	103.28	1.74E+15	1.26E+04			2.827	
229	7218.00	ambient	4.94	***	***	***	***	***	0.0	28.0	2.849	
229	7218.00	2000	4.48	.002	.010	99.93	1.29E+15	1.02E+04			2.849	
230	7221.20	ambient	3.59	***	***	***	***	***	0.0	34.6	2.852	
230	7221.20	2000	3.14	.002	.007	117.45	3.53E+15	1.76E+04			2.852	
231	7222.70	ambient	3.04	***	***	***	***	***	0.0	41.1	2.877	
231	7222.70	2000	2.77	.002	.007	111.70	2.68E+15	1.55E+04			2.877	
232	7227.00	ambient	3.73	***	***	***	***	***	0.0	31.6	2.826	
232	7227.00	2000	3.62	.004	.014	83.86	5.76E+14	7.46E+03			2.826	(1)
233	7229.80	ambient	3.21	***	***	***	***	***	0.0	31.6	2.865	
233	7229.80	2000	2.87	.002	.009	101.41	1.58E+15	1.20E+04			2.865	(1)
234	7232.00	ambient	1.59	***	***	***	***	***	0.0	34.1	2.850	
234	7232.00	2000	1.23	.173	.295	17.26	8.79E+11	5.12E+02			2.850	(1)
235	7235.65	ambient	5.16	***	***	***	***	***	0.0	21.2	2.849	
235	7235.65	2000	4.87	.020	.049	42.86	7.19E+11	4.92E+01			2.849	
236	7238.40	ambient	5.18	***	***	***	***	***	0.0	30.1	2.853	
236	7238.40	2000	4.91	.003	.010	63.57	1.11E+14	1.79E+03			2.853	
237	7241.00	ambient	3.14	***	***	***	***	***	0.0	35.5	2.881	



**CMS-300 CONVENTIONAL PLUG ANALYSIS**

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg (md)	Kair (md)				Oil	Water		
									% Pore Volume			
237	7241.00	2000	***	***	***	***	***	***				(2)
238	7243.70	ambient	4.37	***	***	***	***	***	0.0	22.0	2.848	
238	7243.70	2000	4.29	.004	.011	66.66	3.76E+14	5.53E+03			2.848	
239	7246.70	ambient	5.40	***	***	***	***	***	0.0	18.6	2.842	
239	7246.70	2000	5.01	.194	.323	16.12	2.81E+11	1.80E+02			2.842	(1)
240	7251.40	ambient	5.49	***	***	***	***	***	0.0	26.7	2.852	
240	7251.40	2000	5.37	.007	.022	61.08	1.16E+14	3.50E+03			2.852	
241	7254.00	ambient	3.42	***	***	***	***	***	0.0	21.8	2.868	
241	7254.00	2000	3.14	.0002	.001	180.18	3.86E+16	5.55E+04			2.868	
242	7256.60	ambient	6.33	***	***	***	***	***	0.0	17.1	2.837	
242	7256.60	2000	6.18	.017	.033	26.38	7.73E+12	4.71E+02			2.837	
243	7258.50	ambient	5.78	***	***	***	***	***	0.0	17.6	2.852	
243	7258.50	2000	5.60	.009	.025	57.88	8.94E+13	3.09E+03			2.852	
244	7263.80	ambient	4.57	***	***	***	***	***	0.0	31.0	2.856	
244	7263.80	2000	4.15	.001	.004	114.79	3.07E+15	1.65E+04			2.856	
245	7266.00	ambient	4.57	***	***	***	***	***	0.0	37.5	2.860	
245	7266.00	2000	4.28	.002	.008	88.98	7.79E+14	8.60E+03			2.860	
246	7268.30	ambient	1.93	***	***	***	***	***	0.0	26.0	2.846	(5)
247	7272.00	ambient	1.63	***	***	***	***	***	0.0	15.0	2.838	
247	7272.00	2000	1.28	.00004	.0003	231.27	7.58E+17	5.29E+05			2.838	
248	7275.00	ambient	1.25	***	***	***	***	***	0.0	51.8	2.832	
248	7275.00	2000	0.66	.00001	.0001	319.55	7.86E+17	2.29E+05			2.832	
249	7277.80	ambient	1.23	***	***	***	***	***	0.0	53.9	2.831	
249	7277.80	2000	0.77	.00003	.0002	276.49	2.95E+18	1.25E+06			2.831	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
250	7280.60	ambient	0.43	***	***	***	***	***	0.0	86.3	2.790	
250	7280.60	2000	***	***	***	***	***	***				(2)
251	7283.80	ambient	0.89	***	***	***	***	***	0.0	88.5	2.788	(5)
252	7285.90	ambient	0.30	***	***	***	***	***	0.0	85.7	2.667	(5)
253	7289.70	ambient	0.60	***	***	***	***	***	0.0	85.3	2.740	
253	7289.70	2000	***	***	***	***	***	***				(2)
254	7293.15	ambient	0.66	***	***	***	***	***	0.0	86.8	2.732	
254	7293.15	2000	***	***	***	***	***	***				
255	7295.90	ambient	1.14	***	***	***	***	***	0.0	78.7	2.758	(5)
256	7299.00	ambient	0.32	***	***	***	***	***	0.0	87.5	2.720	(5)
257	7302.10	ambient	0.49	***	***	***	***	***	0.0	86.1	2.741	
257	7302.10	2000	***	***	***	***	***	***				(2)
258	7304.30	ambient	0.68	***	***	***	***	***	0.0	88.2	2.783	(5)
259	7307.00	ambient	1.20	***	***	***	***	***	0.0	54.6	2.724	
259	7307.00	2000	***	***	***	***	***	***				(2)
260A	7310.25	ambient	1.69	***	***	***	***	***	0.0	51.2	2.692	
260A	7310.25	2000	0.91	.0004	.002	192.54	5.60E+16	6.62E+04			2.688	
261	7312.25	ambient	1.99	***	***	***	***	***	0.0	64.9	2.728	
261	7312.25	2000	1.31	.0004	.003	178.13	3.54E+16	5.25E+04			2.728	
262	7314.15	ambient	2.18	***	***	***	***	***	0.0	65.7	2.698	
262	7314.15	2000	1.88	.001	.006	118.57	3.72E+15	1.81E+04			2.698	
263	7316.40	ambient	2.48	***	***	***	***	***	0.0	60.0	2.698	
263	7316.40	2000	2.04	.002	.007	112.54	2.80E+15	1.58E+04			2.698	
264	7318.50	ambient	2.13	***	***	***	***	***	0.0	52.8	2.689	

Whiting Oil and Gas  
Tully 16-9-36D  
Emery County, Utah



CL File No.: DEN-120167  
Date: 5/31/2013  
Analyst(s): JC

### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
264	7318.50	2000	1.54	.039	.108	48.00	4.72E+13	6.08E+03			2.689	
265A	7320.25	ambient	2.23	***	***	***	***	***	0.0	53.3	2.693	
265A	7320.25	2000	1.86	.001	.005	132.57	6.95E+15	2.44E+04			2.693	(1)
266	7324.50	ambient	2.19	***	***	***	***	***	0.0	38.5	2.709	
266	7324.50	2000	1.70	.0004	.002	188.10	4.84E+16	6.13E+04			2.709	
267	7326.40	ambient	3.96	***	***	***	***	***	0.0	53.6	2.708	
267	7326.40	2000	***	***	***	***	***	***				(2)
268	7328.10	ambient	1.97	***	***	***	***	***	0.0	53.8	2.666	
268	7328.10	2000	1.48	.003	.012	90.44	8.59E+14	9.00E+03			2.666	
269A	7330.35	ambient	1.42	***	***	***	***	***	0.0	52.6	2.704	
269A	7330.35	2000	0.95	.001	.004	146.52	1.20E+16	3.13E+04			2.704	
270	7332.25	ambient	1.55	***	***	***	***	***	0.0	53.8	2.669	
270	7332.25	2000	1.06	.001	.004	144.81	1.12E+16	3.04E+04			2.669	
271	7334.15	ambient	1.15	***	***	***	***	***	0.0	38.1	2.712	
271	7334.15	2000	0.56	.001	.003	163.53	2.21E+16	4.19E+04			2.712	
272	7336.05	ambient	1.08	***	***	***	***	***	0.0	33.8	2.715	
272	7336.05	2000	0.37	.001	.004	150.79	1.41E+16	3.38E+04			2.715	
273	7338.00	ambient	1.23	***	***	***	***	***	0.0	37.3	2.688	
273	7338.00	2000	0.96	.001	.004	150.83	1.41E+16	3.38E+04			2.688	
274A	7340.05	ambient	1.37	***	***	***	***	***	0.0	36.8	2.708	
274A	7340.05	2000	0.82	.002	.008	112.42	2.77E+15	1.57E+04			2.708	
275	7342.05	ambient	1.44	***	***	***	***	***	0.0	35.0	2.700	
275	7342.05	2000	0.84	.002	.007	112.96	2.85E+15	1.59E+04			2.700	
276	7344.05	ambient	1.13	***	***	***	***	***	0.0	35.6	2.719	



### CMS-300 CONVENTIONAL PLUG ANALYSIS

Sample Number	Depth (ft)	Net Confining Stress (psig)	Porosity (%)	Permeability		b(air) psi	Beta ft(-1)	Alpha (microns)	Saturation		Grain Density (g/cm3)	Footnote
				Klinkenberg	Kair				Oil	Water		
				(md)	(md)				% Pore Volume			
276	7344.05	2000	0.47	.001	.004	152.33	1.49E+16	3.47E+04			2.719	
277	7346.05	ambient	1.24	***	***	***	***	***	0.0	30.0	2.728	
277	7346.05	2000	0.48	.001	.005	134.53	7.47E+15	2.50E+04			2.728	
278	7348.30	ambient	1.13	***	***	***	***	***	0.0	52.5	2.717	
278	7348.30	2000	***	***	***	***	***	***				(2)
279A	7350.55	ambient	4.25	***	***	***	***	***	0.0	56.2	2.773	
279A	7350.55	2000	3.65	.001	.004	148.07	1.26E+16	3.21E+04			2.773	
280	7352.05	ambient	1.33	***	***	***	***	***	0.0	32.7	2.671	
280	7352.05	2000	0.72	.0005	.003	172.82	2.98E+16	4.82E+04			2.671	
281	7354.10	ambient	1.29	***	***	***	***	***	0.0	31.4	2.695	
281	7354.10	2000	0.75	.002	.008	107.57	2.18E+15	1.40E+04			2.695	
282	7356.10	ambient	1.78	***	***	***	***	***	0.0	46.6	2.677	
282	7356.10	2000	1.10	.100	.123	5.91	8.20E+12	2.67E+03			2.677	(1)
283	7358.10	ambient	1.54	***	***	***	***	***	0.0	59.0	2.691	
283	7358.10	2000	1.08	.001	.006	119.20	3.82E+15	1.82E+04			2.691	

Footnotes :

(1) : Denotes fractured or chipped sample. Permeability and/or porosity may be optimistic.

(2) : Sample permeability below the measurement range of CMS-300 equipment at indicated net confining stress (NCS). Data unavailable.

(3) : Denotes very short sample, porosity may be optimistic due to lack of conformation of boot material to plug surface.

(4) : Sample contains bitumen or other solid hydrocarbon residue.

(5) : Denotes sample unsuitable for measurement at stress. Porosity determined using Archimedes bulk volume at ambient conditions.

Permeability greater than 0.1 mD measured using helium gas. Permeability less than 0.1 mD measured using nitrogen gas. All b values converted to b (air)



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-52222
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL Oil Well		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: WHITING OIL & GAS CORPORATION		8. WELL NAME and NUMBER: Tully 16-9-36D
3. ADDRESS OF OPERATOR: 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		9. API NUMBER: 43015500030000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0860 FNL 0856 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		9. FIELD and POOL or WILDCAT: WILDCAT
		COUNTY: EMERY
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <b>8/21/2013</b>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input checked="" type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Whiting Oil and Gas Corporation requests permission to temporarily abandon this well pending further evaluation.

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

Date: October 30, 2013

By: *D. K. Duff*

NAME (PLEASE PRINT) Pauleen Tobin	PHONE NUMBER 303 390-4267	TITLE Engineer Tech
SIGNATURE N/A		DATE 8/21/2013



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**

**Sundry Conditions of Approval Well Number 43015500030000**

**In accordance with rule R649-3-36, well may be shut-in or temporarily abandoned for 12 consecutive months without approval.**



GARY R. HERBERT  
Governor

SPENCER J. COX  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

June 5, 2014

Certified Mail No. 7003 2260 0003 2358 7158

Mr. John D'Hooge  
Whiting Oil & Gas Corporation  
1700 Broadway Suite 2300  
Denver, CO 80290

43 015 50003  
Tully 16-9-36D  
16S 9E 36

Subject: Extended Shut-in and Temporary Abandon Well Requirements for Fee or State Leases

Dear Mr. John D'Hooge:

As of April 2014, Whiting Oil & Gas Corporation (Whiting) has ten (10) State Lease Wells (see attachment A) that are currently in non-compliance with the requirements for extended shut-in or temporarily abandoned (SI/TA) status. Seven (7) of these wells have previously received notices with nothing being done or shown by Whiting to bring into compliance status.

The Division was preparing to issue Notices of Violation for all wells listed above. However, during the meeting with the Division on June 3, 2014, Whiting verbally noted its plans concerning these wells. Whiting stated that five (5) of the wells will be plugged, one (1) being evaluated for water disposal, one (1) being evaluated for up hole potential, and the remaining three (3) to be returned to production.

Whiting needs to submit individual sundry's for each well, detailing plans and near future timeframe for work to be accomplished. Additionally, the wells that are candidates for plugging need to have a plugging procedure and a scheduled date for PA submitted for approval. All other wells will need to meet the requirements per the rules below.

Wells SI/TA beyond twelve (12) consecutive months requires filing a Sundry Notice (R649-3-36-1). Wells with five (5) years non-activity or non-productivity shall be plugged, unless the Division grants approval for extended shut-in time upon a showing of good cause by the operator (649-3-36-1.3.3). For extended SI/TA consideration the operator shall provide the Utah Division of Oil, Gas & Mining with the following:

1. Reasons for SI/TA of the well (R649-3-36-1.1).
2. The length of time the well is expected to be SI/TA (R649-3-36-1.2), and



Page 2  
Pacific Energy & Mining Company  
June 4, 2014

3. An explanation and supporting data if necessary, for showing the well has integrity, meaning that the casing, cement, equipment condition, static fluid level, pressure, existence or absence of Underground Sources of Drinking Water and other factors do not make the well a risk to public health and safety or the environment (R649-3-36-1.3).


Please note that the Divisions preferred method for showing well integrity is by MIT.

Submitting the information suggested below may help show well integrity and may help qualify your well for extended SI/TA. **Note: As of July 1, 2003, wells in violation of the SI/TA rule R649-3-36 may be subject to full cost bonding (R649-3-1-4.2, 4.3).**

1. Wellbore diagram, and
2. Copy of recent casing pressure test, and
3. Current pressures on the wellbore (tubing pressure, casing pressure, and casing/casing annuli pressure) showing wellbore has integrity, and
4. Fluid level in the wellbore, and
5. An explanation of how the submitted information proves integrity.

**If the required information is not received by July 1, 2014, Notices of Violation will be issued and further actions may be initiated.** If you have any questions concerning this matter, please contact me at (801) 538-5281.

Sincerely,



Dustin K. Doucet  
Petroleum Engineer

DKD/JP/js

cc: Compliance File  
Well File  
LaVonne Garrison, SITLA

N:\O&G Reviewed Docs\ChronFile\PetroleumEngineer\SITA

## ATTACHMENT A

	Well Name	API	LEASE	Years Inactive	Prior Notices
1	CHIMNEY ROCK 32-11	43-047-33445	ML-47437	6 years 8 months	NOV
2	FLAT ROCK 13-32-14-20	43-047-36992	ML-44317	12 years 6 months	2 <sup>ND</sup> NOTICE
3	FLAT ROCK 14-32-14-20	43-047-36993	ML-44317	12 years 5 months	2 <sup>ND</sup> NOTICE
4	FLAT ROCK 15-32-14-20	43-047-36994	ML-44317	12 years 5 months	2 <sup>ND</sup> NOTICE
5	STATE 16H-32-15-12	43-007-31482	ML-49797	4 years 5 months	1 <sup>ST</sup> NOTICE
6	CARBON CANAL 5-12	43-015-30709	ML-49116	6 years	2 <sup>ND</sup> NOTICE
7	UTE TRIBAL 32-1A	43-047-32758	ML-44317	4 years 2 months	2 <sup>ND</sup> NOTICE
8	UTE TRIBAL 32-3A	43-047-33334	ML-44317	3 years 1 month	
9	UTE TRIBAL 32-4A	43-047-33335	ML-44317	3 years	
→ 10	TULLY 16-9-36D	43-015-50003	ML-52222	1 year 1 month	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-52222
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> WHITING OIL & GAS CORPORATION		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		<b>8. WELL NAME and NUMBER:</b> Tully 16-9-36D
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0860 FNL 0856 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		<b>9. API NUMBER:</b> 43015500030000
<b>PHONE NUMBER:</b> 303 390-4095 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WILDCAT
<b>COUNTY:</b> EMERY		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/21/2013	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	<input checked="" type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> APD EXTENSION	
	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Well temporarily abandoned. CIBP set @ 6703.5' with 2 sxs of cement dumped on top of the plug.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> July 08, 2014		
<b>NAME (PLEASE PRINT)</b> Cara Mezydlo	<b>PHONE NUMBER</b> 303 876-7091	<b>TITLE</b> Engineering Technician
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/1/2014	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-52222
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: Tully 16-9-36D	
2. NAME OF OPERATOR: WHITING OIL & GAS CORPORATION		9. API NUMBER: 43015500030000
3. ADDRESS OF OPERATOR: 1700 Broadway, Suite 2300, Denver, CO, 80290 2300	PHONE NUMBER: 303 390-4095 Ext	9. FIELD and POOL or WILDCAT: WILDCAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0860 FNL 0856 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		COUNTY: EMERY
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <b>9/1/2014</b>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input checked="" type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Please see the attached Plug and Abandonment proposal.

**Approved by the**  
**Utah Division of**  
**Oil, Gas and Mining**

Date: August 21, 2014

By: *Derek Dunt*

Please Review Attached Conditions of Approval

NAME (PLEASE PRINT) Cara Mezydlo	PHONE NUMBER 303 876-7091	TITLE Engineering Technician
SIGNATURE N/A		DATE 7/29/2014





**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

**Sundry Conditions of Approval Well Number 43015500030000**

- 1. Notify the Division at least 24 hours prior to conducting abandonment operations. Please call Dan Jarvis at 801-538-5338.**
- 2. Add Plug #1: A minimum of 100' ( $\pm 20$  sx) shall be spotted on the CIBP @ 6703'.**
- 3. Add Plug #2: A 200' plug ( $\pm 40$  sx) shall be balanced from  $\pm 5500'$  to 5300'. This will isolate the base of the Navajo Formation.**
- 4. Amend Plug #3: This plug shall be moved uphole 300' and balanced from 3800' to 3700'.**
- 5. All balanced plugs shall be tagged to ensure that they are at the depth specified.**
- 6. All annuli shall be cemented from a minimum depth of 100' to the surface.**
- 7. Surface reclamation shall be done in accordance with R649-3-34 – Well Site Restoration.**
- 8. All requirements in the Oil and Gas Conservation General Rule R649-3-24 shall apply.**
- 9. If there are any changes to the procedure or the wellbore configuration, notify Dustin Doucet at 801-538-5281 (ofc) or 801-733-0983 (home) prior to continuing with the procedure.**
- 10. All other requirements for notice and reporting in the Oil and Gas Conservation General Rules shall apply.**

8/6/2014

## Wellbore Diagram

r263

API Well No: 43-015-50003-00-00

Permit No:

Well Name/No: Tully 16-9-36D

Company Name: WHITING OIL &amp; GAS CORPORATION

Location: Sec: 36 T: 16S R: 9E Spot: NWNW

Coordinates: X: 511339 Y: 4360531

Field Name: WILDCAT

County Name: EMERY

## String Information

String	Bottom (ft sub)	Diameter (inches)	Weight (lb/ft)	Length (ft)
HOL1	97	26		
COND	97	20	94	97
HOL2	2081	17.5		
SURF	2081	13.375	54.5	2081
HOL3	6297	12.25		
II	6297	9.625	47	6297
HOL4	7460	8.5		
PROD	7460	7	29	7460 (0.2085) 4.794
CIBP	6703			

Plug # 5

$$(20 \times 1.15 \times 4.794) = 110'$$

TOC @ SFC  
V.O.K.

## Cement Information

String	BOC (ft sub)	TOC (ft sub)	Class	Sacks
CIBP	6703		UK	2
COND	94	0		
II	6297	0	UK	1470
PROD	7460	0	UK	665
SURF	2081	0	PL	1510

## Perforation Information

Top (ft sub)	Bottom (ft sub)	Shts/Ft	No Shts	Dt Squeeze
6714	6729	*MOVE Plug # 3 (3800' to 3700')		
6772	6784	(20 x 1.15 x 4.794) = 110'		
7180	7194	TOC @ 3700'		
		V.O.K.		

## Formation Information

Formation	Depth
DKTA	1891
MRSN	2647
SUMM	3270
CRTS	3534
ENRD	3714
CARM	4291
NAVA	4925
KAYT	5350
WINGT	5476
CHIN	5841
MNKP	6156

\*Add Plug # 2

$$(40 \times 1.15 \times 4.794) = 220'$$


TOC @ 5300'

Spot across  
Base of NAVA 50  
5500 to  
5300'

\*Add Plug # 1A

TOP CIBP @ 6703 w/ 100' (± 20 x) Cement

Page 1



TD: 7480 TVD: 7480 PBTD: 6765

Tully No. 16-9-36D  
API No. 4301550003  
Section 36, T16S, R9E  
Emery County, Utah

Whiting Oil and Gas respectfully requests approval to plug and abandon the Tully No. 16-9-36D well. The well is currently shut-in.	
1.	Advise the Utah DOGM 48 hours before plugging operations commence.
2.	TIH with tubing. Displace the hole with clean heavy produced water or 9.0 ppg mud.
3.	Spot a 20 sack Class “G” balanced cement plug from approximately 4100’ to 4000’.
4.	Spot a 20 sack Class “G” balanced cement plug from approximately 2130’ to 2030’. (Base of surface casing)
5.	Spot a 20 sack Class “G” balanced cement plug from approximately 100’ to 0’. Note, the 7” – 9 5/8” annulus was cemented to surface with the 7” production casing.
6.	Cut and remove the casing head. Install a regulation dry hole marker.
7.	Clean and restore the location, weather permitting.





Lease Review All CR  
Well Name: TULLY 16-9-36D

API Number 43015500030000	WPC ID 1UT029802	Well Permit Number	Field Name Wildcat	County Emery	State UT
Well Configuration Type Vertical	Orig KB Elv (ft) 5,887.60	Ground Elevation (ft) 5,871.10	Casing Flange Elevation (ft)	Tubing Head Elevation (ft)	Total Depth (ftKB) 7,480.0
Original Spud Date 12/7/2012	Completion Date 3/5/2013	Asset Group Central Rockies Asset Group	Responsible Engineer Jared Huckabee	N/S Dist (ft) 860.0	N/S Ref FNL
				E/W Dist (ft) 856.0	E/W Ref FWL
Lot	Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36
			Section Suffix	Section Type	Township 16 S
					Range 9 E
					Meridian S

Vertical - Original Hole, 7/29/2014 11:00:04 AM						Other In Hole								
MD (ftKB)	TV D (ftKB)	n cl (°)	Vertical schematic (actual)		Logs	Des	OD (in)	ID (in)	Run Date	Pull Date	Top (ftKB)	Btm (ftKB)		
						2 mandels, Jars, sinker bar	6.184		2/6/2013	2/14/2013	6,543.0	6,726.9		
						Cast Iron Bridge Plug	6.184		3/5/2013		6,703.5	6,704.5		
						Cast Iron Bridge Plug	6.184		2/15/2013		6,765.0	6,766.0		
						Cast Iron Bridge Plug	6.184		1/24/2013		7,150.0	7,151.0		
Bottom Hole Cores														
Date		Core #		Top (ftKB)		Btm (ftKB)		Recov (ft)						
12/25/2013				6,670.0		6,850.0		180.0						
12/26/2013				6,850.0		7,030.0		180.0						
12/27/2013				7,030.0		7,210.0		180.0						
12/28/2013				7,210.0		7,308.0		98.0						
12/29/2013				7,308.0		7,359.0		51.0						
16.4	16.4	0.0												
25.6	25.6	0.1												
50.2	50.2	0.1												
96.5	96.5	0.3												
2,034.4	2,034.3	0.7												
2,035.4	2,035.3	0.7												
2,080.7	2,080.8	0.7												
2,081.0	2,080.9	0.7												
2,122.0	2,121.9	0.8												
3,293.6	3,293.4	0.7												
3,295.9	3,295.7	0.7												
6,193.9	6,193.2	1.6												
6,250.0	6,249.3	1.6												
6,251.3	6,250.6	1.6												
6,292.7	6,291.9	1.7												
6,294.3	6,293.5	1.7												
6,315.0	6,314.2	1.8												
6,703.4	6,702.6	1.4												
6,704.4	6,703.6	1.4												
6,713.9	6,713.1	1.4												
6,716.9	6,716.0	1.4												
6,722.1	6,721.3	1.4												
6,729.0	6,728.2	1.4												
6,765.1	6,764.3	1.5												
6,766.1	6,765.2	1.5												
6,772.0	6,771.1	1.5												
6,784.1	6,783.3	1.5												
7,149.9	7,148.9	2.2												
7,150.9	7,149.9	2.2												
7,180.1	7,179.1	2.2												
7,184.1	7,183.0	2.2												
7,190.0	7,188.9	2.2												
7,193.9	7,192.8	2.2												
7,418.0	7,416.7	2.3												
7,419.0	7,417.7	2.3												
7,459.0	7,457.7	2.3												
7,460.0	7,458.7	2.3												
7,480.0	7,478.7	2.3												

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-52222
<b>1. TYPE OF WELL</b>		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> WHITING OIL & GAS CORPORATION		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		<b>8. WELL NAME and NUMBER:</b> Tully 16-9-36D
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0860 FNL 0856 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		<b>9. API NUMBER:</b> 43015500030000
<b>PHONE NUMBER:</b> 303 390-4095 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WILDCAT
<b>COUNTY:</b> EMERY		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 12/16/2014	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input checked="" type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. P&A subject well as follows: 1. Pressure tested casing to 1000# for 15 min. 2. Tagged CIBP @ 6717'. 3. Rolled hole clean with corrosion inhibited fluid. 4. Balanced a 20 sk cement plug from 6717' to 6615'. Confirmed TOC with wireline. 5. Balanced a 40 sk cement plug from 5500' to 5270'. Confirmed TOC with wireline. 6. Balanced a 20 sk cement plug from 3800' to 3677'. Confirmed TOC with wireline. 7. Balanced a 20 sk cement plug from 2130' to 2029'. Confirmed TOC with wireline. 8. Balanced a 20 sk cement plug from 110' to surface. 9. Cut csg off 10' below ground level, welded on regulation dry hole marker, and backfilled. Note: Please see attached cementing reports for cement plug details.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> January 13, 2015		
<b>NAME (PLEASE PRINT)</b> Cara Mezydlo	<b>PHONE NUMBER</b> 303 876-7091	<b>TITLE</b> Engineering Technician
<b>SIGNATURE</b> N/A	<b>DATE</b> 1/9/2015	





## Job Summary

**Whiting Oil & Gas Corp**  
**1700 Broadway, Suite 2300**  
**Denver, CO 80290**  
**(303) 837-1661**

**Well Name: TULLY 16-9-36D**

**Plug & Abandon**  
**Job Started on 12/7/2014**

WPC ID 1UT029802	API Number 43015500030000	Field Name Wildcat	County Emery	State UT	Operator WOGC	Gr Elev (ft) 5,871.10	Orig KB El... 5,887.60
AFE Number 14-3782		Total AFE Amount (Cost) 99,500.00		Supp Amt (Cost) 99,500.00		Total AFE + Supp Amount (Cost) 15,231.00	
Job Category Plug & Abandon		Job Type Plug & Abandon		Working Interest (%) 100.00	Total Fid Est (Cost) 84,269.00	Start Date 12/7/2014	End Date

### Daily Operation Reports (6am to 6am)

Job Day (days)	Rpt #	Start Date	End Date	Summary
1.0	1.0	12/7/2014	12/8/2014	Moved in Red Rock Well Service rig #2 and support equipment from Flat Rock area. Spotted rig and equipment off the side of location have to install spill containment on location before well service rig can be rigged up. Will install containment and rig up equipment in the AM.
2.0	2.0	12/8/2014	12/9/2014	SICP = 10 psi. Notified Dan Jarvis with UDOGM by voicemail @ 7:35am of our intent to pump cement and P&A well on 12-10-14. Installed spill containment liners, RU Red Rock Well Service rig #2 and spotted in support equipment. Bled off well, removed master valve, and installed Weatherford 7-1/16" 5K BOPE. CSG standing full of fluid, pressure tested CSG to 1030 psi, held for 15 minutes, good test no leak off. Tallied and RIH with 2-7/8" notched collar and 195 JTS 2-7/8" 6.5# N-80 TBG, EOT @ 6342'. Secured wellhead and SDFN.
3.0	3.0	12/9/2014	12/10/2014	SICP = 0 psi. RIH with another 12 JTS 2-7/8" 6.5# N-80 TBG, tagged BP @ 6717', laid down 1 JT TBG and spaced out with pup JTS. EOT @ 6715'. Added 55 GAL WSCR-202 Corrosion Inhibitor and 15 GAL Dantogard 2000 Biocide to 390 BBL fresh water and mixed with rig pump. Displaced wellbore fluid with 240 BBL treated water. Laid down pup JTS and POOH with 10 JTS 2-7/8" 6.5# N-80 TBG EOT @ 6372'. Secured wellhead and SDFN. Pro-Petro Cementers will arrive in the AM.
4.0	4.0	12/10/2014	12/11/2014	SICP = 0 psi. RIH with 10 JTS 2-7/8" 6.5# N-80 TBG, picked up 18' of pup JTS, EOT @ 6716'. RU Pro-Petro Cementers pumped 5 BBL fresh water, 4.1 BBL 20 sks neat G CMT (15.8# 1.15 yield 2% CaCl2 accelerator added), 1 BBL fresh water, 37.2 BBL treated water. Laid down 5 jts TBG, EOT @ 6537', reversed out with 58 BBL treated water. POOH with another 32 JTS TBG, picked up 4' pup JT (EOT @ 5500') waited 2 1/2 hours. RIH with wireline tagged cement top @ 6615'. POOH pumped 5 BBL fresh water, 8.2BBL 40 sks neat G CMT (15.8# 1.15 yield 2% CaCl2 accelerator added), 1 BBL fresh water, 29.4 BBL treated water. Laid down 12 JTS TBG (EOT @ 5104'), reversed out with 47.7 BBL treated water. POOH with another 40 JTS of TBG, picked up 4' pup JT (EOT @ 3800'). Waited 2 1/2 hours, RIH with wireline, tagged cement top @ 5270', POOH. Pumped 5 BBL fresh water, 4.1 BBL 20 sks neat G CMT (15.8# 1.15 yield 2% CaCl2 accelerator added), 1 BBL fresh water, 20.3 BBL treated water. Laid down 6 JTS TBG (EOT @ 3614'), reversed out with 33 BBL treated water. POOH with another 30 JTS TBG (EOT @ 2803'). Secured wellhead and SDFN.
5.0	5.0	12/11/2014	12/12/2014	SICP = 0 psi. POOH with 22 JTS of TBG, picked up 8' pup JT (EOT @ 2130'). RIH with wireline, tagged cement top @ 3677', POOH. Pumped 5 BBL fresh water, 4.1 BBL 20 sks neat G CMT 15.8# 1.15 yield 2% CaCl2 accelerator added, 1 BBL fresh water, 10.6 BBL treated water. Laid down 6 JTS TBG EOT @ 1932' reversed out with 17.5 BBL treated water. POOH with another 56 JTS of TBG, picked up 18' pup JT EOT @ 110'. Waited 2 1/2 hours, RIH with wireline tagged cement top @ 2029'. POOH, rigged down and released wireline. Pumped 1 BBL fresh water, 4.1 BBL 20 sks neat G CMT 15.8# 1.15 yield w/ 2% CaCl2 accelerator added. Cement returns to surface. POOH with 3 JTS TBG, removed and washed out BOPE. Installed B1 adapter flange and master valve, shut in and secured wellhead. Rigged down and released cement crew, racked out 2-7/8" work string on side of location and rigged down service unit. Moved rig and support equipment to Nielsons Construction yard. There were no UDOGM inspectors present during P&A operations.
9.0	6.0	12/15/2014	12/16/2014	SICP = 0 psi. Cleaned and removed spill containment liners. Removed cellar ring and excavated hole for welders to work, cut thru 13-3/8" CSG, 9 5/8" CSG, 7" CSG 10' below GL and removed wellhead assembly. Found good cement to surface on CSG annulus, attached regulation dry hole marker and welded out. Should have 5' of dry hole marker above GL after reclamation. SDFN.
10.0	7.0	12/16/2014	12/17/2014	SICP = 0 psi. Back filled dry hole marker, dug out then removed guy wire anchors and back filled holes. Loaded out wellhead onto hotshot trailer, hauled off trash basket, pit liners and wellhead fencing. Location ready for reclamation.

API Number 43015500030000			WPC ID 1UT029802			Well Permit Number			Field Name Wildcat			County Emery			State UT	
Well Configuration Type Vertical				Orig KB Elv (ft) 5,887.60		Ground Elevation (ft) 5,871.10		Casing Flange Elevation (ft)		Tubing Head Elevation (ft)		Total Depth (ftKB) 7,480.0				
Original Spud Date 12/7/2012		Completion Date 3/5/2013		Asset Group Central Rockies			Responsible Engineer Jared Huckabee			N/S Dist (ft) 860.0		N/S Ref FNL		E/W Dist (ft) 856.0		E/W Ref FWL
Lot		Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36	Section Suffix	Section Type	Township 16 S	Township N/S Dir	Range	Range E/W Dir 9 E	Meridian S			

Page 1/2



API Number 43015500030000			WPC ID 1UT029802			Well Permit Number			Field Name Wildcat			County Emery			State UT		
Well Configuration Type Vertical					Orig KB Elv (ft) 5,887.60		Ground Elevation (ft) 5,871.10		Casing Flange Elevation (ft)		Tubing Head Elevation (ft)		Total Depth (ftKB) 7,480.0				
Original Spud Date 12/7/2012			Completion Date 3/5/2013		Asset Group Central Rockies			Responsible Engineer Jared Huckabee			N/S Dist (ft) 860.0		N/S Ref FNL		E/W Dist (ft) 856.0		E/W Ref FWL
Lot	Quarter 1 NW	Quarter 2 NW	Quarter 3	Quarter 4	Section 36	Section Suffix	Section Type	Township 16 S	Township N/S Dir	Range	Range E/W Dir 9 E	Meridian S					

Vertical - Original Hole, 1/8/2015 4:13:24 PM		Other Strings			
MD (ftKB)	Vertical schematic (actual)	Set Depth (ftKB)	Comment	Run Date	Pull Date

		Item Des	OD (in)	ID (in)	Len (ft)	Top (ftKB)	Btm (ftKB)
16.4	4-2: Landing Joint: 7: 6 184:						

Depth (ft)	Casing Joints
16.5; 9.05	4-3; Casing Joints; 7; 6.184;
25.6; 24.67	1-1; Casing Joints; 20;
19.124; 16.5; 80.00	

109.9	<p>2-1; Casing Joints; 13 3/8; 12,615; 16.5; 2,018.00</p> <p>3-1; Casing Joints; 9 5/8; 8,681; 16.5; 3,277.02</p>	<b>Bottom Hole Cores</b>				
2,028.9		Date	Core #	Top (ftKB)	Btm (ftKB)	Recov (ft)
		12/25/2013	1	6,670.0	6,850.0	180.0
2,034.4		12/26/2013	2	6,850.0	7,030.0	180.0
		12/27/2013	3	7,030.0	7,210.0	180.0
2,035.4	2-2; Float Collar; 13 3/8; 12,615; 2,034.5; 1.00	12/28/2013	4	7,210.0	7,308.0	98.0
	2-3; Casing Joints; 13 3/8; 12,615; 2,035.5; 45.20	12/29/2013	5	7,308.0	7,359.0	51.0

2.080.7  
2.081.0

12.615; 2,080.7; 43.20  
2-4; Shoe; 13 3/8; 12.615;  
2,080.7; 0.50

2,129.9

3,293.6

3.3: DV Tech 9.5/9: 3.303.5

3.295.9 ..... 3-2; DV 1001, 9 5/8, 3,293.3, 2.50

3,676.8  
3,799.9

4-5; Casing Joints; 7; 6.184;  
50.2; 7,367.76

5,270.0

3-3; Casing Joints; 9 5/8;  
8.681; 3,296.0; 2,953.90

The diagram shows a cross-section of a building facade. A central window is depicted with a yellow interior and a dark frame. Above the window, there is a grey textured area representing a roof or overhang. A blue wavy line, resembling a sine wave, runs horizontally across the top of the facade, above the window and the textured area. The line oscillates between two horizontal levels. On the left side of the diagram, there are two numerical labels: '5,500.0' at the top and '6,193.9' below it, corresponding to the two levels of the wavy line.

6.250.0

3-4; Float Collar; 9 5/8;  
6.249.9; 1.50

6,251.3  
3-5; Casing Joints: 9 5/8;  
8.681; 6,251.4; 41.28  
6,292.7  
3-6; Guide Shoe: 9 5/8;

6,294.3	6,292.7; 1.50
---------	---------------



The diagram illustrates a cross-section of a building's exterior wall and roof assembly. The wall assembly on the left consists of an exterior cladding, a structural layer, and an interior finish. The roof assembly on the right consists of a structural layer, an insulation layer, and a waterproofing layer. The diagram is labeled with dimensions and material types.

Layer	Material	Thickness (mm)
Exterior Cladding	Concrete	150
Structural Layer	Concrete	150
Interior Finish	Gypsum Board	12.5
Structural Layer	Concrete	150
Insulation Layer	Polystyrene	100
Waterproofing Layer	Bitumen	2

6.713.9

Perforated; 6.714.0-6.717.0;  
2/15/2013

6,716.9

6,717.8

Cast Iron Bridge Plug; 6.18; 6,717.0-6,718.0

6.722.1

Perforated; 6,722.0-6,729.0;  
2/15/2013

Cast Iron Bridge Plug; 6.18;

6,765.1

6,765.0-6,766.0

6,766.0

DFIT: 6,772.0-6,784.0;  
1/24/2013

7,149.9

7,150.0

Cast Iron Bridge Plug; 6.18;  
7,150.0-7,151.0

1/17/2013

Perforated; 7,190.0-7,194.0;  
1/17/2013

4-6; Float Collar; 7; 6.184;  
7,418.0; 1.00

7.420.9 4-7; Casing Joints; 7; 6.184;

7,459.0 7,419.0; 40.02  
4-8; Float Shoe; 7; 6.184;  
7,459.0; 1.00

7,480.0	
---------	--

**PROPETRO**P.O. Box 827 • Vernal, UT 84078  
Phone: (435) 789-1735

8878

**JOB SUMMARY REPORT**

<b>Customer</b> Whiting Oil & Gas Company			<b>Date</b> 12-10-2014		<b>Ticket Number</b>
<b>Lease &amp; Well Name</b> Tully 16-9-36D		<b>Sec.</b>	<b>Twp.</b>	<b>Range</b>	<b>County</b> Carbon
<b>Job Type</b> Plug & Abandon			<b>Drilling Contractor</b> Red Rock #2		
<b>Surface CSG Size</b>	<b>Wt./Grade</b>	<b>Thread</b>	<b>Depth From</b>	<b>To</b>	
<b>Inter CSG Size</b>	<b>Wt./Grade</b>	<b>Thread</b>	<b>Depth From</b>	<b>To</b>	
<b>Prod. CSG Size</b> 7"	<b>Wt./Grade</b> 29 #	<b>Thread</b> 8 Rd	<b>Depth From</b> 0	<b>To</b> 6716'	
<b>Liner CSG Size</b>	<b>Wt./Grade</b>	<b>Thread</b>	<b>Depth From</b>	<b>To</b>	
<b>TBG or D.P. Size</b> 2 7/8	<b>Wt./Grade</b> 6.5 #	<b>Thread</b> 8 Rd	<b>Depth From</b> 0	<b>To</b> 6716'	
<b>SKS</b>	<b>Materials Furnished</b>		<b>Slurry Wt. P.P.G.</b>	<b>Slurry Yield FT³</b>	<b>Water Gal./Sk.</b>
12-10-14 80	100% Neat 6 CMT, 2% CaCl <sub>2</sub>		15.8	1.15	5
12-11-14 40	100% Neat 6 CMT, 2% CaCl <sub>2</sub>		15.8	1.15	5
<b>Float Equipment</b> N/A					

**Equipment & Personnel**

Paul 1172, Peter 10, Jarom 65/68

**Notes**

1st Plug set @ 6606' - 6716' (E.O.T. 6716')	} 12-10-14
2nd Plug set @ 5780' - 5500' (E.O.T. 5500')	
3rd Plug set @ 3690' - 3900' (E.O.T. 3900')	
4th Plug set @ 2020' - 2130' (E.O.T. 2130')	
5th Plug set @ 0 - 110' (E.O.T. 110')	} 12-11-14



**PROPETRO**P.O. Box 827 • Vernal, UT 84078  
Phone: (435) 789-1735

8645

Date 12-10, 2014For Whiting Oil and Gas CompanyLease Tully 16-9-36DRig No. Red Rock #2**JOB LOG**

TIME	DESCRIPTION	RATE	PSI	VOLUME
07:15	On location - Rig Up - Safety Mtg			
	Pressure Test Pump & Lines			
09:12	Start H <sub>2</sub> O - 1st Plug - (E.O.T. 6716')	2	175	0
	END			5
9:17	Start Neat G CMT @ 2% CaCl <sub>2</sub> 20 SKs	3	400	0
	END			4.1
9:18	Start H <sub>2</sub> O	3	375	0
	END			1
9:19	Start Treated Water	5	550	0
	END - (Balanced Plug from 6606' to 6716')			37.2
9:47	Reverse	5	800	0
	END			58.3
	2nd Plug - (E.O.T. 5500')			
12:50	Start H <sub>2</sub> O	4	400	0
	END			5
12:55	Start Neat G CMT @ 2% CaCl <sub>2</sub> 40 SKs	4	475	0
	END			8.2
12:57	Start H <sub>2</sub> O	4	220	0
	END			1
12:58	Start Treated Water	5	450	0
	END - (Balanced Plug from 5280' to 5500')			29.4
13:35	Start Reverse	5	700	0
	END			47.7
	3rd Plug - (E.O.T. 3800')			
16:20	Start H <sub>2</sub> O	4	400	0
	END			5
16:25	Start Neat G CMT @ 2% CaCl <sub>2</sub> 20 SKs	3	300	0
	END			4.1
16:27	Start H <sub>2</sub> O	3	250	0
	END			1

Operator Paul

Accepted and approved by \_\_\_\_\_



# PROPETRO

P.O. Box 827 • Vernal, UT 84078  
Phone: (435) 789-1735

8646

Date 12-10, 20 14

For Whiting Oil & Gas Company

Lease Tully 16-9-36b

Rig No. Red Rock #2

## JOB LOG

[illegible]

Operator Paul

**Accepted and approved by**



**Accepted and approved by**

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-52222			
<b>1. TYPE OF WELL</b>		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>			
<b>2. NAME OF OPERATOR:</b> WHITING OIL & GAS CORPORATION		<b>7. UNIT or CA AGREEMENT NAME:</b>			
<b>3. ADDRESS OF OPERATOR:</b> 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		<b>8. WELL NAME and NUMBER:</b> Tully 16-9-36D			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0860 FNL 0856 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		<b>9. API NUMBER:</b> 43015500030000			
<b>PHONE NUMBER:</b> 303 390-4095 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WILDCAT			
<b>COUNTY:</b> EMERY		<b>STATE:</b> UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>				
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>4/30/2015</b>  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  Per landowner request, the Tully 16-9-36D will be reclaimed in the Spring 2015, in the following manner: 1. Cattle guard and gates will remain in place 2. The gravel road to the well site will stay as is, and culverts left in place. 3. The well site will be returned to the natural slope, with natural top soil. 4. No rock will be hauled in. 5. Well site and sides of road that have been damaged will be reseeded with Russian Wildrye and Forage Kochia. Please see attached landowner request. The operations supervisor on this well is Scott Swain, reachable at (435) 781-1804 office, (435) 299-0414 cell, or scott.swain@whiting.com.					
<b>NAME (PLEASE PRINT)</b> Cara Mezydlo		<b>PHONE NUMBER</b> 303 876-7091			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Engineering Technician			
<b>DATE</b> 1/9/2015		<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b>  <b>Date:</b> <u>January 30, 2015</u> <b>By:</b> <u><i>Scott Swain</i></u>			



To whom it may concern the original lease between Whitening Oil Company and pervious land owners Mark and Angie Austin was put in place May of 2012. In July of 2014 Robert and Josie Ramstetter purchased the land.

Poison Springs #16-9-36D, Lands NW/4NW/4, Section 36, Township 16 South, Range 9 East, Emery County, Utah.

For reclaiming the oil well site owners would like as followed:

Cattle guard and gates stay the same.

Gravel road going to well sight stays as is and culverts left in place.

The well site returned to the natural slope with natural top soil.

No rocks hauled in for (natural placement).


Receding well site and sides of road that have been damaged.

Seed Type: Russian Wild Rye and Forage Koshia.



12-22-2014

Robert Ramstetter



12-22-2014

Josie Ramstetter

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-52222
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
1. TYPE OF WELL		7. UNIT or CA AGREEMENT NAME:
2. NAME OF OPERATOR: WHITING OIL & GAS CORPORATION		8. WELL NAME and NUMBER: Tully 16-9-36D
3. ADDRESS OF OPERATOR: 1700 Broadway, Suite 2300, Denver, CO, 80290 2300	PHONE NUMBER: 303 390-4095 Ext	9. API NUMBER: 43015500030000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0860 FNL 0856 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		9. FIELD and POOL or WILDCAT: WILDCAT
		COUNTY: EMERY
		STATE: UTAH

11.


CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION	OTHER: <input type="text" value="Pit Closure"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/25/2014				
<input type="checkbox"/> SPUD REPORT Date of Spud:				
<input type="checkbox"/> DRILLING REPORT Report Date:				

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Whiting Oil and Gas Corporation has closed the pit on this location and received approval from Mark Jones on 8/25/14. Attached are photos showing the pit closure and soil testing.

**Accepted by the  
Utah Division of  
Oil, Gas and Mining**

Date: ~~November 02, 2015~~By: 


NAME (PLEASE PRINT) Cara Mezydlo	PHONE NUMBER 303 876-7091	TITLE Engineering Technician
SIGNATURE N/A		DATE 6/17/2015








Pit










Pit liner exposed






Stuck piling mud -  
as per state request





Sundry Number: 63971 API Well Number: 43015500030000

Pit after cleaned out





Sundry Number: 63971 API Well Number: 43015500030000

Pit after cleaned out





Sundry Number: 63971 API Well Number: 43015500030000  
Pit liner removed





Sundry Number: 63971 API Well Number: 43015500030000


Location reclaim





Sundry Number: 63971 API Well Number: 43015500030000

Location reclaim





Sundry Number: 63971 ARI Well Number: 43015500030000


Location unclear





Sundry Number: 63971 API Well Number: 43015500030000

Location reclaim





Sundry Number: 63971 API Well Number: 43015500030000

Location reclaim





Sundry Number: 63971 API Well Number: 43015500030000

Pit





Sundry Number: 63971 API Well Number: 43015500030000

PIT





>  
> On Jul 7, 2014, at 9:47 AM, "Heather Otterstetter" <hotterstetter@ltenv.com<mailto:hotterstetter@ltenv.com>>  
wrote:  
>  
> Scott,  
> See the attached guidance from the state that Sam sent over. FYI-the SAR, ESP, and conductivity results are at the back  
of the lab report since it was sub'd out. Looks like the SAR, ESP, and EC results are over the limit. Would you like me to  
put together a table?  
>  
> Heather Otterstetter, P.E.  
> Project Engineer/Group Manager  
> 303-962-5516 (direct)  
>  
> From: Sam LaRue [mailto:slarue@ltenv.com]  
> Sent: Tuesday, July 01, 2014 3:33 PM  
> To: Heather Otterstetter  
> Subject: RE: Pace Project 60172423, Wellington Drill Pit Sampling  
>  
> Are we still waiting on the SAR, ESP and conductivity reports then? Surprising that the non pit samples had TPH. Based  
on the UDOGM recommended abandonment levels none of the samples exceed UDOGM Total TPH levels of 1% or  
10,000ppm. Attached is the regulatory page from the UDOGM environmental handbook.  
>  
> Sam LaRue  
> Staff Environmental Scientist  
> (435) 630-4748 cell  
>  
> From: Heather Otterstetter [mailto:hotterstetter@ltenv.com]  
> Sent: Tuesday, July 01, 2014 3:14 PM  
> To: Heather Wilson  
> Cc: slarue@ltenv.com<mailto:slarue@ltenv.com>  
> Subject: RE: Pace Project 60172423, Wellington Drill Pit Sampling  
>  
> Thanks.  
>  
> \_\_\_\_\_  
> From: Heather Wilson  
> [Heather.Wilson@pacelabs.com<mailto:Heather.Wilson@pacelabs.com>]  
> Sent: Tuesday, July 01, 2014 3:09 PM  
> To: Heather Otterstetter  
> Cc: slarue@ltenv.com<mailto:slarue@ltenv.com>  
> Subject: Pace Project 60172423, Wellington Drill Pit Sampling Hi  
> Heather-  
>  
> Good afternoon! Enclosed is the final report for the samples received at the lab on June 26th. I apologize that we are  
not able to meet the requested turn you had originally asked for. The invoice for this project will follow later as I'm in  
the process of making sure that the sub lab doesn't apply rush charges when they didn't meet the turn and I confirm the  
pricing. If you have any questions about the results, please let me know. Have a wonderful day!  
>  
> Heather  
>  
>

TABLE 1  
COMPOSITE SOIL SAMPLING RESULTS  
TULLY 16-9-36D  
WHITING PETROLEUM CORPORATION  
WELLINGTON, UTAH

SAMPLE ID	DATE	TPH-DRO (mg/kg)	TPH-GRO (mg/kg)	TPH-ORO (mg/kg)	TPH (mg/kg)	SAR	ESP	CONDUCTIVITY (mmhos/cm)
EAST PIT COMPOSITE	6/24/2014	228	<24.3	216	444	54.9	44.4%	137
EXCAVATED COMPOSITE	6/24/2014	69.0	<10.8	30.2	99.2	48.1	41.1%	17.5
PRE-STORAGE COMPOSITE	6/24/2014	19.6	<10.8	26.9	46.5	58.5	46.0%	24.9
WEST PIT COMPOSITE	6/24/2014	197	<27.8	126	323	244	78.2%	>250
UDOGM Cleanup Levels					10,000	12	15%	4

**Notes:**

&lt; = analytical results is less than the reporting limit (non-detect)

% = percent

**Bold** = Analytical results exceeded the UDOGM cleanup level

ESP = exchangeable sodium percentage

mg/kg = milligrams per kilogram

mmhos/cm = millimhos per centimeter

SAR = soil adsorption ratio

TPH-DRO = total petroleum hydrocarbons diesel range organics

TPH-GRO = total petroleum hydrocarbons gasoline range organics

TPH-ORO = total petroleum hydrocarbons oil range organics

UDOGM = Utah Division of Oil, Gas, and Mining

EDGE OF SITE FROM STEEL STOCK  
ED FOR PROD. PIT. SOIL COLLECTED  
~~IN~~ 0-0.5' & PLACED IN ZIPLOC  
BAG. CONTENTS MIXED &  
3x40Z GLASS JARS. JARS PLACED  
ON ICE.

COMPOSITE: 3 POINT COMPOSITE  
J EASTERN EDGE OF SITE WHERE  
CONTENTS WILL BE STORED. SOIL  
BETWEEN 0-0.5' & PLACED IN  
ZIPLOC BAG. CONTENTS MIXED &  
3x40Z GLASS JARS. JARS PLACED  
ON ICE.


IN WESTERN QUADRANT. SOIL COLLECTED  
AT A DEPTH OF APPROXIMATELY 0.5-1'  
IN ZIPLOC BAG. CONTENTS MIXED  
PLACED IN 3x40Z GLASS JARS. JARS  
PLACED IMMEDIATELY ON ICE.

1325 OFFSITE

*[Signature]*  
6/24/18

	<u>SAMPLE TIME</u>
SITE	1110
OSITE	1126
MROSITE	1141
COMPOSITE	1250

DO CONSTR. CONTACT LEAVE SITE  
SURE TRACK-HOE OR PLANKS  
WEST END OF PROD. PIT. UNABLE  
SAMPLE DUE TO SOFTNESS OF SOIL  
> OF PIT. COLLECT OTHER SAMPLES  
JRN





## Scott Swain

---

**From:** Mark Jones <markjones@utah.gov>  
**Sent:** Thursday, July 31, 2014 12:55 AM  
**To:** Scott Swain  
**Subject:** Tully reserve pit closure

Scott,

I've reviewed the sample results of the drill cuttings as well as the background samples that we have taken. The cutting samples are beyond our threshold limits as shown in the lab results. However they are not as far off as one might conclude based on some of the data. I've sought the council of a coworker that has more experience and is well educated on pit closures and particularly well educated on salt based contaminants. He too has been looking at the data with me as you have provided it to me. We feel like the environmental risk associated with the Tully location is very low. Both at the surface as well in the subsurface and deeper in the formation. The risks are small, both short term and long term, of these drill cuttings ever creating an environmental threat to anyone or anything. The salts of these cuttings if buried on site will leach very slowly and the will not migrate very far over a very long period of time. The threat of these salts being pulled back to the surface is small due to the local environment being a low precipitation and high evapo-transpiration site. This coupled with the soil characteristics of the Mancos clay being very "tight" doesn't allow moisture to penetrate very deeply. Water making it's way from the surface to the salts of the cuttings and then returning back to the surface thus pulling the salts to the surface is extremely low. The reality of the situation is that dealing with these salt loaded cuttings in this situation and environmental parameters will in fact be more effect than disposal at a waste facility where we then compound our waste problems and ultimate clean ups and environmental hazards by increased volumes and concentrating the pollutant. Concentrated amounts of wastes are always more dangerous to the enviroment that if the waste were kept small, contained, and dealt with on a case by case situation. Not all wastes can be looked at this way and not all situations will allow for a safe on site disposal. However, I feel that this site and case is perfect for on site disposal of these salt based cuttings.

The cuttings may be replaced into the reserve pit on this location under the following guidelines:

- 1) back fill the pit with the cuttings in layers nor more than 2 feet think.
- 2) compact each layer with the dozer or other suitable mechanical means.
- 3) the final 2 foot layer should be native pit spoils material and again compacted in place mechanically.
- 4) if there are any drill cuttings that do not fit back in this pit, consult with Mark Jones of UDOGM for options for remaining cuttings.



5) Re-test the soil of the well pad surface in several locations of the entire area that was used to stock pile and dry the drill cuttings. To assure that all of the high salt material has been disposed of and not left on the location surface. These samples should be surface samples only. The cuttings have not had even close to enough time to leach any deeper into the surface soils.

6) remove from the site and dispose of at the landfill, all of the synthetic pit liner and any other trash type waste.

7) Notify Mark Jones when back filling has begun and upon completion to allow for spot inspection of the process and progress.

Thank you,  
Mark Jones

--

Mark L. Jones  
Division of Oil, Gas and Mining  
office: 435-613-3735  
cell: 435-820-8504

Sundry Number: 63971 API Well Number: 43015500030000  
Sundry Number: 59749 API Well Number: 43015500030000

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b> Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-52222
1. TYPE OF WELL		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: WHITING OIL & GAS CORPORATION		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		8. WELL NAME and NUMBER: Tully 16-9-36D
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0860 FNL 0856 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		9. API NUMBER: 43015500030000
		9. FIELD and POOL or WILDCAT: WILDCAT
		COUNTY: EMERY
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/30/2015	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input checked="" type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER: <input type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
<p>Per landowner request, the Tully 16-9-36D will be reclaimed in the Spring 2015, in the following manner: 1. Cattle guard and gates will remain in place 2. The gravel road to the well site will stay as is, and culverts left in place. 3. The well site will be returned to the natural slope, with natural top soil. 4. No rock will be hauled in. 5. Well site and sides of road that have been damaged will be reseeded with Russian Wildrye and Forage Kochia. Please see attached landowner request. The operations supervisor on this well is Scott Swain, reachable at (435) 781-1804 office, (435) 299-0414 cell, or scott.swain@whiting.com.</p>		
<div>Accepted by the Utah Division of Oil, Gas and Mining</div> <div>Date: <u>January 30, 2015</u> By: <u>[Signature]</u></div>		
NAME (PLEASE PRINT) Cara Mezydlo		PHONE NUMBER 303 876-7091
SIGNATURE N/A		TITLE Engineering Technician
		DATE 1/9/2015

RECEIVED: Jan. 09, 2015

Sundry Number: 63971 API Well Number: 43015500030000

Sundry Number: 59749 API Well Number: 43015500030000

To whom it may concern the original lease between Whitening Oil Company and pervious land owners Mark and Angie Austin was put in place May of 2012. In July of 2014 Robert and Josie Ramstetter purchased the land.

Poison Springs #16-9-36D, Lands NW/4NW/4, Section 36, Township 16 South, Range 9 East, Emery County, Utah.

For reclaiming the oil well site owners would like as followed:

Cattle guard and gates stay the same.


Gravel road going to well sight stays as is and culverts left in place.

The well site returned to the natural slope with natural top soil.

No rocks hauled in for (natural placement).


Receding well site and sides of road that have been damaged.

Seed Type: Russian Wild Rye and Forage Koshia.



12-22-2014

Robert Ramstetter



12-22-2014

Josie Ramstetter



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-52222
<b>1. TYPE OF WELL</b>		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> WHITING OIL & GAS CORPORATION		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1700 Broadway, Suite 2300, Denver, CO, 80290 2300		<b>8. WELL NAME and NUMBER:</b> Tully 16-9-36D
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0860 FNL 0856 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWNW Section: 36 Township: 16.0S Range: 09.0E Meridian: S		<b>9. API NUMBER:</b> 43015500030000
<b>PHONE NUMBER:</b> 303 390-4095 Ext		<b>9. FIELD and POOL or WILDCAT:</b> WILDCAT
<b>COUNTY:</b> EMERY		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/29/2015	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input checked="" type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  Whiting Oil and Gas Corporation respectfully submits the completed reclamation agreement on the Tully 16-9-36D well. Based on the signed agreement, the land owner is satisfied with the reclamation performed, and there is no further action to be done.		
<b>NAME (PLEASE PRINT)</b> Cara Mezydlo		<b>PHONE NUMBER</b> 303 876-7091
<b>SIGNATURE</b> N/A		<b>TITLE</b> Engineering Technician
<b>DATE</b> 1/29/2016		<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> April 05, 2016



September 3, 2015


Robert Ramstetter  
(Include address)

**RE: Poison Springs #16-9-36D Reclamation Agreement between Whiting Oil and Gas Corporation and the Owners of the following property.**

**Township 16 South – Range 9 East**  
**Section 36: NW ¼ NW ¼**


The following agreement has been entered into by Whiting Oil and Gas Corporation (Operator) and Robert Ramstetter (Owner) as a settlement for reclamation of the Poison Springs #16-9-36D Well Site. Owner requested in a letter dated December 22, 2014 to the Operator that the cattle guards, gates, gravel road, and culverts remain in place and not be reclaimed. Owner requested that the well site be reclaimed back to its original natural slope or as reasonably possible with the natural topsoil and that no rocks are to be hauled in for placement. Owner also requested that all disturbed areas be reseeded with Russian Wild Rye and Forage Koshia. The execution of this document serves as evidence that the Operator has met the above terms as requested by the Owner and that no further action is necessary.

Owners of said property are:

  
Robert Ramstetter

This agreement was signed on the 29<sup>th</sup> day of Sept. 2015.

If you have any questions or comments, please feel free to give me a call at the following number:  
Office # 435-781-1804  
Cell # 435-299-0414

  
Scott Swain  
Operations Supervisor  
Operations- Denver  
scott.swain@whiting.com

**Scamp Excavation, Inc**  
**PO Box 50, Wellington, UT 84542**  
**Phone: (435) 636-8101 Fax: (435) 637-5696**  
**E-Mail: SEOPLLC@EMERYTELCOM.NET**

"24 hours a day, 7 days a week"


September 29, 2015

Robert Ramstetter

Re: Whiting Petroleum Corporation  
Tully Well: Fencing, Materials, and Seed

Mr. Ramstetter is in receipt of the fencing and materials as attested to by his signature below.

Scamp Excavation has the seed mix, will cross rip the field, and will seed when Mr. Ramstetter agrees on the date.

A handwritten signature in dark ink, appearing to read "Robert Ramstetter", is written over a horizontal line.

Robert Ramstetter